

# Farm Dairy Effluent Pond Design and Construction

Version 2, March 2013



## Preface

This Practice Note has an intentional engineering focus on the design and construction of Farm Dairy Effluent (FDE) ponds as other aspects of the effluent management system are covered by other industry documents.

While this Practice Note specifically refers to FDE, there are other agricultural industries that produce effluent that may benefit from it.

The costs of commercially supplied fertilisers are high and likely to climb higher. This Practice Note introduces a commercial incentive for farmers to apply effluent to pasture in a way that assists with nutrient retention in the root zone and provides a partial substitution for commercial fertiliser. Storage enables farmers to target when FDE is applied and thereby gain benefit from recycling nutrients back to the farm.

### KEY POINTS

- This Practice Note has been produced to provide a good-practice industry standard for designing and constructing FDE ponds.
- Poor-quality ponds adversely affect the environment.
- Stored effluent is a valuable source of nutrients for plants and can offset fertiliser costs.
- The farmer/owner is ultimately liable for breaches of the Resource Management Act (RMA) and the Building Act (BA) and should seek and be able to rely on sound professional advice to ensure compliance.

## Practice Note Development

The Institution of Professional Engineers (IPENZ), with support from principal sponsors DairyNZ, has brought together a group of professionals from civil, geotechnical, agricultural, and environmental engineering backgrounds to develop a Practice Note on the design and construction of FDE ponds.

Formation of the group in early 2011 was initiated by:

- Growing concerns expressed by both IPENZ Members and farmers on the poor quality of FDE ponds being designed and constructed in New Zealand
- The impact that poor-quality FDE ponds are having on the environment
- Identification that regulatory requirements under the *Building Code* are not being understood by some authorities
- Lack of clear definition around who may sign off for FDE ponds and structures
- Recognition by IPENZ and DairyNZ for the need to set industry standards for FDE pond design and construction.

The IPENZ Engineering Practice Advisory Committee (EPAC) has given the authors the task of preparing a document that reflects a national perspective to be adopted by the dairy engineering industry. The Practice Note has been prepared in accordance with standard IPENZ Practice Note procedures. This includes reporting on progress to EPAC, peer review and general Membership review. This review and reporting process ensures the delivery of a robust, good-practice, technical document.

The Practice Note's intent is to provide good-practice guidelines for professional engineers and other technical specialists who are involved in the design and construction of FDE ponds. This Practice Note is also intended to be a good-practice reference source for Regional Council (RC) and Local Authority (LA) staff, agriculturists, product suppliers, contractors, and others involved in the FDE pond industry. In addition, the authors have reviewed New Zealand legislation and regulations and sought to interpret these as they relate to FDE ponds and structures.

To maintain an up to date and industry relevant document, Practice Note 21 underwent a review in late 2012 and three new parts were added: clay liners, geomembrane (synthetic liner) selection, and ponds and tanks on peat.

DairyNZ continues to raise the profile of effluent management in New Zealand. Their *FDE Design Code of Practice* and the *FDE Design Standards* provide generic guidance for the design and development of effluent management systems. This distinctly separate Practice Note complements these documents.

In designing FDE pond systems, several other documents may need to be referred to and the references section links to a number of relevant publications.

While the authors have made every effort to present a carefully considered Practice Note based on their own professional practice, as well as consultation with the wider industry, they accept that what constitutes good practice may alter over time following changes in knowledge, technology, and legislation. They also acknowledge that differing interpretations of relevant legislation and regulations are possible and that each practitioner will need to confirm with the relevant authorities as to their requirements.

# Contents

PREFACE.....	i
PRACTICE NOTE DEVELOPMENT .....	ii
GLOSSARY .....	viii

## Part 1: Design and Construction Principles

<b>1.0 INTRODUCTION</b>	3
1.1 FDE MANAGEMENT .....	3
1.2 FDE PONDS .....	3
1.3 TYPES OF FDE PONDS .....	3
<b>2.0 BACKGROUND</b>	4
2.1 WHAT IS GOOD PRACTICE? .....	4
2.2 WHY ARE FDE PONDS NECESSARY? .....	4
2.3 ROLES AND RESPONSIBILITIES .....	5
<b>3.0 LEGISLATION AND REGULATIONS</b>	6
3.1 INTRODUCTION .....	6
3.2 HEALTH AND SAFETY IN EMPLOYMENT ACT .....	6
3.3 RESOURCE MANAGEMENT ACT .....	9
3.4 BUILDING ACT .....	10
3.5 HISTORIC PLACES ACT .....	16
3.6 REGULATORY REQUIREMENTS OVERVIEW .....	17
<b>4.0 SITE INVESTIGATIONS</b>	20
4.1 INVESTIGATION PURPOSE: AN OVERVIEW .....	20
4.2 SOIL PROPERTIES .....	20
4.3 SITING A NEW POND .....	21
4.4 FIELD INVESTIGATION STEPS .....	23
<b>5.0 DESIGN</b>	25
5.1 INTRODUCTION .....	25
5.2 TYPES OF PONDS .....	25
5.3 EFFLUENT TREATMENT DESIGN .....	25
5.4 SOLIDS MANAGEMENT .....	26
5.5 EFFLUENT IRRIGATION .....	27
5.6 POND SIZING .....	29
5.7 POND GEOMETRIC DESIGN .....	31
5.8 SOLIDS MANAGEMENT DESIGN .....	33
5.9 LINERS .....	34
5.10 POND PERFORMANCE CONSIDERATIONS .....	35

<b>6.0</b>	<b>CONSTRUCTION</b>	37
6.1	INTRODUCTION .....	37
6.2	DRAWINGS AND SPECIFICATIONS .....	37
6.3	THE SUPERVISING ENGINEER'S ROLE .....	37
6.4	EFFECTS OF WORKS ON OTHERS .....	38
6.5	UNDERGROUND SERVICES .....	38
6.6	DRAINAGE CONTROL .....	38
6.7	CONSTRUCTION EQUIPMENT .....	39
6.8	COMPACTION .....	40
6.9	EXPOSED BATTERS .....	42
6.10	FENCES AND GATES .....	43
6.11	PRACTICAL COMPLETION AND DEFECTS LIABILITY CERTIFICATES .....	43
<b>7.0</b>	<b>CERTIFICATION</b>	44
7.1	INTRODUCTION .....	44
7.2	CERTIFICATION UNDER THE RMA BY REGIONAL COUNCILS .....	45
7.3	CERTIFICATION UNDER THE BUILDING ACT .....	45
7.4	CERTIFICATION BY CONSTRUCTION CONTRACTOR .....	46
7.5	CERTIFICATION FOR POND DESIGN AND CONSTRUCTION REVIEW .....	47
<b>8.0</b>	<b>OPERATION AND MAINTENANCE</b>	49
8.1	INTRODUCTION .....	49
8.2	AS-BUILT PLANS .....	49
8.3	OPERATION MANUAL .....	49
8.4	INSPECTIONS .....	49
8.5	POND MONITORING .....	50
8.6	LEAKAGE DETECTION AND RESPONSE .....	50
8.7	DROP TEST .....	51
8.8	SYSTEM OPERATION .....	51
8.9	EXISTING FDE PONDS .....	52
<b>9.0</b>	<b>FORMS OF CONTRACT</b>	53
9.1	SCOPE OF WORK AND PRACTITIONER ENGAGEMENT .....	53
9.2	ETHICS .....	53
9.3	CONTRACTOR SELECTION .....	54
9.4	CONTRACTOR ENGAGEMENT .....	55
9.5	NZS 4431 (CODE OF PRACTICE FOR EARTH FILL FOR RESIDENTIAL DEVELOPMENT) .....	56

## PART 2: CLAY LINERS FOR PONDS

<b>1.0</b>	<b>INTRODUCTION</b>	59
1.1	INTRODUCTION .....	59
<b>2.0</b>	<b>DESIGN CALCULATIONS</b>	60
2.1	HYDRAULIC CONDUCTIVITY.....	60
2.2	SEEPAGE CALCULATION .....	60
2.3	FLOW AND SEEPAGE WITH VARYING HYDRAULIC CONDUCTIVITY .....	61
<b>3.0</b>	<b>INVESTIGATION AND TESTING</b>	63
3.1	INVESTIGATION .....	63
3.2	LABORATORY TESTING.....	63
<b>4.0</b>	<b>LINER DESIGN</b>	71
4.1	SLOPE ANGLES.....	71
4.2	THICKNESS OF LINER .....	72
4.3	<i>IN SITU</i> CLAY PONDS .....	72
4.4	CLAY LINER PROTECTION.....	72
4.5	UNDER DRAINAGE.....	73
4.6	SOIL TREATMENT USING BENTONITE .....	74
<b>5.0</b>	<b>CONSTRUCTION METHODOLOGY</b>	76
5.1	COMPACTION EQUIPMENT .....	76
5.2	CONTROL OF WATER .....	77
<b>6.0</b>	<b>QUALITY ASSURANCE</b>	78
6.1	COMPACTION TRIAL.....	78
6.2	SITE TESTING .....	78
6.3	SEEPAGE TESTING.....	79
6.4	RECORDS AND SIGN-OFFS .....	80

## **PART 3: GEOMEMBRANE (SYNTHETIC LINER) SELECTION**

<b>1.0</b>	<b>INTRODUCTION</b>	85
1.1	INTRODUCTION .....	85
<b>2.0</b>	<b>GEOMEMBRANES</b>	87
2.1	TYPES OF GEOMEMBRANES .....	87
2.2	GEOSYNTHETIC RESEARCH INSTITUTE (GRI) SPECIFICATIONS .....	87
2.3	GEOMEMBRANE SELECTION BY ATTRIBUTES .....	90
<b>3.0</b>	<b>INSTALLATION</b>	92
3.1	EXPERIENCED INSTALLERS .....	92
3.2	SUBGRADE PREPARATION .....	92
3.3	ANCHOR TRENCHES .....	92
3.4	GEOSYNTHETIC CLAY LINER (GCL).....	93
3.5	SAFETY.....	93
3.6	GROUNDWATER AND DRAINAGE .....	93
3.7	GAS VENTING .....	93
3.8	DRAINAGE AND VENTING SYSTEM DESIGN.....	94
3.9	PENETRATIONS.....	94
3.10	STIRRERS.....	94
3.11	QUALITY ASSURANCE AND WARRANTIES .....	95
<b>4.0</b>	<b>SUMMARY</b>	96

## **PART 4: PONDS AND TANKS ON PEAT**

<b>1.0</b>	<b>INTRODUCTION</b>	99
1.1	PURPOSE .....	99
1.2	WHAT IS PEAT? .....	100
1.3	WHY IS PEAT A CHALLENGE? .....	101
<b>2.0</b>	<b>ENGINEERING PROPERTIES OF PEAT</b>	103
2.1	ENGINEERING ISSUES WITH CONSTRUCTION ON PEAT .....	103
2.2	BEARING CAPACITY FAILURE .....	103
2.3	EXCESSIVE SETTLEMENT.....	104
2.4	SHALLOW GROUNDWATER TABLE .....	105
2.5	GAS COLLECTION .....	106
<b>3.0</b>	<b>SETTLEMENT</b>	107
3.1	MANAGING SETTLEMENT .....	107
3.2	POND BANK SETTLEMENT.....	108
3.3	TANK SETTLEMENT.....	109
3.4	SETTLEMENT DURING USE.....	109

<b>4.0</b>	<b>GROUND INVESTIGATION, DEPTHS AND METHODS</b>	110
4.1	SCOPE OF INVESTIGATION .....	110
4.2	DEPTH OF INVESTIGATION .....	110
4.3	METHODS.....	111
<b>5.0</b>	<b>DESIGN PROCESS AND CONSIDERATIONS</b>	114
5.1	COST AND RISK ASSESSMENT.....	114
5.2	DESIGN PROCESS STEPS .....	115
<b>6.0</b>	<b>SUMMARY</b>	116
<b>7.0</b>	<b>ACKNOWLEDGEMENTS</b>	117

## REFERENCES

<b>REFERENCES</b>	121
OVERVIEW.....	121
PART 1: DESIGN AND CONSTRUCTION PRINCIPLES.....	121
PART 2: CLAY LINERS FOR PONDS .....	125
PART 3: GEOMEMBRANE (SYNTHETIC LINER) SELECTION.....	125

## APPENDICES

APPENDIX A – IPENZ SHORT FORM AGREEMENT .....	129
APPENDIX B1 – FORM OF PRODUCER STATEMENT FOR: DESIGN OF FARM DAIRY EFFLUENT PONDS .....	131
APPENDIX B2 – FORM OF PRODUCER STATEMENT FOR: CONSTRUCTION REVIEW OF FARM DAIRY EFFLUENT PONDS.....	132
APPENDIX B3 – FORM OF PRODUCER STATEMENT FOR: CONSTRUCTION OF FARM DAIRY EFFLUENT PONDS .....	133
APPENDIX C – REGULATORY CHECKLIST.....	134
APPENDIX D – POND CERTIFICATION CHECKLIST.....	138

# Glossary

<b>ATSM</b>	American Society on Testing and Materials	<b>IPENZ</b>	Institution of Professional Engineers New Zealand
<b>BA</b>	Building Act 2004	<b>LA</b>	Local Authority
<b>BCA</b>	Building Consent Authority	<b>LDS</b>	Leakage Detection System
<b>BOD</b>	Biochemical Oxygen Demand (a measure of degradable organic matter content)	<b>LL</b>	Liquid Limit
<b>CCL</b>	Compacted Clay Liner	<b>LS</b>	Linear Shrinkage
<b>CPT</b>	Cone Penetrometer Testing	<b>MC</b>	Moisture Content
<b>DC</b>	District Council	<b>MDD</b>	Maximum Dry Density (soil)
<b>DD</b>	Dry Density	<b>MBIE</b>	Ministry of Business, Innovation and Employment
<b>PN</b>	Practice Note	<b>NDM</b>	Nuclear Density Meter
<b>CPEng</b>	Chartered Professional Engineer	<b>NZHPT</b>	New Zealand Historic Places Trust
<b>DESC</b>	Dairy Effluent Storage Calculator (Massey University and Horizons Regional Council)	<b>NZS</b>	New Zealand Standard(s)
<b>DD/WC</b>	Dry Density/Water Content	<b>OMC</b>	Optimum Moisture (water) Content (soil)
<b>EPDM</b>	Ethylene Propylene Diene Monomer (Rubber)	<b>PL</b>	Plastic Limit
<b>ETPract</b>	Engineering Technology Practitioner	<b>PI</b>	Plasticity Index
<b>FDE</b>	Farm Dairy Effluent	<b>Principal</b>	Client or farm owner
<b>Freeboard</b>	Volume (or height) above maximum effluent design level in pond	<b>PS</b>	Producer statement
<b>GCL</b>	Geosynthetic Clay Liner	<b>QA</b>	Quality Assurance
<b>GRI</b>	Geosynthetic Research Institute	<b>RA</b>	Regional Authority
<b>HDPE</b>	High-Density Polyethylene (Plastic)	<b>RC</b>	Regional Council
<b>HSE</b>	Health and Safety in Employment Act 1992	<b>RMA</b>	Resource Management Act 1991
<b>IANZ</b>	International Accreditation New Zealand	<b>SQP</b>	Suitably Qualified Person
		<b>SV</b>	Shear Vane
		<b>TA</b>	Territorial Authority
		<b>UV</b>	Ultra Violet
		<b>WC</b>	Water Content

# PART 1

## **Design and Construction Principles**



# 1.0 Introduction

## 1.1 FDE MANAGEMENT

Farm Dairy Effluent is the collective term for dairy cow urine, faeces, and wash-down water. It varies in volume and composition and is a reflection of many factors, including the number of cows milked, feed type, shed practices, wash-down methods, weather, and the time of year.

During the milking process it is estimated that around 10 per cent of a cow's daily urine and faeces is excreted in the dairy shed or yard. The FDE may also include material collected from laneways, feed pads, wintering pads, silage stacks, and stock underpasses. Generally, the FDE captured from these sources is retained in a temporary containment facility and irrigated to pasture. However, there are times when soil conditions are not suitable for FDE irrigation and its deferred storage is required.

## 1.2 FDE PONDS

Farm Dairy Effluent ponds are primarily constructed to provide temporary deferred storage and treatment for effluent generated from dairy milking sheds. They are also used to store and treat leachate and effluent generated from silage stacks, wintering pads, barns, and farm infrastructure such as lanes and stock underpasses.

The purpose of an FDE pond is to provide temporary storage and treatment of effluent during periods when soil conditions are not suitable for effluent irrigation. Scientific research on the environmental effects of effluent irrigation highlights the importance of effluent storage as contingency during these periods. Effluent storage is particularly important in wetter regions of New Zealand where there are extensive mole and tile drainage networks, high water tables, and higher drainage-risk soil types where nutrient leaching to groundwater or waterways could occur.

Agricultural research has identified the value in providing increased on-farm effluent storage. However, a lack of national guidance has seen the development of FDE ponds which are inappropriately designed, sited, and constructed.

This Practice Note highlights the critical elements of good FDE pond design and construction. It also considers FDE pond operation and maintenance, explores the definition of ponds, tanks, and "small" dams, and outlines the Building and Resource Consents required for their construction.

## 1.3 TYPES OF FDE PONDS

Farm Dairy Effluent ponds range in size, shape, construction materials, and capacity. Earthen embankment ponds are formed from compacted earth material with a Compacted Clay Liner (CCL) or geomembranes (also known as synthetic liners), while concrete ponds may be formed from a series of concrete cast *in situ* or precast panels or sprayed (Shotcrete) concrete. There are also a number of other FDE containment structures such as proprietary concrete and synthetic lined tanks.

# 2.0 Background

## 2.1 WHAT IS GOOD PRACTICE?

Good practice may be defined as “a level of effort that seeks to meet industry expectations and typically exceeds minimum compliance requirements”.

To meet the key operational good-practice outcomes, FDE designs must:

- Meet RC and BA rules and consent conditions
- Include a pond liner of a sufficiently low seepage rate to minimise adverse environmental effects, including infiltration to groundwater
- Allow for ongoing operation and maintenance and be appropriately sized for the volume of on-site effluent
- Meet its intended use and life span’s durability and serviceability requirements
- Provide a clear documentation trail of accountability for the respective suppliers and the components they provided (that is, equipment and products) incorporated into the works.

## 2.2 WHY ARE FDE PONDS NECESSARY?

### 2.2.1 REGIONAL COUNCIL REQUIREMENTS

Regional councils and unitary authorities impose a range of regulatory requirements on the discharge of effluent (to air, land, or water). The purpose of these regulations is to avoid, remedy, and mitigate the adverse effects on the environment.

The requirement for FDE ponds is driven by most councils under the Resource Management Act 1991 (RMA). Aspects of FDE pond construction are also regulated by RCs and District Councils (DCs) under both the RMA and the BA. There is variability in the regulatory requirements relating to FDE ponds throughout New Zealand. This creates uncertainty as to standards that are to be applied.

### 2.2.2 ENVIRONMENTAL PROTECTION

Using an FDE pond to process and store effluent enables farmers to manage the effluent’s discharge. The irrigation method used determines the rate, depth, and evenness of application and therefore the likelihood of environmental contamination; however, this is outside the scope of this Practice Note.

Regional Councils advocate that good practice is to discharge effluent to land when soil conditions are appropriate. Appropriate conditions are those where soil moisture is at a sufficiently low level for the contaminants in the effluent to:

- Be utilised by the soil’s biological system
- Not move to surface water through overland or subsurface flow
- Not infiltrate to groundwater
- Any such ponding or run-off has the potential to have adverse effects on the environment, such as excessive nutrients and pathogens entering groundwater and surface waterways.

All FDE structures including ponds, sumps, tanks, dams, as well as the pipes or channels between them must provide a contained system that prevents FDE leakage.

## 2.3 ROLES AND RESPONSIBILITIES

In understanding the roles and responsibilities associated with FDE pond design and construction, it is important to identify the various parties and their roles. Table 2.1 summarises these.

<b>Client/farmer (or principal)</b>	The principal is the person who meets the costs, makes the decisions, and in most cases is the pond owner. They are responsible for ensuring their pond is designed, constructed, and operated in a safe and legally compliant manner.
<b>Regional Council</b>	The RC has the jurisdiction to determine the rules for FDE pond construction and operation under the RMA. This includes setting the pond liner's allowable permeability, the pond's volume, and its separation from features such as waterways. It is also responsible for administering BA requirements where a dam exists (including all aspects of the dam structure's physical integrity and mechanical safety).
<b>District Council</b>	The DC has the jurisdiction to dictate the rules relating to the FDE pond's amenity aspects under the RMA. District plans may specify separation requirements (from neighbours, roads, public amenities etc), either as conditions of a Permitted Activity or as an indication of a requirement for a Resource Consent. The DC is also responsible for administering the BA and its related requirements for structures other than dams.
<b>Practitioners</b>	Effluent containment engineers and related specialists with experience and expertise in the field of effluent structures design and construction are a valuable resource in designing and establishing new ponds or modifying existing ponds. While they provide advice to the principal, at the principal's invitation and discretion, they have the important additional professional responsibility to ensure their advice meets good-practice standards. The principal and the RC will both depend on the integrity of this advice.
<b>Contractors</b>	Contractors take instruction from an engineering practitioner, and also a principal when involved, to undertake earthworks and co-ordinate with equipment and service suppliers to construct the pond.
<b>Equipment and service suppliers</b>	These are suppliers of irrigation equipment, pond excavation, suppliers and installers of liners, pumps, and machinery.

Table 2.1: Roles and Responsibilities

# 3.0 Legislation and Regulations

## 3.1 INTRODUCTION

This section sets out the legislation and regulations that must be considered when designing and constructing an FDE pond. While a number of the statutes and regulations relate to design, others simply relate to the presence of a pond or tank.

The Resource Consent requirements for FDE ponds in New Zealand depend on which RC, DC, or unitary authority the FDE pond is located within. These organisations are also known as Building Consent Authorities (BCAs).

The Building Consent requirements required by the BA are intended to be consistently applied across the country. Even where consent is not needed there is still a requirement to adhere to good design principles and construction techniques. The *Building Code* performance requirements and Permitted Activity standards in regional and district plans must be met and adverse effects on the environment must be minimised.

## 3.2 HEALTH AND SAFETY IN EMPLOYMENT ACT

The Health and Safety in Employment Act 1992 (HSE Act) is about the prevention of harm to persons associated with work. To do this effectively then workplace hazards have to be identified and controlled effectively. There are duties under the Act on a range of people at work, including designers, suppliers of plant, principals to contracts, and employers and employees.

HSE requirements will generally relate more to a containment facilities' on-going operation and its owners responsibilities, rather than their initial construction, or a facility's engineering or construction components.

However, in-ground tanks and ponds need to be specifically designed to address the hazards that they pose, and in particular systems dealing with FDE which will require a higher standard of 'safety design' than for instance systems dealing with clean water.

The employer, who will normally be the containment facility owner, is responsible for protecting people from mishaps on their worksite. The HSE Act gives the Labour Group within the Ministry of Business, Innovation and Employment (MBIE), a range of powers to respond to improperly managed hazards.

### 3.2.1 ELIMINATION, ISOLATION OR MINIMISATION OF HAZARDS

The HSE Act requires that hazards in the workplace are identified and that all practicable steps are taken to control them through using a top down hierarchy of control as follows:

- Significant hazards (i.e. the hazards that have the potential to cause serious harm or death) must have all practicable steps taken to eliminate the hazard (removed completely).
- Where hazards cannot be eliminated, then all practicable steps must be taken to isolate the hazard (physically separated).
- Only if there are no practicable means of elimination or isolation available is it acceptable to minimise the hazard (protect employees form harm).

This hierarchy of control process for a new FDE system (including ponds and associated plant), would include the on-going monitoring and assessment of hazards identified during each and every phase, from investigation and design, through construction, to its operation and maintenance.

Both the designer and the construction supervising engineer have some responsibility for identifying potential safety issues as part of their design and supervision roles, specifically to eliminate, isolate or minimise possible hazard risks for items that comprise, or are used, or encountered in the workplace.

### **3.2.2 FDE PONDS HAZARD IDENTIFICATION**

Farm Dairy Effluent containment facilities (ponds and tanks) can present two types of significant hazard. First, an effluent pond may fail causing the released effluent to harm people and the environment. Second, a person, whether an employee or not, may involuntarily enter a containment facility and suffer harm.

Containment failure hazards are best addressed by farm owners ensuring design and construction is undertaken with competent advice. It is noted that meeting BA requirements may partly assist with meeting these and the HSE requirements, but not all HSE requirements can be satisfied solely by complying with the BA.

A feature of the application of the HSE Act to FDE containment facilities is that no permit is required to operate, so there is no confirmation of compliance before any mishap. However, a mishap can trigger an investigation, which can result in punitive action if HSE requirements are found to have not been met.

Should there be an accident involving such a system, then MBIE would be looking at the design of the pond and related systems ensuring that the HSE Act, and attendant regulations regarding the duties of designers and suppliers, were being met using “all practicable steps” available. So this could include considering that although a structure is built ‘safely’, it still needs to be operated with safe practices or protocols.

### 3.2.3 HAZARD MITIGATION

Regardless of how large the pond is, or the type of lining, it is strongly recommended that all ponds and other FDE storage facilities have the following Health and Safety related features designed and integrated into their construction:

HAZARD MITIGATION AROUND FDE PONDS	
Fencing	Permanent and secure fencing to prevent stock and children from accessing FDE pond areas
Gates	Lockable access gates
Escape ladders	Permanent ladders, or alternative means of escape from ponds
Anchor Points	Anchor points to attach floating pontoons to (if used) to improve stability
Signage	Hazards on site clearly shown

In addition there needs to be direct communication to farm staff, contractors and visitors about hazards on the farm. Farm policies and forms can be developed from the DairyNZ Health and Safety Compliance Toolkit.

[www.compliancetoolkit.co.nz/index.asp?pageID=2145868742](http://www.compliancetoolkit.co.nz/index.asp?pageID=2145868742)

### 3.2.4 FENCING FDE FACILITIES

Fencing FDE containment facilities is required under the farm's health and safety policy. The farm owner should decide what level of fencing is required based on their HSE risk assessment.

The appropriate type and extent of fencing required for each farm will vary and be dependent on the hazard risks identified at the site. Where a site contains hazards, which might attract the unauthorized or unexpected entry of the public, children, or wandering animals (both small and large), then the hazard needs to be enclosed to restrict access. At the very least, a five wire fence, preferably with netting and an electric fence 'hot wire' should be constructed. In some locations a higher fence such as deer fencing will be appropriate. Lockable gates and hazard warning signage is strongly recommended.

The Fencing of Swimming Pools Act 1987 requirements do not apply to FDE storage ponds as the ponds are not intended for swimming.

## 3.3 RESOURCE MANAGEMENT ACT

### 3.3.1 FDE AND THE RESOURCE MANAGEMENT ACT

Regional Councils are responsible, under the RMA, for FDE ponds. Table 3.1 outlines the relevant RMA sections.

<b>Section 13</b>	This section places restrictions on certain uses of riverbeds and lakebeds, including dam constructions in riverbeds, or even ephemeral watercourses. In practice, most FDE ponds do not involve damming existing watercourses. This is because they are essentially pits in the ground with no contributing catchment; in these cases Resource Consents for water diversion are unlikely to be required.
<b>Section 14</b>	This section outlines the restrictions relating to water. No person may take, use, dam, or divert water without appropriate plan or consent provision. However, FDE ponds built out of and away from natural watercourses will not involve damming water in the sense intended by the RMA.
<b>Section 15</b>	This section states that no person may discharge any contaminant into water, or onto land, in circumstances which may result in contaminants entering water; unless the discharge is expressly allowed by a rule in a regional plan or Resource Consent.
<b>Note:</b> Agricultural effluent ponds are also administered by some RCs under section 9 of the RMA (restrictions on use of land).	

Table 3.1: FDE and the RMA

The term “dam” as used in the RMA, refers to “the action of causing confinement of otherwise unconfined natural water” (verb). This is different from the use of the term “dam” in the BA which refers to “a physical structure” (noun).

Regional councils regulate certain aspects of FDE pond construction and operation through their plans and/or consent process. The primary purpose of this is to protect surface water and groundwater from potential of FDE contamination.



2,000m<sup>3</sup> precast concrete tank.

### 3.3.2 REGIONAL COUNCIL REQUIREMENTS FOR FDE PONDS

There is wide variation between regional plan specifications for FDE ponds. Councils often consider the following in their internal guidance documents:

- A pond's volumetric capacity and slope of batters
- The pond liner's maximum seepage rate at full hydraulic loading
- The pond's spatial separation from bores, wetlands, waterways, and waahi tapu
- Design and construction sign-off protocols.

Some RCs require land use consents for ponds. Environment Southland, for example, requires a land use consent for every FDE containment structure with a capacity >22.5m<sup>3</sup>. This includes ponds, tanks, and sumps irrespective of whether they need a Building Consent.

### 3.3.3 REGIONAL COUNCIL RESPONSIBILITIES FOR FDE PONDS

The RMA and regional plan requirements and specifications vary in relation to directing FDE pond management and construction.

Much of the RC guidance concerns the impact of FDE pond discharges on the environment. The RC provisions are only legally binding if they are incorporated into a consent and have been accepted by the parties involved. This differs to requirements in a regional plan which has been through a public process prior to being adopted, and is therefore legally binding.

The Regulatory Checklist in Appendix C indicates the rule variation between RCs for effluent management at the time the rules became operative.

### 3.3.4 DISTRICT COUNCIL RESPONSIBILITIES

Section 31 of the RMA says Territorial Authorities (District Councils) are responsible for controlling the actual or potential effects of "the use...of land".

District councils generally view FDE pond construction and operation as a Permitted Activity. This permission can be given specifically or by default. Separation distances from roads, houses, or property boundaries are often specified. These may be greater than the separations required by RCs. In some districts (for example, Horowhenua and Queenstown Lakes District) there are additional limitations on earthworks where they may compromise visual landscape values.

Under section 9 of the RMA, any land use is permitted unless stated otherwise in a regional or district plan. Care is needed to ensure FDE ponds are allowed (that is, a Permitted Activity) in the zones involved, so the regional and district plan should always be consulted for certainty.

The plans may also include performance standards that must be maintained.

## 3.4 BUILDING ACT

### 3.4.1 OVERVIEW

Farm Dairy Effluent can be contained in a variety of structures including tanks, pits, dams, and ponds. It is therefore important for the FDE system designer to have some understanding of the BA as it relates to both Building Consent and *Building Code* requirements.

The BA provides a process for regulating the design and construction of structures and is generally managed by DCs. However, the requirements for dams are managed by the BCA.

The BCA does not require Building Consents in all cases. For containment structures which are considered to be dams under the BA, the proposed Building Amendment Act (No 4) 2011, Schedule 1, Part 1, section 22 says “Building work in connection with a dam that is not a large dam” is exempt from a Building Consent. In general, FDE ponds are covered by this provision and do not generally require Building Consents.

However, two important BA sections need to be considered when structures (including ponds and tanks) are constructed or altered.

Section 7 states that building work includes “site work” and “design work relating to building work”. Therefore, in general terms no site work can be started until a Building Consent (if not exempted) has been approved for the proposed construction.

Section 17 states “All building work must comply with the *Building Code* to the extent required by this Act, whether or not a Building Consent is required in respect of that building work”. Therefore, regardless of the DC and RC requirement for (or not for) Building Consents, there is still a requirement for structures to meet the performance requirements of the *Building Code*.

When this Practice Note was being prepared it became clear that some building regulations are intended to relate to FDE buildings and structures. However, this is not as clearly expressed and understood as it could be. As a result, legislation and the resulting building regulations are not being universally applied. Some DCs are choosing to enforce requirements to “the letter of the law” while other councils seem less rigid in their interpretation of the regulatory requirements.

Clarification should therefore be sought at an early stage in a project’s development as to the consents required from the relevant statutory authority.

### 3.4.2 BUILDING CONSENTS FOR TANKS AND PONDS

While a tank and pool are referenced in the *Building Code*, they are not defined. While no explicit definition is made of a “tank” in the BA, it is generally accepted that some effluent structures, for example concrete-lined ponds, should be classified as tanks. Tanks in the BA context may also refer to pools, sumps, some ponds, and some other containment structures. Presently Building Consent requirements under the BA for new tanks and alterations to existing tanks attract varied interpretations around the country.

A definition for the elements associated with FDE design has not been agreed, so for the purpose of this Practice Note the following definitions for tanks and ponds associated with agricultural effluent are used. It should be noted these definitions do not have legal status.

**Tank (effluent):** is constructed of man-made materials such as concrete, steel, plastic, or milled timber, or other products; its purpose is to retain and store or collect fluids (including sludge/effluent). The tank materials are used as the structural elements to retain the fluid. A tank may or may not have a lid and has essentially vertical sides.

**Pond (effluent):** is either constructed of compacted soil or rock embankments, or excavated into the existing ground – or a combination of both these methods – to provide a containment facility for fluid (including sludge/effluent). Ponds may have a liner installed to seal the pond from leakage; however, the earthen materials are used to provide the structural elements for confinement. The internal batters are less than 45 degrees and do not have lids.

### 3.4.3 BUILDING CONSENT EXEMPTIONS

Using the definition of effluent tanks in section 3.3.2, the following guidance is given about qualifying for a Building Consent exemption. The Building Amendment Bill (No 4), Schedule 1, proposes a number of exemptions.

Under section 23(g) of that Bill, an exemption for constructing or altering a tank or pool is based on its capacity as described in Table 3.2 below.

A Building Consent is not required for the following work:

**Tanks and pools (excluding swimming pools)**

“Building work in connection with a tank or pool and any structure in support of the tank or pool (except a swimming pool as defined in section 2 of the Fencing of Swimming Pools Act 1987), including any tank or pool that is part of any other building for which a building consent is required, that—

(g) does not exceed 35,000 litres capacity and is supported directly by ground.”

Table 3.2: Building Consent Exemption – Excerpt from Section 23(g)

This means all tanks <35 m<sup>3</sup> (35,000 litres) built on or in the ground do not require a Building Consent, but all tanks >35 m<sup>3</sup> do.

However, an exemption from a Building Consent for tanks >35 m<sup>3</sup> is possible under section 2 as described in Table 3.3 below.

**Territorial and regional authority discretionary exemptions**

“Any building work in respect of which the territorial authority or regional authority considers that a building consent is not necessary for the purposes of this Act because the authority considers that—

(a) the completed building work is likely to comply with the building code; or

(b) if the completed building work does not comply with the building code, it is unlikely to endanger people or any building, whether on the same land or on other property.”

Table 3.3: Building Consent Exemption – Schedule 1, Part 1 Exempted Building Work, Section 2

This exemption allows a BCA to exempt proposed building work in the circumstances specified. The decision to allow any exemption is at the council’s discretion. It is based on the council’s own assessment of the risk of building work not being carried out according to the *Building Code*, or of endangering people or property.

There are a number of proprietary tank suppliers of tanks >35 m<sup>3</sup> on the market and the manufacturers or suppliers of these can apply under section 2 of the Building Amendment Bill (No 4) Schedule 1 for their product to be specifically exempt. In these cases, the Design Producer Statements (PS1) would need to be provided by the manufacturer. If Building Consent is required, then it would follow that a Producer Statement – Construction Review (PS4) would also be required. These Producer Statements can only be issued by a Chartered Professional Engineer (CPEng).

### 3.4.4 DAM REQUIREMENTS

With respect to the BA, a dam is the physical structure that can hold back water above ground level. Table 3.4 below provides the legal definition of a dam. This definition is different from the definition of a pond, which describes the contained liquid. A pond can exist without a dam, in which case the maximum water level would be below ground level. As soon as the water level rises above the ground surface, the containment structure is described as a dam. The dam is not the whole containment structure, but only the physical barrier where the water level exists above ground level.

“A dam —

(a) means an artificial barrier, and its appurtenant structures, that—

- (i) is constructed to hold back water or other fluid under constant pressure so as to form a reservoir; and
- (ii) is used for the storage, control, or diversion of water or other fluid; and

(b) includes—

- (i) a flood control dam; and
- (ii) a natural feature that has been significantly modified to function as a dam.”

Table 3.4: Dam Definition, Building Act 2004, section 7

Large dams are those which retain >3 m depth and hold >20,000 m<sup>3</sup> of fluid. The Building and Housing section of MBIE propose that this volume threshold will increase. A legislative amendment is proposed that will give Regional Authorities (RAs) responsibility for all dams in their region. Given that it would be rare for an effluent pond to meet the large dam criteria, the additional requirements of these ponds are not further explored in this Practice Note.

Many ponds are essentially pits in the ground, with the placement and compaction of the cut material forming an embankment around the pond perimeter. When the pond is filled up to, or lower than, the lowest elevation of the surrounding ground, no damming will have occurred. However, if the fluid level rises above the lowest level of the surrounding ground, so the surrounding wall provides a barrier, the surrounding wall will be functioning as a dam.

Depending on the particular circumstances, some pond-related structures, such as jetties and floating pon-toon structures, may meet the “appurtenant structure” definition described in the BA. In these cases, they will be considered to be part of a dam. They are also likely to be considered “building work” so must comply with the *Building Code*.

In terms of the BA, dam management is delegated to RCs, rather than DCs. The RCs’ concern focuses on the potential for the dam structure to fail; and the consequences if they do fail.

Table 3.5 below shows FDE ponds can fall into one of three categories when determining if they are dams or not. They can be generally described as either “not a dam”, a “dam”, or a “large dam.

<b>Not a dam</b>	If a pond is constructed by excavating a pit in the ground, and does not have an embankment constructed to allow the fluid to rise to a greater height* than that of the surrounding land, then the pond is not confined. It is therefore not a dam.
<b>Dam</b>	If the fluid in the pond is confined by an earthen embankment or any other structure in such a way that the fluid in it may rise to a maximum height* of 3 m or the holding capacity of the pond is <20,000 m <sup>3</sup> , then the pond is confined and is therefore defined by the BA as a dam.
<b>Large dam</b>	If the fluid in the pond is confined by an earthen embankment or any other structure in such a way that the fluid in it may rise to a height* >3 m and the volumetric capacity of the pond exceeds 20,000 m <sup>3</sup> , then the pond is classified as a large dam.  (Note: the definition of a large dam is due to change following the passing of a BA amendment to “large dam means a dam that has a height of 4 or more metres, or holds 20,000 or more cubic metres of water or other fluid”.)
<p><b>*Height of dam</b></p> <p>“the height of a dam is the vertical distance from the top (crest) of the dam and must be measured:</p> <ul style="list-style-type: none"> <li>(a) in the case of a dam across a stream, from the natural bed of the stream at the lowest downstream outside limit of the dam; and</li> <li>(b) in the case of a dam not across a stream, from the lowest elevation at the outside limit of the dam.”</li> </ul>	

Table 3.5: Categories of FDE Ponds

The BA states that all building work carried out must comply with the Building Regulations 1992 (also known as the Building Code). Building work includes the construction and alteration of dams even though they are exempt from requiring a building consent for this work.

The Building Code sets out performance standards that building work must meet, and covers aspects such as structural stability and durability. The Building Code does not prescribe how building work should be done (ie, no detailed requirements for design and construction), but states how completed building work, and its components, must perform. This is important when considering constructing a dam, as each dam is unique to its location and environment. A dam, however, should be designed and constructed and maintained in a manner that safeguards people and property from structural failure and throughout its life continues to comply with the Building Code and have a low probability of failure. Mention is made again that the dam definition will capture some ponds and sumps.

It is also important to note that while a Building Consent may not be required for a dam, a Resource Consent may be required for the earthworks associated with its construction.

### 3.4.5 RETAINING WALLS

The BA's definition of a retaining wall is interpreted so that if a FDE pond, tank, sump or other retaining wall structure (e.g. constructed of concrete, steel or timber) is not higher than 1.5 metres and does not support any load, then it will not require a Building Consent. This decision will probably also depend on the retaining structure's construction, function, depth, and geometry.

If a retaining structure of less than 3 metres depth were to be constructed in a rural zone, then it would may be exempt from the Building Consent requirement. However, this will only be the case if the design is carried out or reviewed by a CPEng and is not required to support a load, for example, a farm vehicle or building.

These exemptions for retaining structures are detailed in Sections 20, 22 and 40 of schedule 1 of the Building Amendment Bill (No 4); refer to Table 3.6 below.

Throughout New Zealand there are a variety of council consent and enforcement requirements for containment structures. They are best placed to clarify and confirm the specific consent requirements in their areas.

<p><b>Part 1</b>  <b>Exempted building work</b>  <b>Other structures</b></p> <p>“(20) Building work in connection with a retaining wall that—  (a) retains not more than 1.5 metres depth of ground; and  (b) does not support any surcharge or any load additional to the load of that ground (for example, the load of vehicles).”</p> <p>“(22) Dams (excluding large dams)  Building work in connection with a dam that is not a large dam.”</p>
<p><b>Part 3</b></p> <p>Building work for which design is carried out or reviewed by chartered professional engineer</p> <p>“(40) Building work in connection with a retaining wall in a rural zone, if—  (a) the wall retains not more than 3 metres depth of ground; and  (b) the distance between the wall and any legal boundary or existing building is at least the height of the wall</p> <p><b>rural zone</b> means any zone or area (other than a rural residential area) that, in the district plan of the territorial authority in whose district the building work is to be undertaken, is described as a rural zone, rural resource area, or rural environment, or by words of similar meaning.</p>

Table 3.6: Retaining Structures–Building Amendment Bill (No 4) Exemptions

### 3.4.6 BUILDING CODE AND INDUSTRIAL LIQUID WASTES

Section G1 of the *Building Code* does not specifically define FDE as a hazardous material. Nor is it listed in Table 1 of section G14 as an example of industrial liquid waste.

However, the section on storage facilities (G14.3.2 of the *Building Code*) does provide some good-practice considerations when designing FDE ponds (refer to Table 3.7 below).

- “Facilities for the storage, treatment, and disposal of industrial liquid waste must be constructed—
- (a) with adequate capacity for the volume of waste and the frequency of disposal; and
  - (b) with adequate vehicle access for collection if required; and
  - (c) to avoid the likelihood of contamination of any potable water supplies in compliance with Clause G12 “Water supplies”; and
  - (d) to avoid the likelihood of contamination of soils, groundwater, and waterways except as permitted under the Resource Management Act 1991; and
  - (e) from materials that are impervious both to the waste for which disposal is required, and to water; and
  - (f) to avoid the likelihood of blockage and leakage; and
  - (g) to avoid the likelihood of foul air and gases accumulating within or entering into buildings; and
  - (h) to avoid the likelihood of unauthorised access by people; and
  - (i) to permit easy cleaning and maintenance; and
  - (j) to avoid the likelihood of damage from superimposed loads or normal ground movement; and
  - (k) if those facilities are buried underground, to resist hydrostatic uplift pressures.”

Table 3.7: *Building Code Section G14.3.2: Industrial Liquid Wastes*

These considerations pick up several issues which are covered in other design guidance Practice Notes and Standards, which are crucial for good-practice design. This guidance is available for instance for (a) pond capacity; (e) leakage and is prescribed by RCs; and (h) safety, which is covered by the Health and Safety Employment Act 1992 (HSE).

## 3.5 HISTORIC PLACES ACT

The Historic Places Act 1993 makes it unlawful to destroy, damage, or modify an archaeological site without prior authority from the New Zealand Historic Places Trust (NZHPT). This means any work that may affect an archaeological site requires an authority from the NZHPT before work begins. This may include road works, quarrying, and any other excavation activities related to pond construction. This is the case regardless of whether a Resource or Building Consent has been granted.

As part of their district plan, Territorial Authorities (TAs) prepare maps which include heritage and archaeological sites. These should be checked prior to consent applications being submitted for pond and related earthworks.

If a previously unknown site is uncovered during earthworks, permission from the NZHPT may be needed for the work to continue. For further information on investigating archaeological sites, contact NZHPT or email [archaeologist@historic.org.nz](mailto:archaeologist@historic.org.nz)

## 3.6 REGULATORY REQUIREMENTS OVERVIEW

There are potentially four sets of regulatory standards to be met for FDE containment facilities (which include dams, tanks, sumps, pools, and ponds). Up to three of these may involve consent requirements.

While in most situations dams, tanks, and ponds may be constructed without requiring Building Consent, *Building Code* performance compliance is still required. Furthermore, if the FDE pond or tank design and construction require a Building Consent, then generally only a CPEng has the authority for signing off such work. Whether this is required depends on the BCA's policies.

As an overview, Table 3.8 below notes the key regulatory requirements for FDE ponds, while Figure 3.1 outlines consenting and code of compliance requirements. Figure 3.2 provides a schematic regulatory decision flow diagram to help practitioners understand the consent process. The relevant regulatory requirements are summarised in a checklist in Appendix C.

ACT OR TYPE OF LEGISLATION	POSSIBLE REQUIREMENTS	REGULATORY AUTHORITY
Resource Management Act 1991	Resource Consent for construction/earthworks (if trigger is exceeded) Resource consent for use/discharge Consent for stream diversion	Regional Council
Building Act 2004; <i>Building Code</i>	Consent for construction Consent for tank Dam consent	District and Regional Council or unitary authority
Local government requirements (district plan/RMA)	Land use consent Earthworks/gravel extraction	Local council or unitary authority
Health and Safety in Employment Act 1992	Safety during construction Fencing of ponds	MBIE (Labour Group) <a href="http://www.dol.govt.nz">www.dol.govt.nz</a>

Table 3.8: Regulatory Requirements

### KEY POINTS

- Pond consents required will depend on whether they are: not a dam, a dam, or a large dam.
- Regional Council and Building Consent requirements vary within New Zealand.
- Tanks may need Building Consents.
- Health and safety requirements including fencing and means of escape must be considered.
- All ponds must meet the performance requirements of the Building Act.




Figure 3.1: Consenting and Code Compliance Requirements




Figure 3.2: Regulatory Decision Flow Diagram

# 4.0 SITE INVESTIGATIONS

## 4.1 INVESTIGATION PURPOSE: AN OVERVIEW

Site investigations determine whether, given the site conditions, a structurally sound structure that meets TA and RC rules can be built.

### 4.1.1 NEW PONDS

For new FDE ponds, the proposed site should be thoroughly investigated before design and construction begins. Generally, an FDE pond should be located in an area with low permeability soils to reduce the risk of seepage loss.

Soil profile samples should be obtained to provide information on the material properties. These should be obtained at the depth, and beneath, the bottom of the proposed FDE pond. The prevailing groundwater regime is also critically important.

### 4.1.2 EXISTING PONDS

Assessing the potential for an existing FDE pond to leak is difficult. However, it may be possible to see if it is leaking from visual observations and by measuring fluid levels over time, while taking into account evaporation. Essentially, ponds that show a rapid drop in level over relatively short time periods will probably be seeping at unacceptable rates and need further assessment. Visual assessments to determine obvious high-seepage zones (for example, through embankment or conduits) are good starting points. It would also be prudent to establish whether the existing liner (if present) has been damaged.

These assessments could be followed by verifying the soil profile and characteristics around representative portions outside the pond using the techniques described below. Associated permeability testing may also be necessary to confirm the seepage rate of the soil profile, to confirm whether unacceptable seepage is an issue.

If there is any doubt about a pond leaking and no obvious cause is located, then environmental sampling and investigation may be required to pinpoint the source and impact of any contamination.

## 4.2 SOIL PROPERTIES

Site investigations must be detailed enough to identify the variations in soil types present at the site.

Early in the investigation the designer needs to consider whether a clay or synthetically lined pond is most likely required. This will ensure the investigation is more precisely conducted to collect relevant information.

Clays and silty clays are the most appropriate natural materials for pond construction. In some cases where sand, gravels, pumice, and other highly permeable soils prevail, the only solution will be a synthetic lining material or a CCL using suitable imported/borrowed materials. A synthetic lining should be considered at sites where soils are unlikely to be able to meet the liner permeability requirement specified by the RC.

The New Zealand Geotechnical Society has a guideline for the field classification and description of soils and rock (refer to References section).

### 4.3 SITING A NEW POND

It is appropriate to investigate where a pond will be sited and to avoid installing design elements that allow for the pond's proximity to sensitive features. These features can include surface water bodies, artificial watercourses, installed subsurface drains, groundwater level, bores, registered drinking-water supplies, coastal marine areas, trees, stop banks, residential dwellings, places of assembly, urban areas, property boundaries, milking areas, and sites of cultural significance. It should be noted that prevailing winds can carry odour a long way.

Unknown sites of cultural significance are unlikely to be identified before works begin. However, if discovered during construction, works should cease and the site should be reported immediately to the NZHPT and local iwi representatives.

Pond placement and orientation should also take into account potential slope instability, inundation from flooding, diversion of flood flows, and stormwater in-flows. In areas subject to actual or potential inundation, the pond base should be at least one metre above the highest known flood level if possible. If not, then specific engineering design should be undertaken. It is also preferable that long ponds be orientated along the floodplain rather than across it, and perpendicular to the prevailing wind to reduce the effect on wave action and potential spillage if the pond level is high.

When assessing a site for its suitability for pond construction and the availability of materials the following factors should be considered:

- The type of soil material is present at the site
- The soil profile to at least one metre below the finished base depth. How the soil texture may vary down the profile and if there are inherent potential problems due to layering of the materials present. The materials available for bank construction, and/or for lining the inside of the pond
- The potential for variation in the soil profile across the pond site
- Proximity to natural ground slopes acting as an outer dam embankment wall
- Whether the base of the pond is well above the maximum predicted level of groundwater; the slope stability and landforms present.

Other recommendations:

- Locate the pond clear of any watercourses, including secondary flow paths; also stream/gully channels
- Check the ability to gravity feed the FDE to the pond from the dairy shed rather than needing to pump
- Place the site as close as possible to a suitable power source to minimise cost of getting power to the pond if required.

Ponds should be located well clear of trees or shelter belts (about 20 metres or two thirds of the tree height) to:

- Avoid damage to synthetic liners from wind-thrown branches
- Minimise debris which would otherwise collect and block pump screens
- Avoid ingress of tree roots into the pond walls.

Figure 4.1 provides a graphic showing some site consideration factors.

Another important consideration in some regions is the time of year construction is planned to take place. While an earthen embankment pond may be very difficult to construct in winter in some regions, alternative pond systems (for example, precast concrete panelled tanks) can be constructed in winter.

The Ministry of Primary Industries requires dairy to specify certain requirements, such as their effluent storage facilities' separation distance from their milking sheds. Designers should ask pond owners to confirm the industry standards that may affect their containment facilities' design, placement, and construction.




Figure 4.1: Site Considerations (allowable distances vary between Regional Councils)

## 4.4 FIELD INVESTIGATION STEPS

Designers need to arrange for field investigations and prepare site investigation reports. Copies of these reports may be required by RCs to be included with pond consent applications.

The field investigation steps are described below.

- Step 1:** Assess and record the site's overall terrain. Need to note: slope stability, surface water, and vegetation type. The site should be devoid of trees to avoid the presence of tree roots near the pond.
- Step 2:** Undertake the investigation to at least one metre below the finished depth of the pond to determine the type of soil materials present. This will require using a hydraulic excavator to dig the investigation test pits across the proposed site. Adhere to the MBIE (Labour Group) requirements for working in and near trenches.
- Step 3:** Log and photograph the soil materials to determine the type of soil present, its physical properties, and overall profile. Record any variations to the natural soils materials such as imported fill containing wood, plastics, or metals as well as any voids created by tree roots or water erosion, as these may render the site unsuitable. Give special attention to any collapsing of the test pit sides and its mechanism for failure, as this may be an indicator of substandard performance for the material type present.
- Step 4:** Closely assess the soil texture and materials to establish whether a synthetic liner is needed to be fitted inside of the excavated pond. If the *in situ* soil itself is intended to be used as a clay liner then this must be substantiated by testing as outlined in Part 2 (Clay Liners). (Note that while a soil may have suitable properties to comply with a "sealed pond's" permeability requirements, the soil structure and texture ultimately govern its permeability by its preferential flow paths.)
- Step 5:** Where a clay liner is considered an option samples of the borrowed material need to be taken for laboratory testing. It is important none of the samples contain any organic material, so topsoil must be excluded. Bulk samples should be placed in a labelled, air-tight plastic bag. Laboratory tests for clay liners are described in Part 2 – section 3.
- Step 6:** The soil investigation test holes are necessary to assess the level of the water table and seasonal fluctuations. These fluctuations can be significant and must be determined if the pond's floor level is to be set at a safe height. Some sites may have a temporary perched water table in winter due to impervious subsoil which overlies the main water table. This is typically indicated by soil discolouration; red-brown indicates oxidised free-draining conditions while mottled grey indicates lack of internal drainage. Typically dark grey or blue-tinged soils indicate permanently wet strata.

#### 4.4.1 GROUNDWATER

Test holes in late winter will normally show the highest water table's location. However, test holes at other times of the year will require more careful interpretation and a period of monitoring may be required to obtain reliable data. To monitor the groundwater level, a piezometer can be installed. The groundwater level can then be measured by dipping a measuring device and recording the depth of the water below the ground surface.

Local knowledge, if available, should also be considered. In addition, the local RC may have information on groundwater levels throughout the region, which will be available upon request.

Where there is subsoil, there will usually be indications of fluctuations in the water table in the soil profile. For profiles without a subsoil (that is, gravels), the water table fluctuations may be more difficult to establish. The accumulation of iron and manganese, for example, can show the range in water-table height. They may also show historic high water-table levels which are no longer relevant.

Agricultural land that has typically been artificially drained with tiles and moles, and the presence (or otherwise) of drainage, may also influence water-table height and allowance must be made for this. Pond construction must also allow for detecting and removing or replacing tile drains that may be present under or near the pond structure.

Groundwater monitoring is required to ensure the pond's proposed base is well above the maximum predicted groundwater level. It is considered inappropriate to construct ponds below the groundwater profile. If this must occur, then specific design from a geotechnical professional must be sought.

##### KEY POINTS

- Consider distances from shed, waterways, houses, trees, boundaries, and power source when deciding where to locate ponds.
- Site locations need to factor in milk company requirements.
- Site investigations must identify all soil types present.
- If using compacted clay liners, it is essential to get the clay tested through a professional engineering laboratory.
- There is a range of liners and manufactured products available.
- Know where the water table and drains are located.



*HDPE synthetic liner being installed.*

# 5.0 Design

## 5.1 INTRODUCTION

Before any design decisions are made about the pond materials, configuration, and construction, a clear understanding needs to be reached with the client about:

- How the pond fits into the overall FDE system
- What type of pond system they require.

There are a number of approaches to managing FDE. Each requires quite different pond designs.

## 5.2 TYPES OF PONDS

Some current pond styles include:

- A single-pond system, collecting raw effluent. This can provide for moderate settling of the solids (forming a sludge unless stirred) prior to the fluid component being discharged and pumped to a land application area. In many cases the single pond is used for bulk deferred storage with no requirement for settling; it may have a stirrer installed to mobilise the sludge for irrigation to land
- A two-pond system involving a typically anaerobic primary pond used for settling solids flowing into a secondary pond which can be aerated to further treat the effluent before it is discharged, or being further clarified (through solids settling or removal), before being discharged
- Multi-stage ponds that are similar to wastewater treatment facilities with various settling, clarification, aeration, and disinfection processes prior to the effluent being discharged (typically) to a waterway or land
- One- to two-day capacity sumps that collect the raw effluent, which is then discharged via a high-rate travelling irrigator to pasture. These are not considered suitable in some regions to manage effluent and maintain compliance throughout the year.

Current good-management practice is for the construction of deferred irrigation storage ponds, so when the soil moisture conditions are suitable the effluent can be discharged to land. Otherwise it is stored.

## 5.3 EFFLUENT TREATMENT DESIGN

### 5.3.1 ANAEROBIC AND AEROBIC PONDS

Commonplace treatment in the past was a twin anaerobic/aerobic pond system which usually discharged to water. However, increasing regulation by most RAs has seen these systems reduce in number across New Zealand.

Traditionally these ponds have been intended to function as treatment ponds. They maintain a fairly constant level, with varying seasonal inflow and rainfall, with a related discharge from the pond. Pumping out and desludging the ponds would be an infrequent occurrence, and the pond would rapidly return to a normal operating level regardless of whether the intended physical and biological processes were present.

Where new anaerobic ponds are designed, they should have a normal operating range of >1.5–2.0 metres with a total depth of at least three metres, although four to five metres is ideal. Shallower treatment ponds (unless mechanically aerated) will be “facultative” with a layer of anaerobic activity on the base and a thin layer of aerobic water on top.

### 5.3.2 EFFLUENT PONDS AS STORAGE

Current industry good practice is for the pond to act as a reservoir, providing buffer storage of effluent for periods (possibly up to six months) when ground conditions do not allow land irrigation. In this mode, the pond is normally at a low level (possibly empty for long periods through the summer) then filled gradually during wet weather, but may be drawn down quite rapidly when irrigation is resumed. Earthworks and lining systems for this type of pond operation need to recognise this fluctuating water-level pattern.

## 5.4 SOLIDS MANAGEMENT

### 5.4.1 SOLIDS REMOVAL

Traditional FDE irrigation involved pumping directly from the yard or transfer sump (10–30 m<sup>3</sup>) to pasture. The sump may have had one or more stirrers to agitate the sump's entire contents. The resultant slurry was then applied direct to land via a high-rate travelling irrigator.

Newer FDE systems incorporate a stone trap prior to flow to a large transfer sump (or tank) of 20–140 m<sup>3</sup> in size. On days where irrigation is allowed, “raw” FDE is pumped directly to irrigation without separation. During days where irrigation is not permitted, effluent can either be passed through a solids separation process (or not) and stored until irrigation is again permitted. The FDE is then either pumped directly from the pond to irrigate the pasture or returned to the sump for irrigation from there.

If solids are removed before the FDE reaches the storage holding pond, problems with pond solids' management are reduced or eliminated. Solids removal is commonly achieved by either mechanical or non-mechanical methods.

### 5.4.2 MECHANICAL SEPARATION

Mechanical separators are typically designed to remove solids down to less than one millimetre. The resulting liquid contains only fine suspended organic material and silts/clays, plus all the dissolved nutrient value (these are mainly Nitrogen (N) and Potassium (K). Phosphorus (P) tends to be in the solid fraction but may also form soluble salts and fine particulates in the effluent).

It is important to be clear about what the principal plans to feed through the mechanical separator and how this may affect the separator's performance. In this context, it is also important to consider the separator's capacity to ensure it will adequately meet the principal's current and future needs.

### 5.4.3 NON-MECHANICAL SEPARATION

Non-mechanical separation methods include “weeping walls”, settling ponds, slope screens, and rotating drum systems.

Recent weeping-wall system developments have improved wall design practice. Good wall design now includes the following common elements:

- Tapered timber or suitably robust plastic or concrete battens with appropriate maximum opening between battens can be used to construct the wall
- International guidance has resulted in wall porosities of 15 to 30 per cent to prevent blockages
- The wall's specific engineering design ensures it remains structurally sound when the pond is full
- The wall's large surface area ensures low flow rates and reduces the potential for solids passing through it
- The wall's height is no greater than 2 metres.

Where gravity systems are used, the bottom of the wall is below the storage pond's maximum fill level. There are a number of other systems in development which are likely to provide other options to these in the future.

## 5.5 EFFLUENT IRRIGATION

The preferred effluent irrigation method will depend on effluent volume, treatment levels, the terrain to which the FDE is applied, budgetary constraints, soil properties, and nutrient constraints.

It is not intended that this document go into detail on effluent irrigation, this being covered in the *DairyNZ FDE Design Code of Practice* and other publications. However, the following information on effluent irrigation is provided to give pond designers general awareness on irrigation delivery methods available.

<b>Centre pivot irrigators</b>	A large-area irrigator with prior solids treatment is required. It requires separate piping for effluent and water irrigation, and is most suited to large operations with flat land. The speeds can be altered to apply high and low application rates, and large volumes (>100 m <sup>3</sup> /hr) can be shifted.
<b>Travelling irrigators</b>	These are large self-propelled wheeled sprinklers with one main drag line. Little treatment is required, as travelling irrigators can generally handle solids well. They typically apply high depth rates. Newer irrigators have been designed to provide lower-depth applications while still having high rates of irrigation. Discharge volumes from 10–100 m <sup>3</sup> /hr are common.
<b>Pods</b>	<p>These are small static sprinklers that require regular moving. There are two main types:</p> <ul style="list-style-type: none"> <li>▪ “K-line”, a 4 mm nozzled sprinkler that requires solids removal and many sprinkler heads in a set (20–100+ depending on farm size)</li> <li>▪ Larger sprinkler heads with 9- to 15-mm nozzles typically in sets of four to five pods perform better with solids removal but are not essential to operation. They are suitable for all terrain. Low-rate application typically &lt;4 mm/hr. Pods have the benefit of pulse application rates, with sets of pods timed for short periods to allow very low average application rates of &lt;1 mm/hr while still achieving volumes discharge requirements.</li> </ul>
<b>Guns</b>	These large sprinkler heads are similar to raw pods on sprinkler stands and are moved from paddock to paddock. They are connected to preinstalled hydrants or pipework in paddocks. They require frequent moving and can cope with well-treated or raw effluent but need specific setup for each. The guns tend to be forgotten if not electronically monitored, causing over-application. Multiple guns can be connected to a manifold to allow low/pulse application.

Table 5.1: Irrigation Delivery Methods (To Pasture)

**Note:** If it is intended to connect effluent pipelines to systems primarily intended for water irrigation (for example, centre pivots), then appropriate risk assessment for back-flow prevention to prevent clean water supplies being contaminated should be carried out. Ideally, separate pipework should be installed to eliminate the risk.

The actual irrigation method will have an impact on pond design, with variations depending on the effluent’s treatment and function. In all cases there will need to be a formed effluent abstraction point, and all-weather access for an excavator or maintenance vehicles to service or replace pumps etc.

A number of equipment options for FDE intake from a pond can be used and will impact on the appropriate pond geometry design.

<b>Floating pontoon</b>	The floating pontoon has a pump intake suspended below it with other ancillary equipment (for example, a stirrer) attached. It requires a minimum water level to prevent it running dry. This will affect useable pond sizing, unless a specific pump sump is built in. Access for the pump may be a difficulty. Recent guidance from the MBIE (Labour Group) should be consulted on the appropriate access provisions.
<b>Jetty or structure</b>	The jetty or structure is set into the pond from which the pump and ancillaries can be secured. Health and Safety issues including barriers need consideration. Building Consents will generally be required.
<b>Self-priming pump</b>	The self-priming pump has an intake line into the pond and screen is typically a centrifugal pump requiring low-solids effluent for best performance.
<b>Positive displacement pump</b>	A positive displacement pump which can process higher solids content, such as progressive cavity pumps, can be set up with an intake pipe into the pond with suction screen. Progressive cavity pumps can also be either vertical pontoon mounted or pond crest mounted.
<b>Pump sump</b>	A pump sump in the base of the pond with the base sloping down into it will allow maximum draw-down of the pond while allowing pump intakes to remain submerged. It also facilitates easier access for maintenance with flushing or scraping of sludge to the pump-out point.

Table 5.2: Irrigation Intake Options (From Pond)



Sludge bed with double weeping wall and PVC battens.

## 5.6 POND SIZING

### 5.6.1 DEFERRED IRRIGATION STORAGE

Where a pond is being designed as a deferred irrigation storage pond, the size needs to be derived from a water balance approach to cover the expected “wet year” period when irrigation may not be allowed due to insufficient soil-moisture deficit to accept the applied effluent which without ponding or runoff. Guidance should be sought from the RC or best-practice guides as to the return period at which the calculated maximum annual storage-pond volume required is not to be exceeded.

The size of storage is determined by taking into account a number of factors:

- How the principal wishes to manage his FDE
- Number of days FDE storage is required (by RC or design standards, whichever is the greater)
- Normal daily FDE production volume – some RC’s require a per-cow volume
- Rainfall
- Soil saturation levels – prevalence of weather conditions and/or soil type where effluent applied would either excessively pond on the soil surface or runoff to surface water, both of which are unlikely to be allowed under Resource Consent conditions
- Maximum nutrient loading, as required by Resource Consent, or best practice, or catchment regulations, while allowing for nutrient concentration in effluent
- Proposed irrigation method and pumping rate. Low-application irrigation provides a wider window of opportunity to irrigate soils near field capacity, while systems with a high pumping capacity allow more effluent to be irrigated in a short time and therefore the pond volume can be lowered quicker. The daily irrigation volume must be at least double the daily input or the pond is unlikely to be emptied
- Expected solids accumulation in the pond
- Allowance for the minimum level to which the pump can draw down to (for example, if on a pontoon, it may be best to provide a sump in the pond over which to locate the pump)
- Minimum freeboard of 0.5 metres but may need to be greater depending on pond size and prevailing wind conditions
- Breakdowns and maintenance contingency allowance
- Allowance for future stocking rate (for example, increased herd size, or increased shed utilisation or addition of a feed, standoff, or silage pad).

A water balance model is best calculated by using the Dairy Effluent Storage Calculator (DESC) developed by Horizons Regional Council and Massey University. It calculates the required stored volume based on a number of factors including rainfall from the previous 30-year period and soil types. However the following should be noted:

- Local rainfall variability should be taken into account in sizing based on the pond calculator, as coverage of rain-gauge sites in the calculator is limited in some regions, although more will be added with time
- The RC will set the rainfall return period, which may be more frequent than one in 30 years
- There is currently some variation in the amount of storage that different RC’s require. It is recommended that sizing be based upon a rational assessment of water balance and irrigation application rather than a council minimum storage requirement where the latter gives a lesser volume. This will ensure the installation is future-proofed
- The DESC determines pond working storage volume and does not currently allow for freeboard or sludge accumulation volume, but does allow for a specific number of days of “emergency storage” to be added.

### 5.6.2 RETENTION TIME

Where ponds are being designed as a treatment component with normal constant level and daily liquid removal, then sizing will be based on retention time. Additional ponds or capacity are included separately for the deferred irrigation requirement.

For solids removal, allowance needs to be provided for sludge accumulation. Around 1.5–7 per cent of the shed effluent may be solids (again a highly variable figure depending upon water use, feed, and season). Feed pads will be different again, as there tends to be a larger solids component due to feed wastage (15–45 per cent).

Allowance should also be made for the time interval between solids removal with timing of this in line with the farm management and seasonal work load. Above the sludge storage allowance will be the liquid volume required to achieve settling. In effect, the treatment pond is being designed as a rudimentary clarifier and normal surface-loading rate considerations would apply.

For oxidation or aerated ponds the sizing will be provided by the treatment process designer and is not within the scope of this Practice Note.

### 5.6.3 EFFLUENT PRODUCTION RATES

Per-cow effluent production figures should be used with caution. They will vary widely from site to site depending on milking times, shed type, stock handling, feed, season, and wash-down methods. While a “typical figure” of 50–70 litres/cow/day is often quoted for dairy shed effluent, water efficient installations may use much less (30 litres/cow/day) and poorly set-up sheds may use in excess of 90 litres/cow/day.

To confirm the design FDE volumes, for example, from the DESC, are consistent with the actual volumes it is sensible to measure the actual production (in dry weather). This may be possible by measuring the input water to the shed over milking (watch for milk chiller water as this should not be feeding into the effluent), plus an allowance of about 10 per cent for urine and faeces. Alternatively, measure the effluent being pumped away. Allowance should be made for shed upgrades that change the herd size or water management regime of the shed.

For a new farm/conversion, typical figures will need to be relied on. It is suggested that designers seek input from the milking plant installer, especially when green water reuse systems are to be installed. IPENZ promotes good-practice guidelines for water conservation and use.

## 5.7 POND GEOMETRIC DESIGN

### 5.7.1 GEOMETRY

While there are no specific requirements for storage geometry, the pond's operation and use will govern its shape. For treatment and settling ponds in general, a long pond with a set width will be better as it will be easier to clean and provides a longer path for the solids to settle out. A 2:1 length to width ratio is often used. Consideration should also be given to access for solids removal. The width of the pond will be determined by what equipment will be used to carry out solids removal. Likewise, the depth is constrained by desludging equipment, unless specific ramp access is incorporated into the design.

Where a pond containing unprocessed FDE is to be stirred prior to pumping, a round pond would be preferable. However, we suggest making contact with the stirrer supplier to ensure that the pond can be effectively stirred given the proposed pond size.

A long and narrow deferred storage pond should be orientated to avoid the longest dimension being in the direction of the prevailing wind as wave and wind action may increase risk of wave action damage or overtopping/splash. It is also preferable to have rounded interior corners rather than sharp changes in direction which have a higher scouring risk.

DairyNZ has developed a spreadsheet based tool to assist in calculating the working volumes and true dimensions of a new or existing storage pond or tank. It can be used for square, rectangular or circular facilities. The calculator should be used in combination with the storage volumes generated from the Dairy Effluent Storage Calculator, or for calculating the working volume of existing ponds and tanks. A link to it is contained in the References section under DairyNZ.

### 5.7.2 BATTER SLOPES

Both inside and outside fill and cut batters should be no steeper than 2:1 horizontal (H) to vertical (V). Batters steeper than this will need a specific geotechnical assessment for suitability. Where the local soil conditions are known to be sensitive, then flatter batters should be utilised.

Where clay liners are used, the type of construction plant available will determine batter slopes. On slopes steeper than 3:1 (H to V) it will be difficult to achieve adequate compaction of the clay liner to the required specification by traversing the slope. Standard construction methodology as outlined in NZS 4431 is a prudent method of placement. One way around this is to construct in horizontal lifts and then trim back to the desired slope.

Synthetic liners can be laid on steeper slopes if a specific soil-slope stability assessment is conducted. Careful consideration and assessment of the steeper batter under both drained and undrained conditions will need to be conducted to ensure the steeper batter is not at risk of slumping or eroding behind the liner. If moisture or water were able to enter and create undrained conditions, then a drainage layer on the batters and base of the pond would be required. Ponds should not be installed below the highest expected groundwater profile.

Batters must be stable under applied loads from vehicles, for example, tractors or trucks carrying out pump servicing or desludging operations.

### 5.7.3 SPILLWAYS, PIPES, AND FILTER COLLARS

In addition to stormwater diversion, ponds may require a specifically designed emergency spillway for protection from severe storms to avoid overtopping. Means to avoid or mitigate overtopping should also be considered. Spillway design has not been included in this Practice Note and practitioners should refer to references such as KD Nelson's *Design and Construction of Small Earth Dams* (refer to the References section under Pond Design and Construction).

Typically the weakest point in a pond is where pipes penetrate embankments, so pipes through embankments that are below the highest pond water level should be avoided. If installed, these pipes should have filter collars to prevent piping failures. Traditional seepage collars no longer represent best practice. If a pipe penetrates a liner then a liner sleeve or boot should be installed around the penetration to ensure the penetration is watertight. Penetrations in CCL ponds will require additional compaction around pipework.

Where FDE discharges from an open pipe onto a liner this may cause abrasion and scouring of the liner surface over time. The effects of this can be reduced by the use of concrete channels, an additional layer of synthetic lining, and rubber mats.

Where a suction pipe is used, this should be placed through the embankment berm at a height that assists pump priming. An HDPE pipe should be used and be fitted with HDPE collars.

Pond designers should consider using the services of a specialist engineer to assist with detailing of these important pond design aspects.



GCL liner to FDE pond.

## 5.8 SOLIDS MANAGEMENT DESIGN

### 5.8.1 CLEAN-OUT DESIGN

At the design stage, consideration needs to be given to how the pond will be accessed for cleaning or for servicing of pumping and stirring equipment. This will likely require provision of a section of an all-weather track and a hardstand where service vehicles (for example, a truck with hydraulic arm) can be parked. A suitable grade should be provided on the access track.

Increasingly, farmers are choosing to separate solids out from FDE prior to pond storage to simplify the management of effluent, tighten management of nutrient application, and reduce potential RC effluent non-compliance.

For synthetic-lined ponds where solids can accumulate, they may be cleaned out using a floating pump and stirrer, or a shore-mounted suction pump with an intake on the base, or a slurry tanker. They should not be cleaned out with hydraulic excavators or loaders etc, unless appropriate protection layers have been provided. We recommend consulting with the supplier of the synthetic liner.

A CCL pond that is cleaned out regularly will need to be relined periodically as there will have been loss in the thickness of the clay liner during the cleaning operation.

### 5.8.2 LINER PROTECTION FOR MECHANICAL CLEANOUT

For a synthetically lined pond to be safely cleaned out by excavators and other equipment, the pond must be specifically designed and constructed to provide liner protection from the action of the equipment intended to be used. The base and side walls must be robust, and reinforced concrete would generally be used for this purpose. This concrete will need to be specifically designed to prevent excessive cracking during excavator loading. It will also need to have its buoyancy checked, as fluid will get between the liner and the concrete if a bathtub-type concrete base has been constructed.

Where a pond is proposed to be agitated as part of the solids removal operation, then a protected area should be placed on the pond floor and batter to provide a “stirrer point”. This could be a concrete slab extending some 3 metres by 3 metres over the floor. We advise discussion with the irrigation supplier as to their requirements. Depending on the size of the pond, it may require stirring at several locations to fully agitate sludge layers, so more than one stirrer location could be needed. Full agitation may be very difficult to achieve on larger ponds.

We advise discussion with the liner supplier to establish any specific requirements they have regarding concrete or structures on the liner. Typically a very robust protection geotextile would be placed on top of the synthetic liner if concrete is then to be placed.

Clay liners are particularly vulnerable to damage from stirring and will need to be protected. One solution is to use cast *in situ* concrete slabs on the base of the pond and graded rock armouring with a geotextile separating layer on the batters. The rock armouring will need to be specifically designed for the current and vortex forces that will occur in the pond. It is not recommended that clay ponds be stirred without armouring.

### 5.8.3 SLUDGE BEDS, BUNKERS, AND DRAINING PADS

If solids are to be stored on site then these will need to be held on a confined area designed and constructed to provide at least the same permeability criteria as the pond liner, which is  $1 \times 10^{-9}$  m/s, or as required in the Resource Consent. Lining options for sludge beds/bunkers and draining pads include:

- A concrete slab floor with a nib wall or bunker wall. Practically and serviceability wise, concrete gives a good long-term result
- A GCL under a confining layer of cohesive material
- A premium-grade synthetic liner in conjunction with a geotextile underliner. A textured HDPE liner with a cohesive cover layer is another option.

The design of these structures needs to be such that effective draining and drying can occur. Drainage from the base needs to be either contained or directed back into the effluent containment system.

## 5.9 LINERS

### 5.9.1 LINER OPTIONS

Liners can be formed from compacted clay; or specially manufactured geomembrane materials such as polyethylene, polypropylene, synthetic rubber, geosynthetic clay; or concrete.

It is imperative that the type of liner selected is appropriate to the intended purpose and that due diligence is observed during preparation, installation, and subsequent use. No matter what type of lining material is used, defects from inappropriate installation or use are likely to result in consent non-compliances, costs of remedial work, and wasted capital invested in a structure that fails to control environmental liabilities.

Pond Lining options	Refer
<i>In-situ</i> clay	Part 2
Compacted clay	Part 2
Geomembranes (synthetic liners)	Part 3
Concrete	Part 1, Section 5.9.2

Table 5.3: Pond lining options

### 5.9.2 CONCRETE LINERS

Sprayed concrete using compressed air, also referred to as Shotcrete, can be placed as a wet or dry concrete mix to form a liner.

To avoid slumping, this concrete mix is likely to be a special mix of chemical additives, silica sand, fly ash or aggregate, and cement. Synthetic fibres may also be used as an alternative to the use of a wire mesh or metal reinforcing bars. The addition of such fibres will provide improved compressive strength, flexural capacity, and impermeability.

A geotextile or synthetic liner under the liner is required to minimise soil contamination and to dissipate groundwater and sub-surface gases.

## 5.10 POND PERFORMANCE CONSIDERATIONS

### 5.10.1 DRAINAGE CONTROL AND LEAK DETECTION SYSTEMS

Piping failure (erosion along lines of weakness) in soils underlying ponds should not be an issue with a properly constructed and maintained FDE pond where leakage is very low. If foundation soils are dispersive, or otherwise prone to piping and formation of sub-soil cavities (tomos), specific underdrainage provision may be prudent.

An FDE pond would not normally be designed with secondary lining and leak detection systems; however RCs are increasingly encouraging these features in pond design. Foundation soils will generally be orders of magnitude more permeable than the pond liner. Small leakages will dissipate to the soil. If underlying soils are slowly permeable (for example,  $<1 \times 10^{-6}$  m/s), then an underdrainage system (gravel layer or strip drain) could be incorporated.

Whilst it is recommended that the highest water-table level for a site be below the base level of the pond, this is not always achievable. In this situation, liner and pressure release design is particularly important.

Water drainage and water table management can be via trenches. Generally these are either permeable material wrapped with a geotextile or perforated drainage pipe wrapped with a geotextile to avoid finer particles entering. Drains should be placed approximately five metres apart, in addition to being positioned around the foot of the base perimeter. For smaller ponds a ring drain placed at the foot of the batter slope should be suffice. To further aid drainage, allow for 100 mm of drainage metal over the drainage system.

The water drainage network should culminate in an inspection point; this allows the collected liquid to be tested and liner leakage to be ruled out.

A Leak Detection System (LDS) installed at the time of pond construction will provide a very convenient means of providing ongoing leakage detection. These systems consist of a water drainage network (aggregate or piping with impermeable base layer) underneath any clay or synthetic liner, which drain to an inspection well. Liquid in the well can be easily inspected, collected, and, if necessary, tested to determine the source; groundwater will tend to be low in nutrients, solids, and bacteria, whereas FDE will be high in all three.

The well itself should be 400 mm or greater in diameter, for example, formed from a length of culvert pipe and able to be easily sampled from (using a suction pump or grab system). Further, the inspection well should be weathertight, stock-proof, and sealed around the ground surface.

A pond drop test may provide a more conclusive measure of water-tightness but only if there is a major leak. However, an effective LDS will provide a much earlier indication of leakage.

An alternative LDS technique that is relatively new to New Zealand is electric field testing. Water as a conductive medium is applied to a membrane surface, and a tear or leak in the membrane creates a fault that can be detected.

### 5.10.2 GAS DRAINAGE

Drainage of gas from beneath the liner is an important consideration where synthetic membrane liners are used. If the pond has a large flat area and gas is unable to escape to the surface, then the liner will float in large bubbles (also known as humpback whales or hippos). Gas could be the result of decomposition of organic matter in the soil (for example, peat, residue from an old unlined pond, unknown leaks), air trapped by a fluctuating water table, or decomposing effluent (from a previous pond).

Gas drainage could be provided by an aggregate layer beneath the liner (in which case, check for compatibility between the liner membrane and the stone size, or by synthetic drainage products, with a minimum fall of two per cent to allow for positive gas movement. Gas should then be appropriately vented to the surface. Note some saturated gases will drain downhill and may need to be dealt with separately to volatile gases.

The geometry of the pond base is important to ensure gas drainage – slope at one per cent upward from the centre. A narrow base width of with shallow batters could be a better configuration than a wide base with steeper batters if gas is anticipated.

Geotextile is often recommended for both clay and synthetic liners, sometimes above and below, but in particular, underneath the liner. The purpose of a geotextile is to provide separation of fines or to protect the liner from puncturing. Some geotextiles available provide both fines separation and gas drainage.

### 5.10.3 HEALTH AND SAFETY REQUIREMENTS

Steep lined slopes, whether slick clay or synthetic membrane, are a hazard for farm workers (and stock). All ponds should include at least one ladder or alternative escape means in the event of a fall into a pond. Larger ponds will require several such escape routes.

Similarly, all ponds should be fenced off with a netting fence to prevent stock (and children) from straying and falling into the pond.

#### KEY POINTS

- Pond storage volume: allow for maximum herd size, any silage pit and feedpad runoff, rainfall, yard wash-down, future-proofing.
- Prepare detailed construction documents: drawings, specification, schedule of quantities, cost estimate.
- Orientate pond to reduce potential adverse effects of flooding and wave action.
- Include drainage and gas venting systems in pond design.
- Where a pond requires stirring, ensure pump sufficient to adequately stir the volume. needed without liner damage, also factor in maintenance and safety requirements.
- Seek and consider advice from liner/containment specialists.

# 6.0 Construction

## 6.1 INTRODUCTION

Every FDE pond is different and there will be variations in the design and construction of each. This section sets out a number of items that should be considered by farm owners, contractors, suppliers, as well as the Suitably Qualified Person (SQP) who will be signing off the work:

- Meeting consent and regulatory requirements
- Preparing a specification
- Monitoring the construction contractor
- Ensuring quality-assurance requirements are being met
- Meeting the principal's needs.

## 6.2 DRAWINGS AND SPECIFICATIONS

For a contractor to construct a pond that achieves the design criteria, then detailed drawings and specifications are required.

Drawings need to provide sufficient detail so that the contractor can clearly understand the designer's intentions and requirements.

A good starting point for a specification is NZS 4431:1989 (Earth Fill for Residential Development), particularly sections 6–11. Both practitioners and contractors should make themselves familiar with the requirements of that Standard.

## 6.3 THE SUPERVISING ENGINEER'S ROLE

Before a contractor's offer is accepted, it is advised that the proposed construction programme be confirmed as this provides some certainty to the principal around timing and completion for the works.

At the works' commencement, the SQP should ensure that the contractor has a copy of the Resource Consent issued by the RC which permits the pond to be constructed (if that is required), and that the contractor and SQP are fully aware of any Resource Consent conditions. Furthermore, during construction the SQP will need to monitor the construction activities and confirm that all specification requirements are being complied with.

The level of construction management needs to be determined by the SQP prior to construction in consultation with the principal, and will depend on the complexity of the project. The construction monitoring services section on the IPENZ website provides guidance on this.

During excavation, the supervising engineer needs to be aware of any material substantially different from that revealed in the pond site investigation and soil geotechnical analysis. If encountered, the differing material will have to be assessed and pond design or construction adjusted accordingly. An adjustment may require formal amendment or variation of the Building Consent under the BA (and possibly the Resource Consent under the RMA too) prior to undertaking that building work as the adjustment is not consented and the completed work may not be able to be certified.

The person signing off the construction review (the SQP) must satisfy themselves that sufficient compaction to the fill material has been applied. This may be determined by a combination of laboratory and field tests, or compaction trials, together with experience in the plant and materials being used.

If the contract works are to be completed under NZS 3910 then the issuing of the Practical Completion and Defects Liability Certificates will need to be assessed and completed.

## **6.4 EFFECTS OF WORKS ON OTHERS**

The contractor will need to carefully consider the site conditions and timing of the contract with respect to the potential for runoff, dust, and noise generation from the works.

The contractor should arrange and control the work so that the construction of the pond will not cause contamination of waterways or a dust nuisance to any nearby properties. A water cart should be on site to dampen down any area causing a dust nuisance.

Works may have to be arranged to minimise inconvenience to the farmer in their dairy farm operation and work around cow movements and milking times.

## **6.5 UNDERGROUND SERVICES**

Utility providers and the farm owner/manager will need to be approached as to the location, line, and level of underground services before commencing operations in a particular area, and take steps necessary to prevent damage to, or accidents arising from, interference with any pipes, cables, ducts, and underground structures.

Permanent relocation of water troughs, water pipes, and irrigation infrastructure may be necessary and relocation arrangements for these agreed with the farmer.

## **6.6 DRAINAGE CONTROL**

Measures should be taken early in the work to maintain the natural water drainage facilities and avoid the introduction of water into the earthworks. Adequate provision should also be made for the control of water-borne soils/silts and the contractor may need to install temporary silt fences to protect waterways from contamination.

In addition, temporary drainage works may be required during construction to control groundwater and surface water and safeguard the integrity of the works. It is important that the earthworks be carried out in such a manner that surfaces have a sufficient fall at all times to shed water and prevent localised ponding.

Where an existing subsoil drainage or drainage path is encountered or will be intercepted, subsoil drains need to be constructed to direct flows away from the constructed fills and embankments. These subsoil drains need to have sufficient fall to prevent blockages and be self-cleaning.

## 6.7 CONSTRUCTION EQUIPMENT

The type of excavating equipment for construction will depend on scale, availability, the design, climate, and physical conditions at the site. Most types of equipment can be used during dry periods. The most common types of equipment used are motorscrapers, bulldozers, and hydraulic excavators.

Construction machinery needs adequate room to work and the type of equipment to be used should be considered in site layout. Compaction equipment should be matched to the fill materials to be compacted as follows:

- Steel-wheeled rollers – suitable on non-cohesive materials such as gravels, but not silts and clays. Vibratory rollers are particularly effective in compacting layers of well-graded gravels
- Tamping (or pad) foot rollers – protruding plates on the roller combines the advantages of both the steel-wheeled and sheepsfoot rollers. Like the sheepsfoot roller, it compacts from the bottom to the top of the lift for uniform density, and like the steel wheel it compacts from the top of the lift. The tamping foot roller is capable of high rolling speeds without throwing material
- Sheepsfoot rollers – protruding studs on the roller drum provide a kneading action. For compaction of plastic soils like clay or silt they are very effective. On granular materials, sheepsfoot rollers tend to shove rather than compact soils. A sheepsfoot roller is required for compaction of cohesive clay materials
- Motorscrapers and excavators – compaction loaded motor scrapers, if available, have the advantage of providing significant compaction along their haul route. The return route of the scraper should be designed to maximise compaction on the constructed bund being formed.

During fill placement operations by an excavator or motor scraper, a separately operated and stand-alone approved roller solely dedicated to compaction should be used to provide continuous compaction during fill placement.

Excavator or dozer track rolling is not suitable machinery for compaction, as tracks are designed to disperse weight rather than concentrate it. Under track rolling, soil layers will tend to not knit together and may result in high air voids. Approved dedicated compaction equipment for the particular material type must be used to achieve the required levels of compaction. A minimum tare weight of 12 tonnes is generally required for compaction equipment.



*Pond construction.*

## 6.8 COMPACTION

### 6.8.1 COMPACTION THEORY

Getting the target compaction at the right water content into the constructed embankment material is the key to providing an embanked pond meeting acceptable stability and permeability requirements.

The relationship between moisture content and density for a given soil under a given level of compaction can be represented by Figure 6.1 below. These graphs are not universal, they are unique to a particular soil (or mix of soils) under a given compaction effort.

Compaction curves shift up and to the left as the compaction effort increases, for example, by an increase in roller size or number of passes. The black curve in Figure 6.1 demonstrates a higher maximum density being achieved than for the red curve. For the same material, the only difference between the two curves is the amount of compactive effort being applied. Also note the effect of moisture on achievable density. If the material is too wet, then the maximum density cannot be achieved. For clay embankments it is better to compact slightly dry of OMC as increased compactive effort can provide a higher density without water being trapped in pores. For sands and gravels it is better to compact over the OMC as excess water can provide particle lubrication while being able to drain away without pore pressure build up.

A Dry Density/Moisture Content (DD/MC) curve can be produced in a laboratory by wetting up samples at different moisture contents and compacting at NZ standard compaction. These samples can also be tested with a shear vane so as to provide a comparative means to check soil strength and moisture content in the field.

The design process should confirm and specify the minimum construction requirements, such as the number and depth of soil layers, the target percentage of maximum density, and the moisture content required to achieve the necessary soil compaction.




Figure 6.1: Dry Density/Moisture Content Relationship

### 6.8.2 COMPACTION TESTING: EMBANKMENTS

Sampling and laboratory testing of the proposed *in situ* fill material to determine the Maximum Dry Density (MDD) and OMC is best done prior to commencing earthworks construction. From these test results the supervising engineer may confirm target values. Table 6.1 provides details of standard tests and rates of testing. These rates for embankment fill testing are the same irrespective of whether a geomembrane or clay liner are to be installed. For clay liner testing refer Part 2, Table 2.

TEST	STANDARD	MINIMUM RATE OF TESTING
Compaction MDD and OMC	NZS 4402.4:1986 Test 4.1.1	One test, but more if material shows any variation
<i>In situ</i> density and voids content	NZS 4407:1991 Test 4.2.1, Direct Transmission Mode	One test per 50 m <sup>2</sup> of surface area of compacted layer, but not less than 10 tests. Minimum of two sets of tests to be taken; at 0% (trial) and 100% of fill placement completion  Acceptance criteria: >95% MDD and $\pm$ 3% of OMC < 6% voids

Table 6.1: Embankment Testing

Alternatively, if MDD results are not available or the fill material is different from the test results available, the supervising engineer may predetermine the compaction requirement by compaction trial.

The contractor should obtain from an IANZ-accredited testing laboratory, or other agency approved by the supervising engineer, sufficient test results and other measurements to show that the construction is in accordance with the drawings and specification. The contractor must supply copies of test results, certificates etc, to the supervising engineer to confirm that materials or works comply before progressing to the next phase of construction.

If the supervising engineer tests any part of the works and finds that it is not in compliance with the specified requirements, the contractor should be made aware that they are liable for the cost of retesting, including any costs incurred by the supervising engineer and principal.

### 6.8.3 COMPACTION TRIAL

A trial strip using the proposed each cut-to-fill or borrow-to-fill material is recommended. This is to determine:

- The effectiveness of the contractor's equipment with the proposed fill materials to achieve the specified compaction density by using a nuclear density meter (NDM) in comparison to the DD/MC test report provided by the supervising engineer
- The number of roller passes necessary to achieve the specified density.

For clay materials, Scala Penetrometer and shear vane readings on the completed trial embankment may provide a useful reference tool for subsequent compaction control, but should not be used for fill compaction acceptance purposes.

The contractors specification should indicate that the contractor will arrange, and pay for, all labour, plant, and materials required to construct and test the trial embankment. If this service is required it should be clearly stated in the contract documents.

#### **6.8.4 CONSTRUCTION GOOD PRACTICE**

It is desirable to keep topsoil separated from subsoil materials during excavation. Topsoil material needs to be placed in a location where it can be accessed after excavation has been completed.

Material should be placed and compacted in progressive, uniform horizontal layers not exceeding 150mm compacted thickness. Careful attention is required to ensure foreign material not intended for compacted fill layers is not mixed with fill material to prevent modifying the properties of the intended fill material.

Pond banks and crests are best formed by over-constructing and trimming back later to the required level and slopes. Final trimming and static rolling is required to produce an even and tight surface.

The finished top bank width should be more than the roller width. For safety, the bank should be made over dimension so that the roller does not need to work right to the outer edges of the bank since these will be trimmed back later. The crest (embankment top) should also be slightly sloped back throughout construction to prevent rainfall flowing back into the pond.

Compaction should not continue if the material shows signs of heaving or weaving excessively. In this situation, the material should either be left to dry naturally or, where work progress would be affected by a delay, the material should be dried to a moisture content at which heaving and weaving does not occur.

Fill surfaces and materials must be protected from becoming wetter than OMC. If materials become wet, continuing with compaction becomes counterproductive and the required soil densities will not be achieved. Valuable time will be lost in waiting for excessive built-up pore pressures (as evidenced by surface heaving and rutting) to dissipate. The moisture content to achieve optimum compaction needs to be continually monitored during construction.

It is good practice to seal off and slope surfaces away from the works at the end of the day or at the onset of rain. Wet material can be dried either by mixing in drier material or spreading out the wet material in a loose state on a warm or windy day to allow drying. Careful mixing in of small quantities of bentonite can also be beneficial with some materials.

After the bulk earthworks have been completed, topsoil should be placed on the back slope surface and sown out in grass to provide erosion control. Any shrubs or trees (including their roots) need to be cleared well back from the embankment.

### **6.9 EXPOSED BATTERS**

The exposed batters and crests of embankments should be topsoiled and revegetated as soon as possible after construction, then grassed, hydroseeded, or suitably protected to prevent erosion from rainfall, wind, or frost damage.

The back slope batter may be flattened further than the specified slope angle by the placement of excess topsoil and other surplus fill material, but only if it is well compacted, surface-trimmed, and levelled.

## 6.10 FENCES AND GATES

The construction area should remain stock-proof at all times and the contractor should note that some temporary fencing may be necessary to achieve this. All temporary fencing needs to be removed by the contractor prior to works completion.

Fences and gates, as an access safety measure, will need to be installed in the locations as shown on the construction drawings either by the contractor or the principal by agreement.

At project completion, any exposed old post holes require filling, the site should be left in a smooth, tidy surface condition, and redundant fencing-related materials should be removed from the site.

## 6.11 PRACTICAL COMPLETION AND DEFECTS LIABILITY CERTIFICATES

If NZS 3910 (or NZS 3915) is being used on the contract, and it is recommended that it is, then Practical Completion and Defects Liability Certificates will need to be prepared by the supervising engineer. The process for its issuing is as described in the NZS 3910 (General Conditions of Contract). A link to Standards New Zealand Website is contained in the References section under Pond Design and Construction.

The SQP should assess that all the following items (if specified) have been attended to:

- Topsoiling, grassing, and tidy smoothing up of the embankment and surrounds
- Completion of all work specified or scheduled in the contract documents
- Meeting all consent requirements
- That the principal is satisfied with the completed construction.

The defects liability certificate is due for the contract works (or any separable portion) when minor omissions or defects have been repaired and the period of defects liability has expired. The period is typically six months, but could be longer depending on local conditions.

### KEY POINTS

- Allow for local weather conditions.
- Match appropriate compaction equipment with fill material type.
- Monitor compaction, confirm with laboratory testing.
- Pay special attention to pipe penetration areas through embankments and liners.
- Issue practical completion and Defects Liability Certificates on satisfactory completion of all specified work.

# 7.0 Certification

## 7.1 INTRODUCTION

Many pond owners may be satisfied with what they can visually see, supported by the judgement and trust of the construction contractor involved. However, some regulatory authorities specify certification of the work. This certification will generally be beyond the expertise of the owner and/or some contractors.

Institutions with a financial interest in a farm, including banks and insurers, may also require formal certification to ensure that exposure to physical, financial, and legal risks has been appropriately managed and minimised. This can include certification by an engineer where appropriate, and certificates of compliance from councils to verify that regulatory requirements under the RMA have been met. Certification under the BA has other certification requirements and approaches.

Where RCs require formal sign-off for the design and construction for ponds for which the BA does not apply, then verification by a SQP is recommended. Defining who constitutes an SQP is necessary and this Practice Note proposes the following definition:

“A person with the necessary competence, relevant qualifications, knowledge, skills, experience, and understanding of soils, engineering materials and structures to design and supervise the construction of effluent containment systems such that they are fit for purpose, structurally sound, and meet all regulatory requirements. They shall be either a CPEng or an Engineering Technology Practitioner (ETPract), or Regional and District Councils may wish to individually approve other local practitioners as an SQP due to their long-standing demonstration of these attributes.”

For pond owners where verification that structures including some ponds, tanks, and dams meet the BA requirements, certification by a CPEng is the recognised process to verify that all regulatory, design, and construction standards have been met.

A summary of design and construction certification requirements is set out in Figure 7.1.

This Practice Note focuses on the construction of new ponds and while it may provide guidance of expected standards of existing ponds, it is not intended to be a retrospective design guide. The same rationale applies to certification, with the recommendations for certification below applying to the construction of new ponds.

## 7.2 CERTIFICATION UNDER THE RMA BY REGIONAL COUNCILS

The acceptance of the design and construction of ponds in some regions is covered by the RC and left to a FDE practitioner to use industry accepted codes, such as NZS 4431 (Code of Practice for Earth Fill for Residential Development) and section 2 of NZS 4404 (Land Development and Subdivision Engineering), or specific design principles where applicable. Due to the variability associated with the materials used for construction, some element of specific design is required for each application. NZS 4431, while specific to residential development, does give prudent guidance on the construction of earthfills for bulk earthworks. It should not be used for clay liner placement as that is specific design based on the clay material used.

While suppliers and installers of synthetic and concrete pond liners will normally be able to provide their own certification of permeability, earthen pond liners provide a significant challenge. Councils do not specify the method or means by which such permeability is to be measured; they typically require certification by an engineer that the specified permeability rate is not exceeded.

This Practice Note recommends that that an SQP completes a Producer Statement (Design) and Producer Statement (Pond Construction Review). Examples of suitable forms for Producer Statements for SQPs are contained in Appendix B.

To provide continuity between the design and construction phases it is preferable, but not essential, that the same SQP be involved throughout the project. However, only one SQP can sign off on each or both phases.

## 7.3 CERTIFICATION UNDER THE BUILDING ACT

As with the RMA, different aspects of the BA are administered by regional and district councils respectively.

### 7.3.1 CERTIFICATION BY REGIONAL COUNCILS

The focus of the regulation of ponds by RCs under the BA is the safety and integrity of dams. Specific regulations and requirements are discussed in section 3.

If a pond is not a “large dam”(as categorised by Table 3.5), then there is no requirement for a Building Consent to be granted by the RC. However, with a structure that is “not a dam” or a “dam”, there is still a requirement for it to be constructed to meet the performance requirements of the under section 17 of the *Building Code*.

Compliance with the *Building Code* for a pond or dam is left to a dam owner’s judgement in that there is no requirement for any BCA approval or confirmation that those requirements have been met. However, persons or institutions with a financial interest in a farm, including banks and insurers and prospective farm purchasers doing due diligence, may well have an interest in seeing formal confirmation that a pond has in fact met *Building Code* requirements. A physical failure of a dam has the potential to bring about an investigation by the RC, and a dam owner who is unable to provide documentary evidence of *Building Code* compliance will potentially be in difficulty.

### 7.3.2 PRODUCER STATEMENTS FOR BUILDING CONSENT AUTHORITIES

The Producer Statement process is intended to provide BCAs with reasonable grounds for the issue of a Building Consent or a Code Compliance Certificate, without having to duplicate design or construction checking undertaken by others. The four categories of Producer Statement are:

- PS1 (Design)
- PS2 (Design Review)
- PS3 (Construction)
- PS4 (Construction Review).

For the certification of the design and construction of tanks, ponds, or dams under the BA, PS1 and PS4 should be produced, whether required for a Building Consent or simply to establish *Building Code* compliance where consent was not required. These statements will be appropriate whether the pond involves a dam or not, and whether the BCA is the RC or the DC.

These statements should also be appropriate to meet any engineering requirements of DCs under the RMA, and should similarly meet any earthworks certification requirements of councils under the RMA.

Generally only a CPEng has the legal authority to sign-off on such Producer Statements (that is, PS1 to PS4). The Producer Statements forms in Appendix B are intended for SQPs to complete are not for this purpose.

## 7.4 CERTIFICATION BY CONSTRUCTION CONTRACTOR

If an FDE pond is constructed by contractors, and either NZS 3910 or NZS 3915 is used as a form of contract, then the SQP should seek a Producer Statement in the form of Schedule 6 from the contractor. As-built plans should also be requested.

If an FDE pond and any ancillary works are to be constructed under another contractual arrangement, for example, the principal is undertaking his own management of the contractor, then a Producer Statement should still be provided by the contractor. A suitable Producer Statement form for construction signoff for contractors to use is in Appendix B. The significance of the Producer Statement should be discussed between the SQP, contractor and the principal prior to work commencement.

Should a liner be installed separately to the pond contractor's scope of work, then installers of such a liner will need to provide the necessary certification in the form of a Producer Statement to the SQP on behalf of the principal.

Where components of a structure are supplied by a manufacturer and are to be incorporated into the contractor's works, for example, precast concrete panels, then the BCA may require Producer Statements for these as part of the Building Consent sign-off before the issuing a Code of Compliance Certificate.

## 7.5 CERTIFICATION FOR POND DESIGN AND CONSTRUCTION REVIEW

IPENZ has an industry-recognised and respected accreditation system providing competence-based registers for engineers. Two of these registers are appropriate to apply to FDE pond design and construction; these being CPEng and ETPract. These two quality marks can provide both Regional and District councils with the confidence needed to accept the design and construction of FDE ponds, but only where ponds are exempt from Building Consents.

Both CPEng and ETPract persons are bound by ethical guidelines to only certify work that they are competent in, that is, within their practice area, providing further reassurance to councils. For links to the IPENZ Code of Ethics and ethical obligations refer to the References section.

As a further note, DairyNZ has developed an accreditation process for companies who are designers of FDE systems. This programme is primarily aimed at FDE land application systems, but not at pond design and construction, and allows the participation of rural professionals and contractors who do not necessarily have professional engineering qualifications.

### KEY POINTS

- An SQP needs to be engaged prior to design and construction.
- Practitioners need to be ethical at all times.
- Check that regional and district council requirements are being met.
- The SQP and contractor(s) need to provide Producer Statements for their work.

### Summary of Design and Construction Certification Requirements




Figure 7.1: Summary of Design and Construction Certification Requirements

# 8.0 Operation and Maintenance

## 8.1 INTRODUCTION

This section provides a brief summary of what needs to be considered for the effective operation and maintenance of FDE ponds.

## 8.2 AS-BUILT PLANS

As-built plans of the FDE pond should be supplied by the pond construction contractor to the client upon completion. These provide a valuable record and assists with operations, inspections, and monitoring.

As-built plans should include:

- Key levels of base and embankment crests in relation to datum, for example, a level at the dairy shed, so any future settlement or impact of pond cleaning can be assessed
- Location, depth, and diameter of all pipes entering and leaving the pond
- Location of power cables
- Details of any under-drainage and gas drain provision
- Location of subsoil drains and leak detection features.

## 8.3 OPERATION MANUAL

An FDE operation manual should be prepared by the SQP and the equipment and service suppliers in consultation with the principal. All dairy farm staff should be familiar with the manual. One of the most important aspects to include is where and how sludge is to be removed. This includes:

- Where the pond may be accessed for desludging, including providing a plan which can be copied for contractors
- How and what equipment may (and may not) be used
- The location where the removed sludge is to be deposited
- The appropriate method and depth of sludge spreading
- Pond area groundwater monitoring.

The operation manual should also include information on:

- Frequency for the drop test (yearly generally, but more frequently if stirrers and regular mechanical desludging takes place)
- Contact details for repair of synthetic liners
- Maintenance requirements for pumps, valves, and mixers
- Vegetation control
- Meeting and monitoring resource consent conditions.

## 8.4 INSPECTIONS

The following inspections should be carried out by farm management staff, and results recorded so they can be supplied to consent compliance staff if necessary:

- Monthly inspection for general condition (photographs will help to track changes over time)
- After any desludging operation, looking for any obvious signs of damage
- After any unusually heavy rain (for example, >50 mm in 24 hours).

As a minimum, the following items should be checked during an inspection:

- Pond level – is there sufficient freeboard? Consider if it should be as empty as it is or if there could be groundwater ingress raising the water level
- Maintenance of vehicle access and crest of the pond– to allow easy desludging equipment access, including in an emergency
- Synthetic liners – no tugging or tearing is present from anchor trench, no visible or obvious damage to liner
- Clay liners – no excessive erosion, drying, cracking, or damage to liner
- Pipework – check for leaks or damage to pipes
- Bunds – no obvious bund failures or damage
- Modifications – have there been any recent modifications to the pond that have not been recorded?

The New Zealand Society on Large Dams (NZSOLD) publication *Guidelines on Inspecting Small Dams* gives a general overview of what to look for, and why, when inspecting a small dam.

## 8.5 POND MONITORING

Changes in colour, appearance and odour of a pond contents, as well as significant changes in level, can be indicators of issues with the system.

Wet swampy patches or particularly lush areas of grass can be indicators of leaks. These should be investigated early to avoid unnecessary damage to the liner.

Loss of freeboard requires urgent attention by farm management staff. While high-level alarms that can be monitored remotely could be installed to monitor this, a simple level indicator may also be appropriate.

The water level in storage ponds should be monitored regularly, along with groundwater heights and sludge depths. Monitoring of effluent levels allows any seepage losses to be readily detected and corrected. To monitor groundwater, a shallow (up to three-metre) slotted PVC pipe in which depth is measured is satisfactory. Monitor these levels monthly during wet periods when water tables are likely to rise.

## 8.6 LEAKAGE DETECTION AND RESPONSE

In the event that surveillance, either by drop test, obvious seepage, or monitoring beneath the liner, gives concerns that the pond may be leaking, then remedial action will be necessary.

The first action should be to pump the pond's water level right down, and for a synthetic-lined pond, clean out the base, then visually inspect the lining. A clay liner may show obvious damage from machinery or erosion. Repair of damage to clay liners could involve placing more clay and compacting in with a plate compactor (if localised), placing GCL sheet, or if more extensive, ripping and re-compacting the liner. Major repair of clay liners should involve an experienced practitioner.

Damage to a synthetic liner can be difficult to pick up. While damage such as a tear or large penetration by machinery might be easy to see, some damage such as pinholes or defective welds will be less obvious. Inspection by the liner installer may be helpful. Alternatively, if the groundwater outside the liner is high, then defects will show as water weeping back into the pond. Repairs to synthetic liners should only be carried out by an experienced liner installer.

## 8.7 DROP TEST

A drop test will be unsuitable to verify that a liner has achieved the recommended maximum leakage rate due to wave movement, evaporation and the limitations of measuring very small changes in level accurately. However, a carefully run drop test will indicate if there is gross leakage, being a large single-point leakage, or a number of smaller leaks in a liner. While a drop test may be carried out at any liquid level within the pond, the worst case situation will be when the pond is up to freeboard level. This will be the level where leaks will be more easily detected if there are any.

The procedure for a drop test is as follows:

- Shut off any liquid inflows, including rainwater diversion (if in place)
- Choose a period of likely fine weather and preferably when cows are dry
- Securely fix an accurate water-level recording device at a suitable calm location
- To measure evaporation, fill a container of approximately 500 mm diameter by at least 300 mm deep with liquid from the pond to within 100 mm of top, weigh or measure level and float in pond
- Record change in level, ideally over 24 hours.

After allowing for evaporative loss, the water drop should be negligible (that is, less than one millimetre) for a pond with no discernable leakage.

The following information should be collected for a drop test:

- Name of tester and date
- Dimensions of pond – length by width by depth
- Depth and type of clay
- Depth to groundwater
- Test methodology
- Local weather conditions, including rainfall measurement, wind, temperature, and barometric pressure
- Calibration of the water-level recorder
- Graph showing level fluctuations with corrections over the test period
- Testing should run for at least 48 hours, although a longer period may provide a more definitive result.

## 8.8 SYSTEM OPERATION

### 8.8.1 TREATMENT LEVELS

To ensure that the FDE pond system is operating effectively and treatment levels are maintained, the following measures must be undertaken:

- Carry out desludging at regular intervals
- Correct operation of upstream solids removal to maintain settling
- Diligent use of rainwater diverters to avoid hydraulic shocks
- Maintenance of aeration and/or mixing systems.

### 8.8.2 DESLUDGING

Monitoring sludge depths is critical to ensuring sufficient room in the pond for heavy rain. As sludge accumulates, the capacity for effluent diminishes, so ponds must be regularly desludged.

The desludging of an FDE pond will be carried out by pumping the contents (including stirring) or digging out the sludge. Care should be taken to ensure that the desludging process does not damage the embankment or liner. It is recommended that a concrete base be constructed where ponds are designed to be desludged with machinery. The installation of a concrete base is also recommended beneath the pump and/or stirrer to avoid damage to liner.

Sand traps must be cleaned regularly. A programme of sand and grit removal at the front end of the effluent treatment system avoids carryover of these abrasive solids, which have very detrimental effects on pumps, pipes, and valves, and adds to the solids on the bottom of the ponds.

### 8.8.3 ODOURS

If an FDE pond becomes anaerobic it may give rise to odour. In order to minimise the incidence and effect of odour, FDE pond design should take account of location and operational measures.

In a traditional FDE two-pond system there is usually little incidence of odour. This is because the pond crusts over and the floating solids ensure the slow release of gas. Generally, odour only occurs in short duration during desludging.

With a clear water holding pond, solids which could crust will have been removed, but soluble organics and ammoniacal nitrogen remain and the deeper waters will rapidly go anaerobic. Gradual mixing of the effluent within the pond will help aerate the liquid and remove and/or convert the ammonia from the pond. This may lead to a brief instance of odour. At these times consideration should be given to prevailing winds and potentially affected parties in the proximity of the pond.

Regular desludging, varying the level of effluent and turnover of liquid within the pond will also help reduce the incidence of odour. Transfer sumps should be operated with a minimal range so that effluent is mixed and pumped daily.

## 8.9 EXISTING FDE PONDS

If an existing FDE pond is to be used as part of a new or upgraded system, it will need to be demonstrated that it meets the leakage criteria. The FDE pond will also be required to meet the relevant regulatory standards.

If the FDE pond has not been certified by an SQP, the engineer will need to inspect and test the pond and, if appropriate, provide certification.

#### KEY POINTS

- Provide detailed plans and specifications.
- Develop an operation manual that includes a desludging plan.
- Encourage regular monitoring of pond for leakage.
- Stirring the pond can avoid odour.
- Keep pond volumes low during summer to allow filling during wet periods when soil saturated and unable to irrigate onto land.

# 9.0 Forms of Contract

## 9.1 SCOPE OF WORK AND PRACTITIONER ENGAGEMENT

The rural sector is very much relationship-based and these people expect others to keep their word. However, this characteristic can be a problem because with a relatively new area like certified pond construction, which farmers are generally unfamiliar with, there is a real risk of disappointing outcomes for them.

It is important that the client clearly understands the scope of work proposed, the programme, and the fee basis for the services being offered by the FDE-related services provider, whether they be an engineering consultant, a pond contractor, or a liner installation company. A formal written contract between the parties is a must. For FDE ponds, the most appropriate form of client and consultant engagement contract is the IPENZ Short Form Agreement for Consultant Engagement and is contained in Appendix A. Product suppliers will have their own forms for this purpose.

The scope of services to be provided by the practitioner should be clearly documented and agreed to by the client so that there is full understanding by both parties from the outset. If working through a farm management agent, then the engagement, design decisions, project management, and responsibility will need to be clearly defined.

For the services provided by a practitioner, the following elements should be included in the scope of services, unless excluded by agreement:

- Evaluation of the existing system if applicable
- Identification of improvement options/advise and best-practice systems
- Survey and geotechnical investigations
- Design
- Tendering and tender evaluation/recommendation
- Construction supervision
- SQP certification and reporting
- An operation and maintenance manual.

Research indicates that substantial savings can be made to the total project cost through good definition of the project at the initial stage. If the issues are properly considered and agreed at the start of the project, there is a greater likelihood that relationships will develop positively, greater assurance that the client's expectations can be satisfied throughout the project, and a successful conclusion for all parties.

## 9.2 ETHICS

Clients typically rely on relative strangers for significant services in circumstances under which they cannot assess the expertise or diligence of the service. This amounts to a significant risk for the client and this is why IPENZ Members are required to avoid conflicts of interest and display expertise and trustworthiness. Ethical practice is not an optional extra. *IPENZ Practice Note 08* (refer to section 10) further describes these obligations.

## 9.3 CONTRACTOR SELECTION

Where there are aspects of the work which will be undertaken by others, such as supply and installation of pumps to the FDE pond, it needs to be clearly defined who the parties are directly working for, that is, either the practitioner or the client. In many cases, problems arise at the interface between the services that the SQP and supplier are providing on the ground.

Similarly there needs to be an initial discussion and subsequent agreement around how the physical works/contractor(s) are going to be selected and managed. Where specialist contractors are to be engaged, for example, a synthetic lining contractor or a pump installer, who is going to project manage them – the practitioner, the main contractor, or the client?

Some farmers may wish to project manage the construction work themselves. In this case the practitioner will provide the design inputs and/or the final sign-off. The engineer should be careful with such arrangements as they still need to be able to carry out periodic inspections and be able to influence the quality of the construction as it proceeds.

The level of construction monitoring for the pond works should be determined early in the design discussions and may be determined by the engineer's confidence in the proposed contractors. The IPENZ guide to construction monitoring services can be found in the References section.

Physical works contractor selection can take many forms and it is wise to discuss this with the client first.

If the client has a preferred contractor and does not wish to approach any other contractor, it is still important to prepare and supply the contractor with the following, as a minimum:

- Construction drawings
- Schedule of quantities
- Written agreement (NZS 3910, NZS 3915 or supplier/buyer agreement).

If a client wishes to have the physical works competitively tendered, then either invited tenders or open tenders could be appropriate. A full contract document under either NZS 3910 or NZS 3915 is recommended.

Tender evaluation may be solely based on price; however, in some cases where a particularly difficult pond is to be constructed, track record and methodology evaluations may be appropriate. It would be important to get the client's expressed agreement for this, to ensure they understand the value this approach would bring.

## 9.4 CONTRACTOR ENGAGEMENT

The principal, the contractor doing the physical works, and the engineer need to have their roles and responsibilities clearly defined before construction work commences. It is suggested that the traditional rural way of accepting a contractor verbal offer by way of a handshake with no written agreement in place, is not good practice. Given the cost of larger FDE ponds, and the risks involved with poor construction, it is not recommended that contractors be engaged in such a way.

NZS 3910 (Standard Conditions of Contract for Building and Civil Engineering Construction) is the benchmark for construction contracts that have the engineer to the contract defined. It clearly defines the contractual relationship between a principal, the contractor, and the engineer and defines their rights, obligations and communications. Furthermore it sets out procedures to for issues such as payments, insurance, defects liability, and dispute resolution.

NZS 3910 is written using terms that are well understood and has been tested before the courts. The Standard was developed by industry peers that included representation from central and local government, professional and consulting engineers, contractors, and many others to produce a document that is acknowledged as one of the fairest forms of contract in use.

Construction industry leaders promote the use of NZS 3910 in its standard form as an equitable form of contract that is well-tested and fair, and provides certainty to all parties. Given the variability in some effluent pond projects, NZS 3910 also provides an excellent framework to value variations in a way that is fair and reasonable to both the principal and the contractor.

However, NZS 3910 can be quite complex for some clients used to a verbal contract; and for those not willing, or if the scope of works are relatively small, then NZS 3915 can be used as this still provides the relevant contractual engagements, legal status, and responsibilities of the relevant parties.

In both documents there are certification records required from the contractor on completion of works in the form of a Producer Statement, which can be found in Schedule 6 of NZS 3910.

A defects liability period should also be utilised to provide a mechanism for the repair of defects not obvious at the completion of physical works. A period of 26 weeks is usually adequate for FDE ponds.

The requirement for the contractor to provide insurance is also important, and provides reassurance to both the client and the contractor if anything unexpected occurs. It is expected that the contractor have the following insurances in place:

- Contract works (for larger projects)
- Public liability
- Plant and machinery
- Motor vehicle third party liability.

The inclusion of liquidated damages is worthwhile and may be appropriate for time or economically sensitive contracts, as is a construction programme and completion date. An allowance for inclement weather is usually provided.

## 9.5 NZS 4431 (CODE OF PRACTICE FOR EARTH FILL FOR RESIDENTIAL DEVELOPMENT)

NZS 4431 is a guiding document written to provide a proven methodology for the placement and certification of fill, specifically for residential development. It can be used as a simple guide by all parties involved to ensure any fill placed is done so appropriately.

### KEY POINTS

- Clearly define the scope of work offered.
- Signed formal agreement between practitioner/principal.
- Engage contractor under a formal contract, for example, NZS 3910.

# PART 2

## **Clay Liners for Ponds**



# 1.0 Introduction

## 1.1 Introduction

Clay liners for Farm Dairy Effluent (FDE) ponds can sometimes be an effective and economical method for dairy effluent storage. Clay can be highly variable and so it is essential that thorough testing is undertaken prior to and throughout construction of a clay liner. The costs of locating suitable clay sources and subsequent construction will also need to be considered relative to other pond lining options available such as geomembranes.

It is expected that in the future, older clay-lined effluent ponds on New Zealand dairy farms will come under increased scrutiny by Regional Councils as they tighten their FDE storage containment rules. Presently, compliance with containment rules is complicated by some industry confusion concerning the various terms used in relation to storage ponds. Some Regional Council's rules cite seepage or leakage rates, while others use permeability or hydraulic conductivity rates with numbers such as  $1 \times 10^{-9}$  m/s or  $1 \times 10^{-8}$  m/s, while yet others are nonspecific.

Part 2 sets out guidelines for good practice clay liner investigation, design and construction and should be read in conjunction with the whole of *IPENZ Practice Note 21: Farm Dairy Effluent Ponds*.

### KEY POINTS

Clay lining of FDE ponds can be successfully completed if the following key points are met:

- Investigations and full laboratory testing of the proposed clay source is undertaken
- The clay liner meets all laboratory test criteria, especially particle size and permeability requirements
- The minimum total thickness of clay liner to meet Regional Council's seepage (leakage) or hydraulic conductivity (permeability) requirements needs to be specifically calculated for each site, but should not be less than 450 mm thick
- The clay is constructed with a minimum of three evenly compacted layers
- Cover or armouring material of sufficient thickness is spread over the clay lining to protect it from scouring, drying out and cracking
- A Quality Control testing programme is undertaken during liner construction to confirm compaction acceptance
- Design and construction personnel required to check and approve the work are actively involved in the project.

# 2.0 Design Calculations

## 2.1 Hydraulic Conductivity

Hydraulic conductivity is a measure of a soil's ability to transmit water when subject to a hydraulic gradient. The figure below describes the usual relationship between soil types and their inferred hydraulic conductivity, and drainage capability.

Hydraulic Conductivity (m/s)									
1.E-10	1.E-09	1.E-08	1.E-07	1.E-06	1.E-05	1.E-04	1.E-03	1.E-02	1.E-01
Low pervious		Semi pervious				Pervious			
Compacted Earth	Most Soils					Drainage Materials			
Compact Clay	Stratified Clay	Clay Loams	Silt Loams, Loess	Sandy Loams	Sand & Gravel Mixture	Clean Sands		Gravel	
				Low pervious					
Notes: This is a general guide only and should not be relied upon. Hydraulic conductivity in soils can vary due to changes in seepage fluid viscosity and soil water content.									

Figure 2.1: Hydraulic Conductivity of Soils (Table adapted from FAO Training Series – Chapter 9: Soil Permeability)

## 2.2 Seepage Calculation

The term “hydraulic conductivity” is often used interchangeably with “permeability” when water is the seepage fluid. Regional Council rules usually quote maximum permeability values, as acceptance normally relies on undertaking permeability tests on a clay-liner sample using water as the seepage fluid in the laboratory.

The terms “seepage” and “leakage” rates are also used interchangeably and are a measure of the flux. Flux is the rate of flow per unit area. No liner systems, including geomembranes, are completely impermeable and all will have some seepage, albeit very low. Where the seepage rate reaches a predetermined unacceptable value, then, for descriptive purposes, it might be renamed the leakage rate.

Seepage rate has a direct relationship with the hydraulic conductivity of a soil but also includes the head of pressure, that is depth of the pond, and thickness of the clay liner. It is expressed as:

$$v = k \times \frac{\Delta h}{\Delta l}$$

$v$  = seepage (or leakage) rate ( $m/s$ )

Note: ( $v$ ) is also referred to as the flux which is the rate of flow per unit area

$k$  = hydraulic conductivity (also known as permeability) ( $m/s$ )

$\Delta h$  = vertical height from pond surface to base of liner ( $m$ )

$\Delta l$  = liner thickness ( $m$ )

Furthermore:

$$q = k \times \frac{\Delta h}{\Delta l} \times A = v \times A$$

$q$  = flow rate ( $m^3/s$  or  $litres/day$ )

$A$  = area ( $m^2$ )

Example:

What is the seepage rate ( $v$ ) from a pond that has:

Clay permeability ( $k$ ) =  $1 \times 10^{-9} m/s$ , Pond depth = 3.0m, Liner thickness ( $\Delta l$ ) = 450mm

$$\begin{aligned} \text{Seepage rate (v)} &= \frac{\text{Hydraulic conductivity (k)} \times (\text{pond depth} + \text{liner thickness } \Delta l)}{\text{liner thickness } \Delta l} \\ &= 1 \times 10^{-9} m/s \times (3.0 + 0.45 \text{ m}) / 0.45 \text{ m} \\ &= 7.6 \times 10^{-9} m/s \\ \text{or} &= 7.6 \times 10^{-9} \times (1,000 \times 60 \times 60 \times 24) \text{ mm/day} \\ &= 0.7 \text{ mm/day} \end{aligned}$$

## 2.3 Flow and Seepage With Varying Hydraulic Conductivity

The relationship between seepage rate and typical hydraulic conductivity rates, assuming a constant clay layer thickness, is plotted in Figure 2.2. For illustrative purposes only, it is based on a water filled pond of theoretical surface area  $1,000 m^2$  (for example  $40 m \times 25 m$ )  $\times 3 m$  deep with impermeable vertical walls. It also assumes that the material under and supporting the clay liner is free draining and does not affect the hydraulic conductivity of the liner.




Figure 2.2: Flow ( $q$ ) and Seepage ( $v$ ) Rate with Varying Hydraulic Conductivity ( $k$ )

Note that there is a factor of 10 in the increased amount of seepage between each hydraulic conductivity exponent value. For example,  $1 \times 10^{-7} \text{ m/s}$  is 10 times more permeable than  $1 \times 10^{-8} \text{ m/s}$ . Seepage rate also increases with increasing head of water, so therefore a pond that is actively managed to operate at a lower surface level will seep at a lower rate than one that is operated near full.

Again for illustrative purposes only, Figure 2.3 graphs the effect of varying both clay liner thickness and hydraulic conductivity of the soil, with the head of water up to three metres. To further demonstrate, the accompanying Table 2.1 shows what the calculated flow rates ( $q$ ) would be.

Note that seepage rate ( $v$ ) is independent of the surface area of the pond. However for a proportionately larger sized pond, the flow rate ( $q$ ) will be higher as the surface area ( $A$ ) is used in the calculation.




Figure 2.3: Flow ( $q$ ) and Seepage ( $v$ ) Rate with Varying Clay Liner Thickness and Hydraulic Conductivity ( $k$ )

	Hydraulic Conductivity ( $k$ ) (m/s)	
	$1 \times 10^{-8}$	$1 \times 10^{-9}$
Clay Liner Thickness ( $\Delta l$ ) (mm)	FLOW ( $q$ ) (litres/day) (with 3m Head of Water)	
150	17,280	1,730
300	8,640	860
450	5,760	580

Table 2.1: Flow ( $q$ ) with Varying Clay Liner Thickness and Hydraulic Conductivity( $k$ )

Note: These are theoretical flow rates through a clay layer. They have been calculated in isolation of material under the clay liner that could affect the seepage rate.

# 3.0 Investigation and Testing

## 3.1 Investigation

Excavating a number of trial pits over the proposed borrow-area site is essential to investigate potential sources of clay liner. Materials can be quite variable, even within a short distance. A trial pit allows a large sample of the soil to be logged, sampled and tested. It also provides an indication of other conditions that may affect construction, such as groundwater levels, stability of excavations, *in situ* water contents of the proposed clay and how difficult materials may be to excavate.

(Materials investigations are further explained in Part 1 section 4.4 Field Investigation Steps.)



*Investigation trial pit*

## 3.2 Laboratory Testing

If it is proposed to use a local soil as a clay liner then a suite of laboratory tests must be undertaken on representative samples to determine their engineering properties and confirm their test properties meet acceptable criteria.

Table 3.1 provides a guide to the tests that should be undertaken and their test result criteria. The pond designer will need to make their own judgement concerning the numbers of each test undertaken based on such issues as: familiarity with local materials and their performance; size of the pond; material variability; and the proposed pond-liner design.

The suitability of clay materials displaying test values outside of these recommended test result criteria should be subject to specific assessment by a geotechnical engineer.

Test Method	Minimum Test Frequency	Minimum Sample Mass for Testing	Recommended Test Result Criteria
<b>Trial Pits</b>	1 per 500 m <sup>3</sup> of clay, minimum 4 pits		Demonstrate sufficient volume of suitable clay available
<b>Particle Size Distribution</b> NZS 4402:1988 Test 2.8.1 NZS 4402:1988 Test 2.8.4	1 test of each material type	1 kg for clays	>55% passing 0.06 mm >20% passing 0.002 mm Negligible gravel
<b>Plasticity Limits</b> NZS 4402:1988 Test 2.2-1 NZS 4402:1988 Test 2.4-1	2 tests of each material type	500 g	Liquid Limit: 30% – 60% Plasticity Index: 15% – 30%
<b>Linear Shrinkage</b> NZS 4402:1988 Test 2.6	1 test of each material type	500 g	Linear Shrinkage <15%
<b>Standard Compaction Test</b> NZS 4402:1988 Test 4.1.1 NZS 4402:1988 Test 2.1	1 test of each material type	25 kg	Optimum Water Content (OWC) and Maximum Dry Density (MDD) (Water content and shear vane tests at each water content point between –2% to +6% wet of OMC)
<b>Solid Density</b> NZS 4402:1988 Test 2.7.2	1 test of each material type	500 g	Required for Air Voids calculation
<b>Permeability (Triaxial) Test</b> ASTM D5084-03 Method A or, BS 1377:1990 Part 6	1 test of each material type	2 kg	$k < 1 \times 10^{-9}$ m/s Note: some Regional Councils may allow other values, or other acceptance methods (Compaction DD typically at 95% of MDD and +2% wet of OWC)
<b>Pinhole Dispersion</b> ASTM D4647-93 Method A or, BS 1377:5	1 test of each material type	500 g	Non-Dispersive ND1 or ND2

Table 3.1: Clay liners – Laboratory Tests for Clay Liner Suitability

### 3.2.1 PARTICLE SIZE DISTRIBUTION

Test results from a soil grading (also known as a particle size distribution), is the single most important criteria to consider for clay liner suitability. The grading of soil samples down to silt size is undertaken using sieves to separate the soil into separate particle sizes. The smaller silt and clay sized particles (that is below the 0.063-millimetre sieve), may require a separate hydrometer test to determine if there is a sufficient percentage of clay size particles present.

Figure 3.1 below shows a typical full particle size distribution curve.




Figure 3.1: Example Particle Size Distribution for a Clay-Liner Sample

As a guide, a suitable clay liner soil should have:

- Greater than 55% passing 0.06 millimetres, that is the clay + silt fraction
- Greater than 20% passing 0.002 millimetres, that is the clay fraction
- Negligible gravel
- Free of topsoil, tree roots and organic matter.

### 3.2.2 PLASTICITY LIMITS

If the water content of a clay is gradually dried back from being very wet, the clay passes from a liquid state, through a plastic state and, finally' into a solid state. A sequence of tests has been developed to define the boundaries between the plastic and liquid states; these can be used as a basis to classify engineering soils.

#### Plastic Limit

The transition between a dry crumbly state and a plastic deformable state is known as the plastic limit (PL). It is defined as the water content at which a sample of soil begins to crumble when rolled to a three millimetre thread. As a guide, if a finely worked soil with adequate clay content can be kneaded and rolled into a thread of three millimetres in diameter and not crumble, the water content is likely to be close to the plastic limit. Being able to roll a finer worm than this indicates excess water for optimum compaction.

#### Liquid Limit

The water content of the soil at the transition between a liquid state and plastic state is known as the liquid limit (LL). It is defined in the laboratory by the water content at which the clay begins to flow under certain test conditions.

For clay lining the LL of the soil should be in the range 30% to 60%.

### Plastic Index

The range of water contents within which a soil acts as a plastic material is called the plasticity index (*PI*) and is defined as:

$$\text{Plastic Index (PI)} = \text{Liquid Limit (LL)} - \text{Plastic Limit (PL)}$$

Soils with very low plasticity ( $PI < 10\%$ ) are unlikely to produce a low permeability clay liner when compacted.

Soils with high plasticity index ( $PI > 40\%$ ) tend to form hard clods when dried, and sticky clods when wet. Highly plastic soils also tend to shrink and swell when dried and wetted up.

The plasticity chart below provides a useful guide to classify soils based on their engineering properties and identifies a preferred range in which a clay liner's plasticity limits should lie.




Figure 3.2: Plasticity Chart for Classifying Fine Grained Soils

### 3.2.3 LINEAR SHRINKAGE

Clays tend to swell and shrink as they absorb or lose water. For FDE ponds, the potential risk is that drying of the clay liner can cause shrinkage and cracking that leads to significant leakage.

The linear shrinkage measures the percentage decrease in length of a soil core as it changes from the liquid limit state to an oven dry state. Clay soils with a linear shrinkage greater than 15% and a liquid limit greater than 60% are considered particularly susceptible to volume change, and hence cracking from wetting and drying.

Less than 10% shrinkage is considered low and is unlikely to be significant assuming satisfactory compaction has occurred at the appropriate water content.

### 3.2.4 DISPERSION

Soils where the clay particles do not readily bind to each other when in suspension are dispersive. Some dispersiveness is required to help sealing, but excessive dispersion leads to leakage through erosion and removal leading to tunnelling. When soils are checked for stability in water their dispersivity can also be observed.

Some clays may be susceptible to erosion into under-drains or into granular bases due to the influence of seepage forces. The pinhole test provides one method of identifying the dispersive characteristics of clay soils. This test method models the action of water flowing along a crack in an earth embankment. The test results cannot be used to calculate the quantity or rate of erosion, but they do provide an indication of potential erosion problems.

Clay lining soils should be tested to confirm that their classification is Non Dispersive ND1 or ND2.

### 3.2.5 PERMEABILITY

The permeability of potential clay liner material is best measured in a constant head triaxial cell laboratory test. As the liner soil will be reworked during construction through excavation, spreading and compaction, there is no need to obtain undisturbed samples for investigation testing. However, the preparation of the laboratory sample should reproduce minimum acceptable construction conditions, such as Dry Density (DD) at 95% of Maximum Dry Density MDD. The laboratory should carry out the permeability test on samples compacted at 2% wet of Optimum Water Content (OWC). Test reports may include permeability at two or more head levels and averaged.

A triaxial constant head permeability test (ASTM D5084-03 Method A, or BS 1377:1990 Part 6) is recommended because of its repeatable accuracy.

Laboratories accredited for this test can be found by searching under: Testing Inspection Facility, LAB-MECH, 4.08 Soils, ASTM Standards or BS Standards, on the International Accreditation New Zealand (IANZ) database at: <http://cabis.ianz.govt.nz/ianzwebportal/>

Initial indications of soil permeability can also be obtained at sites by filling test holes with water and observing the seepage characteristics over time. This may take the form of falling head, rising head or constant head tests. These tests are not accurate enough to determine hydraulic conductivities of the order required by Regional Councils for liners.

This document recommends compacted clay with a maximum hydraulic conductivity ( $k$ ) of  $1 \times 10^{-9} m/s$  be applied to form the lining of FDE ponds. This is the value adopted by regulatory authorities in Australia and is seen as representing good practice internationally.

However, requirements of Regional Council and individual resource consent conditions can and do vary around New Zealand and the acceptance criteria should be confirmed at the commencement of a project.

### 3.2.6 COMPACTION

#### Compaction testing

The theory of compaction along with relevant testing practice is described in *PN21* Part 1 Section 6.8.

Generally, the higher the density of the soil, the lower the permeability. However, the fabric of the clay soil is also a key factor in permeability, and the target water content to achieve the lowest permeability is found slightly wetter than the Optimum Water Content (OWC).

A Dry Density/Water Content (DD/WC) test will determine the difference in water content between the OWC and the 'as-is' natural Water Content (WC), and how much wetting or drying might be required

to achieve the best water content for low permeability. It should be noted that in some New Zealand locations, prevailing weather conditions may make it virtually impossible to sufficiently dry borrow clay back to within an acceptable water content range.

Figure 3.3 illustrates that compacting clay lining at a WC slightly higher than OWC will achieve a desirable lower permeability, despite having a slightly lower dry density.




Figure 3.3: Relationship between Compaction Water Content, Dry Density and Permeability



Hand Shear Vane

### Shear Vane testing

It is good practice to carry out a hand Shear Vane (SV) test on each compacted sample while undertaking the DD/WC test in the laboratory. These vane readings can then provide the earthworks contractor a comparative means for indirectly checking compaction.

### Compaction acceptance

Prior to construction, compaction acceptance criteria should be set using a combination of test criteria based on both DD/WC and SV laboratory testing, as well as local experience with soils. Your laboratory and specialist designer should be able to provide guidance on this.

The determination of the compaction acceptance criteria is demonstrated in Figure 3.4 and summarised in Table 3.2 below. Especially note the “Compaction Acceptance Area” in which the average density and WC values (as measured in test lots by the Nuclear Density Meter (NDM)) should be contained within. This area is bounded by five points determined using the following five steps:

1. From the DD/WC curve establish the Max DD. Calculate 95% of this value and draw a horizontal line across the graph. Where this line crosses the DD/WC curve the WC at this point (Point 1) is the Max WC allowable, provided that at this WC the SV strength is greater than 70 kPa. If not, then Max WC should be drier and at the WC which corresponds to 70 kPa.
2. From Point 1 extend the 95% MaxDD line horizontally to where it crosses the 5% Air Voids Line; this is Point 2.
3. Extend a line from Point 2 to a Point 3 where the DD/WC and -2% dry of OWC lines intersect.
4. Draw a vertical line upward from Point 3 until it hits the Zero Air Voids line; this is Point 4.
5. Extend a line from Point 4 along the Zero Air Voids curve to the Max WC as determined in step 1; this is Point 5.




Figure 3.4: Determination of Compaction Acceptance Criteria

PART 2: Clay Liners for Ponds

TEST	COMPACTION ACCEPTANCE CRITERIA
Dry Density/Water Content	>95% of MDD
Water Content	Min 2% dry to Max 6% of OWC (nominal)
Shear Vane*	Min 70 kPa to Max 100 kPa
Air Voids	<5%
*SV acceptance criteria takes precedence over WC where SV target values occur inside the nominal WC acceptance range	

Table 3.2: Compaction Acceptance Criteria

# 4.0 Liner Design

## 4.1 Slope Angles

Most compacted clay soils with a firm to stiff consistency and constructed in horizontal layers will have sufficient shear strength to support slope angles of 2H:1V (27°) for banks up to about four metres high.

One method to construct a clay liner on these steeper slopes is to build it up in successive horizontal layers. To do this the constructed layer thickness will need to be increased to accommodate the width of construction equipment. As construction equipment cannot effectively compact at the edge of a steep batter, the inner face of the liner needs to be over-constructed by at least 0.6 metres and then trimmed back into the well compacted zone.




Figure 4.1: Fill Placement by Horizontal Layers

Another method is to construct the layers by working up and down batter slopes. Some compaction equipment will have difficulty safely negotiating the steep slopes while still sufficiently compacting the clay. A flatter batter of 3H:1V, or even 4H:1V (14°), will provide a much higher percentage compaction if this method is adopted.




Figure 4.2: Fill Placement By Up and Down Slope Construction

## 4.2 Thickness of Liner

The rate of seepage through a clay liner is inversely proportional to the thickness of the liner; that is doubling the liner thickness reduces the seepage rate by half. However, most of the leakage from a lined pond is likely to be related to small defects, construction practices or variability in the clay liner material. The design liner thickness must ensure an effective seepage barrier is achieved despite natural variability in clay properties and construction related factors. A minimum thickness of 450 millimetres is required to practically achieve this.

In addition, the required clay liner thickness should be calculated using the seepage formula in Section 2.2 based on the laboratory permeability test result for the clay to be used and the maximum pond depth. The predicted performance should exceed local Regional Council requirements by a comfortable margin. However, in all cases the liner thickness should not be less than 450 millimetres.

The liner should be compacted in at least three, and preferably more, distinct lifts each of 150-millimetres maximum (compacted) thickness, so that any defects or variability in any one lift does not penetrate the whole liner. The upper surface of each lift should be kept moist and not rolled smooth, so that the lifts are well bonded and seepage cannot flow along the interface.

It might be argued that in theory a 300-millimetre-thick liner is sufficient, based on a laboratory permeability test result on a sample of clay prior to construction. However, this represents a best case situation where the compaction and water content on the very small sample undergoing testing is tightly controlled, a situation which can never be replicated in the field, hence the need for the thicker minimum 450 millimetre layer.

## 4.3 *In situ* Clay Ponds

Where the proposed pond location is wholly within a formation of homogeneous *in situ* clay without fissures, layering or other defects which might provide seepage routes, then a slightly different approach is possible. This should be subject to the following considerations:

- *In situ* (natural) and remoulded laboratory permeability test results are acceptable
- The natural water content is close to OWC over the full depth of the pond
- The shear strength is acceptable (generally greater than 70 kilopascals)
- The site meets other pond siting essentials (See also, Part 1 Section 4.3 of this Practice Note).

For such locations, the construction procedure would be to trim the base and slope of the pond to the required shape and dimensions, scarify and disc-up the top 150 millimetre of clay to homogenise it, and then recompact it to greater than 95% MDD. A bumpy type roller in conjunction with a smooth drum will be required. Generally, a slope angle of 3H:1V or flatter will be required to achieve an acceptable compaction result.

## 4.4 Clay Liner Protection

Designing and constructing the base of a clay lined pond well above the maximum predicted groundwater level is crucial as hydrostatic pressures can easily damage clay liners (refer Part 1 section 4.4.1 of this Practice Note for further guidance).

Clay liners are particularly vulnerable to damage from scour and erosion resulting from stirring, wind or wave action, and need protection. Unprotected clay liners are likely to experience significant cracking if they are allowed to become too dry (desiccated). Upon refilling the pond, organic solids from the effluent may fill the cracks before the clay is able to swell and heal the cracks. However with each season's drying, the cracks will get larger and deeper creating pathways for fluid to pass through.

It is recommended that clay liner slopes be covered with a minimum of 200 millimetres of moist soil to provide some protection from the exposure effects of wind, wave and sun. This protection must extend over the full height of the side slopes since the pond effluent level will fluctuate during the year. This approach will not be suitable on steep side slopes. Some effluent, or water, should remain in the pond base to keep the clay liner moist.

For protection of areas of concentrated currents or waves, and ponds with long reaches in exposed locations, scour protection is essential, as is rounded internal corners. Similarly, if the operation of the pond creates areas of high velocity currents, for example through the use of stirrers, then specific scour protection, or armouring, must be constructed in these areas. This prevents damage to the clay liner surface from desiccation cracking and erosional scouring by eddy currents as energy is dissipated by the armouring. Armouring should typically consist of a minimum of 300 millimetres of riprap rock over the 200 millimetres of protective moist soil. An alternative is to replace the soil with a geotextile (also known as a filter fabric) under the riprap rock armouring, or use a Reno mattress which is a rock filled basket. Concrete facing is another option. Professional engineering advice should be sought for these designs.

Sludge removal activities can damage the clay liner through rutting and tracking of the machinery, and through over-excavation of the sludge. If it is intended to operate vehicles within the pond, such as for de-sludging, the liner should be covered by 450 millimetres of aggregate. The protective aggregate is placed progressively over the clay surface, by spreading each load from the previously placed area so that the completed clay liner is not disturbed by aggregate placement activity. The aggregate does not need to achieve any particular degree of compaction, but should be dense enough to support vehicle traffic. A reinforced concrete track into and along the pond base, purely to protect the clay layer from excavator track damage, is also an option.

Pipe penetrations through clay liners below the design maximum pond levels should be avoided if at all possible. Such penetrations, if necessary, should be specifically detailed (refer Part 1 section 5.7.3) of this Practice Note.

## 4.5 Under Drainage

A specifically designed under drainage system beneath a clay liner is critical to ensure that there is no migration of fines into the drainage materials or hydrostatic pressure build up against the underside of the liner.

If clay is placed on top of more permeable soil, such as gravelly soils or subsoil drains, there is a risk that clay particles will migrate into the more porous material through the influence of seepage pressures. To prevent this, a filter layer should be placed between the clay and porous underlying material.

Soil filters are specified by their particle size distribution. The particle diameter of the smallest 15% of the filter soil ( $D_{15}$ ) should be less than the limits in the following table.

GRADING OF CLAY LINER SOIL	FILTER CRITERIA
>85% passing 0.06 mm	$D_{15}$ filter < $9 \times D_{85}$ liner
35% – 85% passing 0.06 mm	$D_{15}$ filter < 0.7 mm

Table 4.1: Soil Filter Criteria

As an alternative to soil filters, filter fabrics or geotextiles may be used provided they meet filtration Class 2 and Strength Class C as set out in New Zealand Transport Agency (NZTA) specification TNZ F/7.

An under drainage system connected to a leak detection system provides a convenient means of detecting any leakage through the liner and should be seriously considered as part of the pond design.

## 4.6 Soil Treatment Using Bentonite

If clay soils are locally available but have marginal permeability, it may be possible to create a complying clay liner by adding a small percentage of bentonite clay. While having low permeability, bentonite also has low strength, and swells to several times its volume when hydrated from dry. It also has a very high LL and PI. Bentonite should be sodium bentonite supplied in a fine powder form, rather than granular or pellet form.

The properties of bentonite and soil when mixed together vary widely and the optimal percentage of bentonite required must be determined by laboratory testing. If the local soil already has a significant proportion of clay fines, a bentonite content of less than 5% may be sufficient. However, a minimum total thickness of 450 millimetres for the clay liner is still required.




Figure 4.3: Typical Effect of Adding Bentonite on Permeability of Soil.

Figure 4.3 shows what typically happens when increasing percentages of bentonite are added to soil. While permeability initially decreases with a small amount of bentonite, the permeability only marginally decreases with further percentages of bentonite added. As bentonite is of low strength, higher percentages of bentonite can be quite detrimental to soil strength. The required percentage of bentonite to achieve a given permeability, while still achieving other performance criteria, must be established by laboratory testing. Furthermore, a field trial should be carried out to confirm the constructability of a bentonite/soil mixture which will be difficult to add water to and evenly mix in the field.

On-site mixing is done by laying out a carefully controlled amount of bentonite with a spreader and mixing in each layer with a highway-type stabiliser or pulveriser. An even higher quality of mixing can be achieved if the bentonite/soil mix is prepared in a pug mill and then transported to the pond. Techniques involving spreading bags of bentonite on the ground by hand and mixing with agricultural equipment are unlikely to achieve a quality liner.

A high bentonite content mix (up to 20%) may however form an effective localised seal around any pipes or structures that go through the clay liner.

#### **4.6.1 BENTONITE LAYERS**

Applying a thin layer of straight quarried bentonite sandwiched between a prepared surface and a cover layer, with the intention of forming an impermeable layer in a pond, is not a recommended practice for the following reasons:

- The bentonite is not sufficiently confined and will flow when it expands as it becomes damp
- Stones, either above or below the bentonite layer, may penetrate through it during compaction creating a leakage point
- It will not be stable on slopes as the bentonite layer provides a weakness plane for the overlying cover material to slide on
- Thin layers of bentonite are unable to practically maintain an even thickness under placement, levelling and compaction by machinery.

# 5.0 Construction Methodology

## 5.1 Compaction Equipment

It is vital that compaction equipment is suitable for breaking down the clods of the original soil mass and knits the compacted clay into a uniform tight mass. This is best done with a bumpy drum type of roller, such as a peg/pad foot or sheep's foot roller, with teeth that extend some way through the lift of clay currently being compacted. The roller can be towed or self-propelled.



*Self-propelled Padfoot Roller*

Agricultural discs may be used to break up clods of soil and to promote drying of wet clay in a separate area away from pond, but only if there is some confidence that there will be an ensuing period of warm drying weather. They are not suitable for mixing soil/bentonite liners.



*Discing*

There should be a good bond between successive lifts so that water cannot seep between the layers. If the surface of the previous lift becomes too dry or too smooth, it should firstly be scarified and re-compacted.

## 5.2 Control of Water

No amount of compaction will be sufficient if the water content of the clay is not carefully controlled within narrow limits. The clay water content should not be drier than the Plastic Limit (PL) during compaction, that is it should be always possible to roll a clod of soil into a thin thread.

Likewise the soil should not be too wet during compaction. Wet clay will be soft and will stick to rollers.

Clay soils shrink when they are dried and can crack. Earthworks contractors should be very careful to ensure that no significant desiccation occurs during or after construction.

Methods to prevent desiccation during the construction phase include:

- Watering the surface of the soil periodically
- Covering the soil with a plastic sheet, weighed down with sandbags, topsoil or similar
- Placing an additional layer of moist soil over the clay liner.

Any areas that do crack should be dug up, the clay replaced or re-wetted, and re-compacted.

**COMPACTED WET OF OPTIMUM AND  
KNEADED WITH SHEEPSFOOT ROLLER**



**CLAY COMPACTED TOO DRY AND NOT  
WELL MIXED**



*Effect of Water Content and Compaction on Clay Liner*

# 6.0 Quality Assurance

## 6.1 Compaction Trial

At the commencement of the clay lining construction phase, a trial strip is recommended to determine:

- The effectiveness of the contractor's equipment on the sourced clay to achieve the specified compaction acceptance criteria relative to that previously determined from laboratory testing
- An offset factor to be applied to future Nuclear Density Meter (NDM) readings on the clay liner by comparing the WC from the NDM against samples sent to the laboratory for oven WC testing
- The number of roller passes necessary to achieve an acceptable density for a given layer lift thickness.

Shear vane tests on the completed trial embankment will provide a useful reference tool for subsequent compaction control, but should not be used in isolation of the NDM for compaction acceptance purposes. Acceptance testing on thin clay liner lifts using a scala penetrometer is not favoured as they do not provide sufficient accuracy relative to NDMs and leave a hole through the liner after testing.

## 6.2 Site Testing

Because of the critical importance of the clay liner providing an (almost) impermeable barrier to the seepage of FDE into the underlying material, the quantity of testing required is significantly more than that required for embankment fill placement. To ensure that the required compaction, and therefore permeability of the clay liner will be achieved during construction, a suite of confirmatory field tests are required.

TEST METHOD	MINIMUM TEST FREQUENCY	RECOMMENDED TEST RESULT
<p><b>NDM Density with Water Content</b></p> <p><i>NZS 4407:1991 Test 4.2.1, Direct Transmission</i></p> <p>Water content samples from 10% of test sites should be laboratory oven dried to confirm water content correction from the trial being applied is still correct</p>	<p>For each lift:</p> <p>1 test per 250 m<sup>2</sup> of liner area</p>	<p>Meets agreed NDM and WC acceptance criteria when used in combination with SV testing</p>
<p><b>Shear Vane (SV)</b></p> <p><i>Guideline for Hand Held Shear Vane Test, NZ Geotechnical Society, August 2001</i></p> <p>(The SV may also be used as a consistency tool to identify areas of concern.)</p>	<p>For each lift:</p> <p>1 test per 250 m<sup>2</sup> of liner area</p> <p>This test only needs undertaking if WCs are marginal</p>	<p>Meets agreed compaction acceptance criteria when SV used in combination with NDM and WC testing</p>

Table 6.1: Field Compaction Testing

Each lift of the liner should be tested and approved before placing each subsequent lift. NDMs are the usual method of determining the bulk density and WC of a soil. Dry density is derived from the measured bulk density and WC. However, the WC of some clay soils cannot be measured reliably onsite using the NDM. Laboratory oven dried WCs should be used to more accurately determine dry density, until (and unless) site testing establishes that the WCs from the NDM are reliable.

Direct transmission mode is the preferred method of operating the NDM. For a 150-millimetre compacted layer a 100-millimetre probe depth is appropriate.



*Nuclear Density Meter for Measuring Density of Compacted Soil*

Some clays *in situ* are variable, especially those derived from residual soils or volcanic ash, and may not have a consistent MDD that can be easily used for compaction acceptance. In these situations it may be possible to establish a minimum shear vane strength to ensure that the soil is adequately compacted and that the WC is not too high. At the same time there should be a maximum air voids set so that clay soils are not too dry when compacted.

Be sure to repair any defects in the clay liner caused by testing or sampling. The area around NDM probe holes can be carefully dug up and re-compacted, or it may be possible to repair the holes with a bentonite mix rammed down and into the hole.

Records should be kept of all compaction control testing so that the adequacy of construction can be verified, and the person signing off on the construction has sufficient supporting records.

### **6.3 Seepage Testing**

If there are concerns at construction completion as to whether the required hydraulic conductivity has been obtained, there are several possible indicative approaches available to confirm this. Two of these are the drop test and core testing approaches. These are not a substitute for proper quality control testing, as field seepage testing on a newly constructed clay liner is difficult to undertake, and can be quite inaccurate.

However, they can also be used as an indicator if there are concerns as to whether an existing clay lined pond is leaking while in service. Any noticeable drop in pond level that is unrelated to operations, or not explained by evaporation, should be considered a possible indication of a defect in the liner system.

Before proceeding the Regional Council's acceptance criteria for seepage should be confirmed. Some councils base their acceptance on pond seepage rate or flux in millimetres per day (mm/day), rather than

the clay liners permeability in metres per second (m/s). Converting from one measure to another requires knowing the pond depth and liner thickness.

For example, Environment Canterbury allows a seepage rate ( $v$ ) of 1 millimetre per day. This is not the allowable surface level drop in a pond, but the maximum flux through the wet pond liner basin, that is the total area of liner below the ponds surface at its maximum designed operating level.

### Pond level drop test

The pond drop test, as its name suggests, requires accurately measuring the drop in pond level over time and calculating the seepage rate. The geometry of the pond is required to be known, from 'as-built' plans, or determined onsite. It should be noted that the complying seepage rate is often so small that it will be difficult to accurately distinguish between seepage, evaporation, precipitation and other inflows. This method will only detect gross leakage and may not be sufficiently accurate to detect a lower but still non-compliant seepage rate. The methodology is further described in Part 1 Section 8.7 of this Practice Note and the relevant formula is:

Maximum seepage (or flux)

$$v = \frac{q}{A}$$

$$= \frac{\text{Pond surface area (m}^2\text{)} \times \text{drop depth (mm/day)}}{\text{wet pond liner basin area (m}^2\text{)}}$$

Average conductivity or permeability of the liner may be back calculated from:

$$v = k \times \frac{\Delta h}{\Delta l}$$

### Permeability testing on clay core

Randomly selected core samples can be taken by using a thin walled sampling tube, sealing it, and sending it to a soils laboratory where a permeability test is undertaken on the extruded sample. However, these are spot samples only and may not replicate the performance of the whole pond when it is full. Samples need to be taken from the base of the pond where the head of water and hence water pressure will be the greatest.

Once the permeability value is known, seepage rate ( $v$ ) can be calculated if the average pond depth and liner thickness is known.

## 6.4 Records and Sign-Offs

It is important that pond owners be given a full set of records for their clay lined pond as they may be requested by their Regional Council for information on the sealing and/or seepage rate for the constructed pond.

Also note that in some regions a Chartered Professional Engineer (CPEng) or a Suitably Qualified Person (SQP) may be required to sign off on a clay lined storage pond, so it is essential that these people are actively involved in the design and construction work. Rules and consent conditions should be sighted before construction begins to confirm any specific requirements.

WHAT?	WHEN?	WHO?
Copy of all investigation and pre-construction testing (as per Table 3)	Prior to construction	
'As-built' plans of the pond which include dimensions, depth, batter slope and construction methodology  Construction testing results  Signed Producer Statements by both Designer/Engineer and Contractor	At completion of pond construction	Designer/Engineer and Contractor provides copies to dairy farmer

Table 6.2: Records



# PART 3

## **Geomembrane (Synthetic Liner) Selection**



# 1.0 Introduction

## 1.1 Introduction

Concerns about Farm Dairy Effluent (FDE) leakage from 'clay' lined ponds are increasing dairy farming community interest in synthetic liners as an alternative pond lining option. These products are technically known as geomembranes and are available in a number of chemistry types. The terms 'geomembrane' and 'synthetic liner' or simply 'liner' are used interchangeably in the industry.

Adding to the choice complexity is the ever increasing range of geomembrane thicknesses available on the market. Sadly, some FDE ponds have been constructed using very thin, or inappropriate geomembrane types, and their durability and in-service performance has not been as claimed. In many cases a thicker geomembrane better suited to the pond (or tank) design may have provided a more dependable and longer-life solution. Furthermore, the geomembrane liner performance will be affected by other factors such as the smoothness of the surface on which it sits and how well it is embankment anchored.

Currently there are few independently written technical documents available which identify what criteria should be used when recommending or selecting a geomembrane to line a FDE pond or tank. In the absence of independent information, this document seeks guidance from the specifications developed by the Geomembrane Research Institute (GRI) which is the international geomembrane industry organisation.



*Geomembrane installation.*

This note provides good practice guidance in the selection of geomembranes and needs to be read in conjunction with Part 1 of this IPENZ Practice Note.

### **KEY INSTALLATION DOCUMENTS**

The following documentation should be supplied by the installer at completion:

- Certificate(s) from the geomembrane manufacturer confirming full Quality Assurance (QA) compliance with the relevant approved GRI test specification for the batch from which the installed geomembrane was supplied
- Site records, including installers subgrade acceptance, panel numbering and placement, trial welds and seam tests, and other supporting QA documentation
- Material warranty for a minimum period of 20 years from the geomembrane supplier, which has been approved by the manufacturer for the stated period prior to installation
- Installation (workmanship) warranty from the geomembrane installer for a minimum period of 5 years
- Certification by the installer that they have completed their work to the drawings, specifications and any other relevant documents. This certification usually takes the form of a signed Producer Statement.

# 2.0 Geomembranes

## 2.1 Types of Geomembranes

Geosynthetics are available in a wide range of forms and materials, each to suit a slightly different end use. These products have a wide range of applications and are currently used in many engineering situations all over the world.

Geomembranes represent the largest group of geosynthetics. They are thin sheets of material manufactured with specific properties in order to provide key attributes. Membrane design-life well in excess of 20 years can be achieved for most applications. Geomembranes can offer the advantages of dependable containment with very low permeability, long life expectancy, fast installation and easy maintenance.

Geosynthetic Clay Liners (GCL) are a slightly different type of geosynthetic. They are factory fabricated thin layers of bentonite clay sandwiched between two geotextiles or bonded to a geomembrane.



*Geomembrane with geotextile underliner being installed.*

## 2.2 Geosynthetic Research Institute (GRI) Specifications

The Geosynthetic Institute (GSI) is a consortium of organisations involved with geosynthetics. Its Geosynthetic Research Institute (GRI) has developed material acceptance specifications which have become the default international specifications for geosynthetic products covering a range of chemistry types.

These specifications make reference to a range of standard American Society for Testing and Materials (ASTM) test methods. Presently GRI's published acceptance criteria based on ASTM tests are limited to the geomembrane types as quoted in Table 2.1 below. Presently it excludes Polyvinyl Chloride (PVC), Ethyl Vinyl Acetate (EVA), Ethylene Interpolymer Alloy (EIA), and Chlorosulfonated Polyethylene (CSPE). This is not to say these or other geomembranes cannot be used for FDE applications, rather that presently there are no internationally accepted specifications for them.

New geomembrane types are expected in coming years, but until they have been tested and specification test values set by GRI, or some other internationally recognised authority, their use for FDE is unable to be recommended.

	<b>GEOMEMBRANE NAME</b>	<b>GRI SPECIFICATION</b>
<b>GCL</b>	Geosynthetic Clay Liner	<a href="#">GCL3</a>
<b>HDPE</b>	High Density Polyethylene	<a href="#">GM13</a>
<b>LLDPE</b>	Linear Low Density Polyethylene	<a href="#">GM17</a>
<b>fPP and fPP-R</b>	flexible Polypropylene (non-reinforced and reinforced)	<a href="#">GM18</a>
<b>EPDM and EPDM-R</b>	Ethylene Propylene Diene Terpolymer (non-reinforced and reinforced)	<a href="#">GM21</a>
<b>PE-R</b>	Polyethylene reinforced (for exposed temporary situations)	<a href="#">GM22</a>
<b>LLDPE-R</b>	Linear Low Density Polyethylene (reinforced)	<a href="#">GM25</a>

Table 2.1: GRI Specifications for Geomembranes

It should also be noted that a geomembrane's conformance with the relevant GRI specification in itself does not confirm acceptability. A careful judgement still has to be made as to whether it is suitable for a particular design application, in this instance as a FDE pond or tank lining.

In the GRI specification each geomembrane type is subdivided into different test acceptance values depending on the standard thickness manufactured. What the GRI specification does not provide guidance on however is what thickness is suitable for differing applications. In general though, the thicker the geomembrane, the better performance and durability that can be expected. For FDE structures including ponds and tanks, the majority view of New Zealand geomembrane suppliers is that the minimum thicknesses contained in Table 2.2 should be adopted. This table also recognises that for manufactured tanks, where geomembranes are cut and seamed in factory controlled conditions, a slightly thinner geomembrane could be acceptable.

For a minimum 20-year warranty period of the geomembrane in contact with FDE, irrespective of its New Zealand location, a minimum thickness of greater than 1mm is recommended. Where it is likely to be exposed to harsh temperatures, weather and operational use, a thicker geomembrane will usually be appropriate.

The design life given by the manufacturer should be many years in excess of the warranty period. Furthermore, the warranty period from the supplier should not be longer than that offered by the manufacturer.

GEOMEMBRANE	GRI SPECIFICATION	***RECOMMENDED MINIMUM THICKNESS (MM) PONDS	***RECOMMENDED MINIMUM THICKNESS (MM) TANKS
<b>GCL</b>	<a href="#">GCL3</a>	Refer Supplier	N/A
<b>HDPE</b>	<a href="#">GM13</a>	1.50	1.25
<b>LLDPE</b>	<a href="#">GM17</a>	1.50	1.00
<b>fPP-R</b>	<a href="#">GM18</a>	1.14	1.14
<b>fPP</b>	<a href="#">GM18</a>	1.52	1.02
<b>EPDM</b>	<a href="#">GM21</a>	1.14	1.14
<b>EPDM-R</b>	<a href="#">GM21</a>	1.14	1.14
<b>LLDPE-R</b>	<a href="#">GM25</a>	1.14	1.14
<b>*PE-R</b>	<a href="#">GM22</a>	Not recommended for FDE	
<b>**PVC, EVA, EIA, CSPE</b>	N/A	Not recommended for FDE	

Table 2.2: Recommended Geomembrane Minimum Thicknesses

\* PE-R is not recommended for FDE even though it has a GRI specification because the maximum thickness the specification covers is for a 0.5mm scrim reinforced polyethylene geomembrane. It is noted that the United States Natural Resources Conservation Services (NRCS) also do not recommend it for wastewater applications in their conservation practice standards [Code 521A](#).

[www.nrcs.usda.gov/Internet/FSE\\_DOCUMENTS/stelprdb1046899.pdf](http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/stelprdb1046899.pdf)

\*\* PVC, EVA, EIA, CSPE and various other polymers are unable to be recommended as there is currently no GRI specification to provide a basis of acceptance.

\*\*\* Many manufacturers refer to nominal thicknesses rather than actual thickness. For example, the actual thickness of a 1.14mm geomembrane might be rounded down and referred to on a data sheet as having a nominal thickness of 1.1mm.

## 2.3 Geomembrane selection by attributes

Depending on their intended location and the type of FDE structure the geomembrane will be installed into, differing relevant criteria will need to be considered by practitioners. Based on industry practice and opinions, Table 2.3 provides a list of the 10 most critical attributes in the New Zealand FDE context for geomembranes.

This attribute assessment is for general comparative purposes only and is not a substitute for direct communication with individual product suppliers who should be able to provide more detailed information and comment on the suitability of their geomembrane for the particular application. Due to subtle variations in test methods, comparison of similar materials using data sheets is not generally recommended. Requiring the batch of geomembrane delivered to site to meet the relevant GRI specifications avoids this issue.

	ATTRIBUTE	COMMENTS
1	<b>Ultraviolet(UV) and Ozone Resistance</b>	Geomembrane materials that are designed for exposed conditions must resist the sun's Ultraviolet (UV) degradation as well as the oxidation effects of ozone. UV and ozone resistance is a very important attribute for endurance in fully-exposed applications. Good UV stabilisation, but without sufficient antioxidants to provide ozone resistance, will result in exposed surfaces being oxidised more rapidly.
2	<b>Thermal Stability</b>	Geomembranes meeting GRI standards are stabilised to reduce deterioration due to thermal extremes. The installation methodology however must take into account any movement (expansion and contraction) over a 40°C temperature range, especially in fully exposed situations. The reduction of thermal stress by covering should be considered.
3	<b>Flexibility</b>	Flexibility relates to the ability of that product to form, bend, mould, adapt and conform to the subgrade and thereby provide intimate contact with the supporting surface. Flexibility can affect the installation method as some materials can be partially prefabricated and others require the jointing of seams to be completed on site. The flexibility of a geomembrane should not be used as a means to compensate for poor design or site preparation, as some liners that are stretched can have a shorter service life.
4	<b>Elasticity</b>	Elasticity is the ability of a sheet material to stretch under stress, for example over a subgrade protrusion, and regain its shape while retaining its elastic properties when the stress is released. Materials that are scrim reinforced generally handle permanent stress better as they have higher strength and minimal elasticity. Elasticity should not be used to compensate for poor surface preparation. Avoid stiff materials spanning voids and highly elastic materials being stretched so as to create localised thin areas.
5	<b>Tear Strength</b>	Tear strength is a test property that measures the resistance of a geomembrane sheet material to tearing which may be introduced by a cut or puncture while subjected to tensile stress. The most tear resistant geomembranes are fabric (scrim) reinforced where the woven scrim provides high resistance to tear propagation. Tear strength is considered important to overall durability on all geomembranes.
6	<b>Environmental Stress Cracking</b>	Some 'stiffer' geomembranes are prone to cracking under stress, especially if scratched, cut or abraded, particularly in areas adjacent to extrusion welds or at creases.
7	<b>Puncture Performance</b>	The ability of a geomembrane to resist puncture by stones or debris in the subgrade or overlying soils is generally referred to as puncture resistance. Products which have the ability to stretch more before yielding have higher puncture resistance. Reinforced materials demonstrate higher puncture strength due to their scrim reinforcement. Tear strength is also important in overall puncture resistance. Good subgrade preparation is always the key to good puncture performance although geotextile used as an underliner can reduce this risk.

	ATTRIBUTE	COMMENTS
8	<b>Repair in Service</b>	An important attribute to consider is the ability to provide competent repairs after many years of service. Oxidation of the geomembrane surface can affect the ability to provide an effective repair. Some materials can be thermally welded. However, most methods require the surface to be clean and dry, the difficulty of which varies between materials. Permanent repairs should always be completed by experienced installers. Repairs by owners can invalidate warranties.
9	<b>Surface Friction</b>	Surface friction is a measure of the roughness of a geomembrane surface to resist sliding on soils, or a substrate, especially under load. Harder surfaced geomembranes provide low surface friction and require a rough texture for steeper slopes. In these situations, 'textured' polyethylene, as well as elastomeric geomembranes that have a higher surface friction, can be considered.
10	<b>Chemical Resistance</b>	The ability of a geomembrane to resist deterioration from chemicals varies. FDE should not be a concern for most commonly available geomembranes. However, a manufacturer's statement stating the suitability of their product for use with FDE should always be confirmed. Suitability will usually exclude the risks from substances such as hydrocarbons, fats, certain sprays and cleaning agents, and harmful chemicals entering the pond or tank. The likelihood of these coming into contact with the liner surface should always be considered.

Table 2.3: Geomembrane Attributes

Table 2.4 below provides a selection guide as to the "pros and cons" for each GRI recommended geomembrane type for FDE ponds and tanks.

GEOMEMBRANE TYPE	PRO'S	CON'S
<b>GCL</b>	High mass and simple joining system, less weather dependant for installation. FDE solids can be removed with care by an excavator (depending on cover material and compaction used).	Requires specific cover materials that may not be available on site. Slope angles, compatibility with subgrade, and cover needs to be evaluated for every site. Reinforced versions recommended for steeper slopes.
<b>HDPE</b>	Good UV and ozone resistance, as well as chemical resistance.	Poorer performance in thermal stability, flexibility, elasticity, stress cracking and puncture performance.
<b>LLDPE</b>	Good puncture performance and tear strength.	Poorer tear resistance, elasticity, thermal stability and chemical resistance.
<b>fPP</b>	Good UV resistance, flexibility, elasticity, chemical resistance, puncture performance and tear strength, repair in service. Popular for prefabricated liners (eg FDE tanks).	Poorer thermal stability, chemical resistance, and tensile performance. Poorer elasticity if reinforced. Can be slightly more expensive.
<b>EPDM</b>	Good UV and ozone resistance, elasticity, flexibility, thermal stability puncture performance, and repair in service. Can be part fabricated.	Poorer resistance to hydrocarbons. Poorer tear resistance. Can be slightly more expensive.
<b>PE-R, PVC, EVA, EIA, CSPE</b>	Not recommended	

Table 2.4: Geomembrane Selection Guide

# 3.0 Installation

## 3.1 Experienced installers

Geomembranes must be installed by experienced installers who have been approved and trained by their supplier to provide this service. A 'Do It Yourself' approach is not recommended, especially if the Regional Council requires Suitably Qualified Person (SQP) signoff (as recommended in Part 1 section 7.1). All the major manufacturers provide installation guidelines for their products and these are available from suppliers for reference purposes.

For the protection of both the farmer and installer (or alternatively the main contractor and their installation subcontractor), a contract agreement which sets out the expectations and responsibilities, including payment terms of all parties, is essential (see also Part 1 section 9.4).

## 3.2 Subgrade preparation

Subgrade preparation must be accepted by the installer and conform to the geomembrane manufacturer's requirements prior to installation. Subgrade materials should not contain sharp, angular stones or any objects that could damage the liner or adversely affect its function unless a cushion layer is used.

A cushioning layer should generally be placed beneath all geomembrane liners, and certainly if the subgrade particles contain sharp angular stones, or the particle size is greater than 9.5mm. The engineer/designer should make the decision whether a protective geotextile is required or not under the liner. Geotextile used as protection should meet the requirements of GRI Test Method [GT12\(a\)](#).

<http://www.geosynthetic-institute.org/grispecs/gt12a.pdf>

## 3.3 Anchor trenches

Geomembranes need to be anchored to prevent uplift due to wind or slippage down the side slope.




Figure 3.1: Typical liner anchor trench detail.

### 3.4 Geosynthetic Clay Liner (GCL)

The selection of soil or aggregate cover materials to be placed over the GCL to provide confinement, and the underlying subgrade material, needs to be carefully considered to ensure that high concentrations of potassium, calcium and magnesium are not leached into the GCL leading to material deterioration. GCL is available in several grades depending on the application and pond side slope. Suppliers representing GCL manufacturers should be consulted to ensure the appropriate product and installation methodology is adopted.

### 3.5 Safety

Geomembrane installation should include appropriate safety features as part of the overall pond design to remove, minimize or isolate hazards. Warning signs, fences, ladders, ropes, bars, rails, and other devices must be provided, as appropriate, to ensure the safety of people and livestock. Requirements of the Territorial Local Authority, Regional Council and Department of Labour should also be carefully considered.

### 3.6 Groundwater and drainage

If the groundwater level is near the proposed base level of the pond, groundwater monitoring should be conducted during the site investigation phase to verify the expected location. The pond should be designed so that it will be well above the highest ground water level expected through the year (See also Part 1 section 5.10.1).

In some situations, it may be necessary to install groundwater monitoring wells for a year or more to determine the ground water levels and gather enough information to properly determine the required flow capacity of the drainage system. If high water tables could adversely affect the proper functioning of the pond structure, such as on a flood plain, an interceptor or relief-type drainage system should be included to control uplift pressures. In these situations an above ground FDE pond or tank may be a better option.

Subsurface conditions such as soil type and groundwater levels will dictate the direction and scope of the design of the drainage and venting system beneath the geomembrane liner. An inadequate drainage and venting system may result in floating of the geomembrane liner. Hydrostatic pressures from fluctuating groundwater levels or leakage through the liner may cause geomembranes with a specific gravity less than 1.000 to float. Furthermore, if the pressure under the liner is higher than that being applied from above by the stored liquid, the liner will float irrespective of its specific gravity. Also water intrusion or uplift will impact more on geomembrane types with rigid seams and so become more susceptible to Environmental Stress Cracking.

### 3.7 Gas venting

Gas production and build-up beneath the geomembrane liner due to the presence of organic material in the soil, or leachate leakage through the liner, may cause “whales” or ‘hippos’ at the base of the liner to form (See also Part 1 section 5.10.2).

Therefore, the need for venting should be considered during design for these membrane liners. Site conditions which may be conducive to gas production include sites which have been subject to long-term seepage of animal waste into the foundation soil, sites with naturally occurring organics in the soil such as peat, geothermal areas, or fine grained foundation soils where fluctuating groundwater levels may trap gases present in the soil.



*Lining with gas vent.*

### **3.8 Drainage and venting system design**

To facilitate collection, drainage of liquids and venting of gas, geosynthetics such as a geonet or geocomposite under the geomembrane liner should be installed to the manufacturer's recommendations. The cut pond base should be sloped, typically a minimum of 2 per cent, to permit positive flow of the liquids or gases. In most cases, the geocomposite will serve both drainage and venting purposes. In very large ponds the base may need to be sloped in multiple directions in order to decrease the required drainage and venting flow travel distances. The drainage system should also incorporate a leak-detection system and this is recommended beneath all pond lining materials.

### **3.9 Penetrations**

The number of penetrations through a geomembrane lining needs to be minimized. Trenching and backfilling of fill around pipes should be carefully detailed so that subsurface water is not able to flow along the outside of the pipe and down the underside of the geomembrane. Mechanical pipe penetrations and filter collars should be considered. A correctly designed concrete slab around the pipe can be installed to reduce differential settlement along the pipe and reduce a potential weak point around the pipe penetration area.

### **3.10 Stirrers**

If stirrer or agitation operations are likely to result in abrasion or other mechanical damage to the liner, then protective measures should be provided to ensure the integrity of the lining. Options include increasing the geomembrane liner thickness above the minimum values recommended, or providing protective pads and aprons at agitation locations. A concrete pad laid upon sacrificial offcuts of geomembrane and underliner is a good option as it acts as both ballasting and diffuses abrasive grit agitated by the stirrer.

### 3.11 Quality Assurance and warranties

It is important that the geomembrane installer prepares a site specific work plan (also known as a Project Quality Plan) which details the full scope of the installation work to be undertaken. A copy of this plan should be supplied to the farm owner or their representative for acceptance prior to work commencement.

During the project, supporting or confirming documentation for all lining materials supplied and incorporated into the works needs to be gathered. The installers documentation needs to cover all sampling, testing, inspection, and proving of compliance with relevant standards.

At contract completion, and as a contract condition, the following documentation should be supplied by the installer, to the owner or the Suitably Qualified Person (SQP) to review:

- Certificate(s) from the geomembrane manufacturer confirming full QA compliance with the relevant, approved GRI test specification for the batch from which the installed geomembrane was supplied
- Site records, including installer subgrade acceptance, panel numbering and placement, trial welds and seam tests, and other supporting QA documentation
- Material warranty for a minimum period of 20 years from the geomembrane supplier, which has been approved by the manufacturer for the stated period prior to installation
- Installation (workmanship) warranty from the geomembrane installer for a minimum period of 5 years
- Certification by the installer that they have completed their work to the drawings, specifications and any other relevant documents. This certification usually takes the form of a signed Producer Statement, for example *NZS3910 Sixth Schedule: Form of Producer Statement – Construction*.

## 4.0 Summary

There are many factors that contribute to good geomembrane performance, and these are summarised in the table below.

<b>GEOMEMBRANE SUCCESS FACTORS</b>	
<b>Material</b>	<ul style="list-style-type: none"> <li>▪ Choose a geomembrane with attributes that are suited to the site conditions</li> <li>▪ Confirm sufficient UV and ozone-resistance provided to suit New Zealand conditions</li> <li>▪ Confirm resistance to long-term environmental stress cracking</li> <li>▪ Assure material will not overstretch creating weaknesses</li> <li>▪ Secure manufacturer's certification that product meets GRI specifications</li> <li>▪ Secure material warranty from the manufacturer for the batch supplied.</li> </ul>
<b>Site</b>	<ul style="list-style-type: none"> <li>▪ Ensure stable-cut side slopes that provide long-term stability</li> <li>▪ Ensure distance from subsurface organic materials that can form gas</li> <li>▪ Construct pond base above highest likely ground water level</li> <li>▪ Install subsoil drainage.</li> </ul>
<b>Design</b>	<ul style="list-style-type: none"> <li>▪ Select competent subgrade construction materials</li> <li>▪ Develop clear specification for materials requirements</li> <li>▪ Design for protection against weather extremes</li> <li>▪ Mitigate stress fatigue and cracking</li> <li>▪ Include a leak detection system.</li> </ul>
<b>Construction</b>	<ul style="list-style-type: none"> <li>▪ Engage experienced contractors and installers</li> <li>▪ Confirm subgrade compaction meets specification</li> <li>▪ Ensure subgrade surface is sufficiently trimmed and smoothed</li> <li>▪ Confirm anchoring details meet designer's specifications</li> <li>▪ Ensure approved sealing around pipes and other penetrations</li> <li>▪ Adopt manufacturer-recommended jointing/seaming system</li> <li>▪ Prepare 'as-built' plans.</li> </ul>
<b>Quality Assurance</b>	<ul style="list-style-type: none"> <li>▪ Approve Quality Assurance (QA) programme prior to installation</li> <li>▪ Complete on-site inspection/testing Quality Control (QC) procedures</li> <li>▪ Documentation reviewed by a Suitably Qualified Person (SQP)</li> <li>▪ Installer provides an installation (workmanship) warranty.</li> </ul>
<b>Operations</b>	<ul style="list-style-type: none"> <li>▪ Arrange for regular inspection and maintenance</li> <li>▪ Have clearly documented cleaning out procedures (if required)</li> <li>▪ Have procedures for damage repair, including patching repairs</li> <li>▪ Consult supplier on chemicals and substances which may affect performance</li> <li>▪ Protect from possible vandalism, stock and other damage causes.</li> </ul>

Table 4.1: Factors Contributing to Successful Geomembrane Performance

# PART 4

## **Ponds and Tanks on Peat**



# 1.0 Introduction

## 1.1 Purpose

Farm Dairy Effluent (FDE) ponds and tanks constructed over peat soils can have an increased performance risk due to the weak and compressible nature of the underlying peat soils.

Anecdotal reports suggest that pond and tank failures on peat have contributed to a climate in which farmers may be reluctant to construct and install dairy effluent storage on their properties.

While tanks and pond embankments may be constructed over peat using procedures and methods outlined in Part 1 of this Practice Note (PN), the engineering properties of peat are such that there needs to be a “step up” in the level of ground investigation and detailed design undertaken. This is necessary to ensure that the long-term integrity and successful performance of these FDE containment and storage facilities are comparable to those constructed over sand, clay and silt soils.

The purpose of this document is to explain the need for this increased level of investigation and design work, and to give some guidance on the choice of investigative techniques appropriate for the intended storage facility type. It is also to identify the issues that need to be considered when choosing construction methods, ancillary works, and the operation of facilities on peat soils. This document is not intended to give design advice, rather to highlight design issues that may need to be addressed by the designer and should be read in conjunction with the rest of the Practice Note.

### KEY POINTS

Ponds and tanks constructed on peat soils provide different engineering challenges to those constructed on other soils:

- Varying rates of settlement across a structure can lead to differential settlement
- Ground settlement can continue over many years
- Ponds and tanks should be constructed above ground
- Gas venting and drainage collection is critical
- Clay and reinforced concrete liners are not considered suitable
- A “step-up” in ground investigations and design is required
- Specialist engineering testing and designer inputs are essential
- Design options are available to reduce settlement and performance risks
- There may be higher long-term maintenance costs that need to be allowed for

## 1.2 WHAT IS PEAT?

Peat is not a single soil material. It is a highly variable material that can exhibit considerable changes in composition and nature over short distances and depths.

There are several definitions including:

*“A mixture of fragments of organic materials derived from vegetation that has been chemically changed and partly fossilised”, and “Dead vegetation in various stages of decomposition”.*

Several engineering classifications for peat soils have been adopted reflecting the difficulty in precisely describing and assessing the engineering properties of peat soils.

However, a simplified approach is proposed in which peat is classified into three broad categories based on the presence of roots and other organic fibres within the peat:

- Thick (Coarse) Fibrous Peat (Fibres >1mm thick)
- Thin (Fine) Fibrous Peat (Fibres <1mm thick)
- Amorphous Peat (No fibres)

Fibrous peat is generally stronger than amorphous peat, sometimes significantly so. The fibrous crust at the ground surface is often the strongest part of the soil profile in peats.

Peat deposits are typically associated with swamp or bog development in low lying water areas. Many show development profiles similar to that illustrated in Figure 1.1 below.




Figure 1.1: Peat Profile in Swamp/Bog Development

The thicknesses and lateral distribution of the three types of peat present can vary and the inflow of streams can result in accumulation of layers of sand, silt and clay within the peat.

For example, a 5-metre-deep peat profile can contain as little as 300 millimetres of soil minerals and organic matter, the rest effectively being 4.7 metres of water held in a sponge-like matrix of decaying vegetation and fibres, and soil particles. By comparison a 5-metre-deep silty clay profile would contain virtually the full 5-metre depth in soil minerals and organic matter.

The figure along side shows typical near surface fibrous peat. Note the rotation of the fibres from vertical to horizontal towards the base of the photograph. These fibres reinforce the soil lending the peat greater strength than the soil matrix has alone.

In general terms, the strength of peat decreases as the number and thickness of fibres also decreases.



Figure 1.2:  
Fibrous Peat

### 1.3 Why is Peat a Challenge?

There are a number of reasons why peat can present challenges to construction:

- Peat exhibits many of the same physical properties as other soils such as silt and clay, but it does so to greater extremes
- All soils settle under loadings from pond embankments and tanks, but peat is highly compressible; settlements are potentially much greater and can continue for much longer periods than most other soil types
- Peat can be very weak as well as highly compressible. Paddocks often consist of a relatively strong surface crust which overlies much weaker softer peat below; and if excavation and construction breaks through this crust, the benefits the crust provides can be lost
- Peat soils are typically associated with shallow groundwater and areas of land where winter groundwater levels are frequently at, or close to, ground level. This means excavations can flood quickly and the sides of excavations can become unstable
- Peat soils can be comprised mainly of water with very little organic or mineral content. They may contain minimal actual 'solid' material, the rest being water and gas
- The natural variation in peat composition means that each location is different. Variation within the peat beneath a large structure, such as a large diameter tank or pond, may result in parts of the structure experiencing different degrees of settlement. This process is known as differential settlement and can have serious detrimental effects on built structures
- Existing ponds on peat cannot be simply cleaned out and a new liner installed. In many cases, existing ponds that have been excavated into peat are unlined and the effectiveness of their effluent containment is questionable. There are significant health and safety risks associated with entering into these ponds, as well as major engineering issues associated with trying to install a suitable liner. Issues are likely to include: groundwater inflow, hydraulic uplift of all liner types, soft compressible soils against which a clay liner cannot be compacted, and unstable sides to the excavation
- Extensive investigations are required to confirm, or otherwise, the continued suitability of a site. Subsequent site specific pond design analysis is required to confirm that the necessary performance from the structure can be expected over its design life
- Investigations need to extend to at least the full thickness of the peat, or to twice the width of the pond bank or diameter of the tank. This is because the loading from the tank or bank is exerted by the soil to this depth as illustrated below in Figures 1.3 and 1.4. Peat soils can still be highly compressible even when buried to significant depth.




Figure 1.3: Stress Zones Imposed in Soil by Circular Tanks




Figure 1.4: Stress Zones Imposed in Soils by Embankments or Bunds

# 2.0 Engineering Properties of Peat

## 2.1 Engineering Issues with Construction on Peat

The key issues that need to be addressed in the design and construction of FDE ponds or tanks on peat are:


- Bearing capacity failure
- Excessive settlement of the structure
- Shallow groundwater table
- Gas collection.

While these issues need to be addressed for construction on all soils, the risks are greater on peat due to its soft and highly compressible nature.

In all cases these issues can only be suitably addressed if an appropriate minimum level of ground investigation is carried out as part of the design process.

## 2.2 Bearing Capacity Failure

Bearing capacity failures are caused when the load from a structure, such as from a tank (Figure 2.1) or pond embankment (Figure 2.2), is too much for the soils to support without shearing and giving way under the structure.



*General failure*

*Local failure*

*Figure 2.1: Bearing Capacity Failure Beneath Tanks*




Figure 2.2: Bearing Capacity Failure of Pond Embankment

The shear strength of a soil is the measure of its resistance to failing by shearing or sliding under a load. Peat is one of the few soils whose shear strength generally decreases with depth. The way to avoid these failures occurring is to measure the shear strength profile of the underlying soils and ensure the stresses imposed by the tank or embankment do not exceed the soil's strength.

The generally unnecessary practice of installing shear key trenches beneath pond embankments may increase the risk of a bearing capacity failure on peat soils. Cutting through the stronger crust at the surface of the peat can reduce its integrity as a consequence.

## 2.3 Excessive Settlement

All soils settle under loading, but settlements are potentially greater with peat. The key issue is to understand and forecast the amount and rate of settlement that will occur over the lifetime of the tank or pond. This is so possible changes in level and shape of the pond or tank can be allowed for in the design process.

The expulsion of water and gas from the soil fabric under the new loading from the tank or pond embankment allows the soil fabric to “close up” causing the ground surface to settle in consequence. This process is known in engineering as consolidation and is equivalent to “shrinkage” in soil science.

Excessive settlement can over-stress and potentially damage liners, disrupt pipe connections, and result in loss of freeboard and capacity in ponds.

Similarly, differential settlement, when one part of the structure settles more than the rest, can cause damage to fixtures and fittings and result in loss of freeboard and capacity in storage structures.

There are two phases of soil consolidation or settlement: a rapid primary phase, and a longer-term, slower secondary phase.

A key difference in settlement characteristics demonstrated by peat over other soils is that the secondary phase does not end. It continues at a constant rate regardless of how heavy the tank or pond embankment is.

The level and rate of the two settlement phases can be estimated from soil test data. This enables the design engineer to allow for the potential effects of these settlement phases in the design and construction of a tank or pond.

## 2.4 Shallow Groundwater Table

Most excavations into peat soils will encounter groundwater at shallow depth. This depth may vary seasonally, being deeper after the drier summer months than in winter.

Groundwater flow into an excavation has a number of significant effects, including:

- Flooding of the excavation requiring pumping out, disposal and possible treatment of the water prior to discharge
- Softening and liquefying soils in the base and sides of the excavation
- Weakening and potentially collapsing sides of the excavation
- Lowering groundwater around the excavation, causing settlement of the ground level around
- the excavation possibly over tens-of-metres distance.




Figure 2.3: Effects of Excavating Below Groundwater

All of these factors increase the difficulty of working in the excavation and can significantly add to the cost of the works. In order to avoid these difficulties, pond and tank construction should be above ground, or ideally moved to a location without these issues.

## 2.5 Gas Collection

The natural degradation of the organic material in peat generates gases, usually methane or carbon dioxide depending on local conditions. If not free to vent to the atmosphere, these gases can collect beneath lining membranes, generating 'hippos' as seen in the photograph below.



*Hippo formation due to gas collection*

This can be prevented by the installation of gas venting measures beneath a synthetic liner (also known as a geomembrane). However, these venting measures need to be kept dry to operate efficiently and for this reason may be designed to double as a drainage vent if an under-drainage system is installed.

# 3.0 Settlement

## 3.1 Managing Settlement

A first step during the design phase in managing settlement is to reduce the actual volume of storage required to a minimum. The Dairy Effluent Storage Calculator (DESC) provides a valuable tool in the hands of an experienced designer to achieve this (See also Part 1 section 5.6 on pond sizing for further background). The design of the FDE pond or tank should not be undertaken in isolation of reviewing the whole effluent system. Reduced storage requirements may be possible through factors such as:

- Adopting a low rate application system, which allows irrigation to continue through times when high rate systems are not desirable
- Irrigating to low risk soil areas
- Reducing storage inflows through dry scraping and low water-pressure yard washing, and water recycling such as green wash systems
- Diverting unused shed roof and yard area rainwater away from the effluent storage collection system

Settlement on peat can be extreme and the aim of managing the settlement is to limit it to a level less than that at which damage could occur to a pond or tank. A number of technical means are available to achieve an acceptable level of settlement, although the small scale nature of individual ponds and tanks often makes it prohibitively expensive.

Never the less there are two common approaches that may be considered:

- If the peat is thin enough, it may be possible to excavate and remove it from beneath the footprint of the tank or pond, or;
- Preloading of the ground surface. This removes the majority of the settlement prior to pond or tank installation.

Other means of managing small settlements are to adopt construction techniques and materials that can best cope with the deformations and stresses that settlement will impose. For example, geomembranes (also known as synthetic liners) have some advantage due to their flexibility and ease of extending and repairing if necessary; whereas, clay and reinforced concrete liners are not considered suitable as they are usually unable to withstand the imposed forces. The selection of the appropriate synthetic liner material is the role of the design engineer. They should be able to estimate the degree of settlement and, in particular, differential settlement that could give rise to deformation and liner stretching. Similarly, pond anchor trenches for synthetic liners must also be properly designed and constructed. Part 3 of this Practice Note provides further guidance.

Settlement of the pond banks may result in progressive “crowning” where the base of the pond rises relative to the sides as illustrated in Figure 3.1. However, subsequent levelling of the peat base by excavating is likely to result in very soft wet peat being exposed following removal of the crust, thereby making installation, or reinstallation, of the synthetic liner very difficult. The design engineer should also consider the loss of storage capacity and freeboard as a consequence of leaving the crown in place.




Figure 3.1: Settlement of Pond Banks and Crowning of Pond Centre

## 3.2 Pond Bank Settlement

As the largest and heaviest part of the pond structure, pond banks will be the area of the pond in which the majority of settlement will be generated.

As previously described there are two phases of settlement, primary and secondary, and these are illustrated in an example in Figure 3.2.

In this theoretical example, the ground on which a 2-metre-high bank has been formed, will settle approximately 750 millimetres in 35 days and 1,000 millimetres after 10,000 days (27 years). If the predicted, remaining long-term settlement of 250 millimetres after 35 days has elapsed is acceptable to the pond designer, then the pond can be lined and completed after that time.




Figure 3.2: Calculated Settlement of a Two-Metre-High Bank (Example Only)

If this approach will not reduce the settlement sufficiently, the designer may consider preloading the ground by constructing a higher, heavier bank to speed the primary settlement, and subsequently remove the extra fill height once 1,000 millimetres of settlement has occurred. The effect of this is shown in Figure 3.3 below.




Figure 3.3: Effect of Preloading (Example Only)

In this example of preloading for a 5-metre-high bank, 1,000 millimetres of settlement will occur in the first 30 days. If the bank is then reduced by 2 metres in height to the finished design height of 2 metres above original ground level (the base having settled 1 metre into the ground 3 metres of fill is needed to achieve the 2 metres height above original level), no further settlement can be expected over the next 25 years.

However, there will be a cost to achieve this which will need to be allowed for in the earthworks budget. Specifically, the cost of excavating from a borrow source, placing three metres of additional but temporary fill to the bank, then subsequently removing two metres of it and placing it elsewhere.

### 3.3 Tank Settlement

Like banks, tanks will settle on first construction following the primary and secondary pattern described above. In general the degree of settlement from a tank is expected to be less than that of a pond bank as it is a lighter structure.

However, differential settlement around the tank circumference and across the diameter needs to be assessed by the design engineer and consequential stress and strain on liner and tank components allowed for. Standard tank designs will generally cope with a predetermined level of deformation, but the likelihood of deformation beyond that needs to be assessed for the proposed site by the design engineer.

Where excessive settlement or deformation of the tank is likely, preloading the tank site and building the tank on an engineered fill platform is recommended.

### 3.4 Settlement During Use

Both ponds and tanks will experience further settlement on filling. Each time a pond or tank is filled, settlement will follow the primary/secondary pattern described above. The extent of settlement will be related to the depth/weight of effluent, how long the pond is filled, the size of the pond/tank, and the nature of the underlying peat. In general terms, the cyclic filling and emptying of the pond or tank will generate further settlement in a series of steps over the lifetime of the pond.

# 4.0 Ground Investigation, Depths and Methods

## 4.1 Scope of Investigation

In comparison to most other soil types, the properties of peat soils require a “step-up” in the level of ground investigation required. The key issues that need to be determined by a ground investigation on peat are:

- Peat thickness
- Peat strength
- Peat compressibility
- Groundwater level.

Before undertaking any ground investigation, a desktop study of available data should be completed to optimise the onsite ground investigation process.

This should include, but not be limited to:

- Inspection of published geological and soil maps
- Examination of any local water bore records (these are sometimes held by Regional Councils)
- Examination of published papers.

From this information the appropriate scope and depth of investigation can be determined.

A minimum of three exploratory holes is recommended, located evenly around the perimeter of the proposed tank or pond. This allows interpretation of ground conditions between exploratory holes and beneath the proposed tank or pond. Any variation in peat thickness and consistency across the site should be identified and any consequential risk of differential settlement considered

## 4.2 Depth of Investigation

Tanks and ponds impose loads on soils to a depth equivalent to the diameter of the tank, and width of the pond. As a minimum the investigation should therefore penetrate the full depth of the peat, or to twice the width of the proposed tank or pond embankment, whichever is the shallower.

Care is needed to ensure that the true base of the peat is reached. Many peat deposits are inter-layered with sand and silt soils which can be mistaken for the base of the peat deposit.

## 4.3 Methods

In very thin peat deposits of up to three metres, investigations by test pitting and field testing, supplemented by scala penetrometer and hand shear vane testing, may be sufficient (See also *Part 2 section 3 for investigation and testing*).

In thicker peat deposits the following methods of investigation should be undertaken.

### 4.3.1 CONE PENETROMETERS (CPT)

In thicker deposits, Cone Penetrometer Tests (CPT) and/or boreholes are needed to determine the peat properties over the depths of soil concerned.

Typically the CPT is carried out from a truck or track mounted rig (Figure 4.1). The CPT itself is a rod fitted with a cone tip that is pushed vertically into the ground at a constant rate. The penetration resistance encountered and the friction on the side of the cone is recorded by pressure and strain gauges fitted to the rods. By comparing the penetration resistance of the cone to the side friction, the soil type and soil strength can be determined continuously by depth. The results are presented as a series of graphs which aid their interpretation (Figure 4.2).

By using a cone fitted to the rod, water pressures are measured as it passes through the soil. The test can be stopped and the time taken for pore water pressure to fall to a background level determined. This is a 'pore water dissipation test' and the results can be used to aid assessment of the rate of settlement.

The CPT tests can be further supplemented by undertaking a limited number of hand shear vane tests in the upper one metre of the soil to aid assessment of the stronger soil crust.

Overall CPTs offer a cost effective means of assessing peat strength and compressibility, but as no samples are obtained, the speed and degree of settlement cannot be determined as accurately as by using samples obtained from a borehole.



Figure 4.1: Truck and Track-Mounted CPT Vehicles




Figure 4.2: CPT Results Showing Typical Raw Data for Thick Peat

### 4.3.2 BOREHOLES

Whilst CPT data can be used to estimate settlements, to fully define and obtain good estimates of likely settlements, in particular the rate of settlement, laboratory testing of soil samples is necessary. The best way to obtain these samples is from a borehole.

Boreholes allow core and tube samples to be obtained from depth that can then be tested for settlement properties in a soil testing laboratory. They allow visual inspection of the soil materials, an assessment of the fibre content and the selection of samples for testing, (Figure 4.3).

The primary soil laboratory test to determine settlement properties is an ‘oedometer consolidation test’. The results of these tests can be used directly to estimate the rate and degree of primary and secondary settlements on peat.

Moisture content and liquid limit tests can also be used to indirectly assess peat properties and aid interpretation of the oedometer and CPT test results.

The use of oedometer test data should give the design engineer a greater level of confidence in the assessment of peat properties than that based on data obtained from the CPT alone.

Oedometer tests are very important to gauge the rate of settlement and the timing of some key construction decisions such as installation of liners or if staged construction is necessary.

If staged construction is considered necessary the test results are then used to assess how much surcharge should be applied, and the timing of its removal.




Figure 4.3: Example of Thick Peat in a Borehole Core Sample Showing Variation with Depth

# 5.0 Design Process and Considerations

## 5.1 Cost and Risk Assessment

It is important to recognise that some degree of settlement of tanks and ponds on peat is inevitable, but that it can be reduced to manageable levels. Periodic future maintenance work related to settlement can be forecast, planned and budgeted for.

At the investigation phase, with each “step-up” from basic test pitting to CPTs, through to boreholes and laboratory testing, there is an increase in investigation cost but also an increase in the quality of the data obtained for use in design. The relationship between costs and risk is illustrated in Figure 5.1.




Figure 5.1: Ground Investigation Relative Cost and Risk Comparison

A discussion of “cost versus benefits” between the designer and farmer is essential during the investigation and design phases. This is to compare the cost of specific design and construction to mitigate settlement, against the cost of maintenance work that will be required over the life of the pond if this is not undertaken.

There is a wide range of possible variations in long-term maintenance costs. For example, annual topping up of pond embankments with associated adjustment of liners and pipework, once every five or even ten years. Maintenance costs can then be estimated and allowed for in the long-term farm business plan.

## 5.2 Design Process Steps

Following the field investigation and laboratory testing of soil samples, tank and pond designers need to finalise their designs using the following steps:

**Step 1:** From the information obtained from the ground investigation, designers need to calculate the bearing capacity of the peat, and compare that to the loading imposed by the proposed pond bank or tank.

If the peat cannot support the tank or pond without a shear failure occurring, the designer can assess possible remediation measures, including:

- Locating the pond or tank elsewhere
- Excavating out the peat
- Reducing the size of the pond or tank
- Including ground improvement measures such as “geogrid” or other proprietary products.

**Step 2:** If the peat has sufficient bearing capacity, or after the design has been modified to meet the site conditions, the designer needs to assess the rate and degree of settlement likely to occur and compare this to the acceptable levels of settlement the proposed pond or tank can tolerate. The options then available are:

- If the primary settlement phase is sufficiently rapid and the secondary phase settlement not excessive, it may be possible to install the pond or tank after the primary settlement is complete.
- If the time taken for primary settlement to be complete and/or the secondary settlement is excessive, look to take remedial actions such as:
  - Locating the pond elsewhere
  - Removing peat if possible
  - Preloading
  - Changing construction material. For example, considering light-weight fill or alternative liner type.

**Step 3:** Assess effects of settlement on ancillary works such pipes, pump locations and drainage:

- Settlement can cause disruption of pipes and a reduction in, or even reversal of, drainage pipe gradients. This could have serious effects on gravity feeds and drain effectiveness
- Pipe penetrations through liners may become areas of stress and deformation. They need to be minimised and preferably avoided
- Low points, including sumps, in ponds and tanks to which FDE falls can move and pump or intake/outfall locations may need relocation. Floating pumps may be a suitable alternative to avoid relocation. Alternatively, fixed pump locations with movable intake pipes may be adopted
- Gas mitigation and venting measures need to be installed beneath any flexible geomembrane liner. These need to be vented at high points around the edge of the pond and if crowning of the pond base is anticipated, additional central venting points should be considered
- The risk of gas collection beneath large diameter tanks should be assessed by the designer and mitigation measures included if necessary. This can comprise a central vent or permeable granular mat beneath the tank
- Surface water drainage around pond sides and tanks needs to be assessed. Settlement of the tank or pond may lead to the collection and ponding of surface water around it. Surface water channels and subsoil drains to cut off surface and subsoil water will generally be needed.

# 6.0 Summary

The following flow charts summarise the investigation, design and construction process for tanks and ponds on peat and supplement the process described in Part 1.




Figure 6.1: Flow Chart for Tanks on Peat




Figure 6.2: Flow Chart for Ponds on Peat

# 7.0 Acknowledgements

Figure 1: Figure 1, N B Hobbs, Mire Morphology and the Properties and Behaviour of Some British and Foreign Peats, Quarterly Journal of Engineering Geology, Vol 19, 1986.

Figure 3: Figure 3.1, N E Simons & B K Menzies, A Short Course in Foundation Engineering, Butterworths, 1977

Figure 6: Figure 1.2: Groundwater Control Design and Practice, CIRIA C515, 2000

Acknowledgement is given for figures from the above sources that have been modified for this document.



# REFERENCES



# References

## OVERVIEW

A selection of documents have been reviewed in preparing this Practice Note covering consenting, investigations, design, construction, and operation of FDE ponds.

This section provides a brief summary and links to relevant documents available.

## PART 1: DESIGN AND CONSTRUCTION PRINCIPLES

### Legislation

#### ***Building Act 2004 No 72***

[www.legislation.govt.nz/act/public/2004/0072/latest/dlm306036.html?search=ts\\_act\\_building+act\\_resel&p=1&sr=1](http://www.legislation.govt.nz/act/public/2004/0072/latest/dlm306036.html?search=ts_act_building+act_resel&p=1&sr=1)

#### ***Building Amendment Bill (No 4)***

[www.legislation.govt.nz/bill/government/2011/0322/latest/DLM3957236.html](http://www.legislation.govt.nz/bill/government/2011/0322/latest/DLM3957236.html)

#### ***Building (Dam Safety) Regulations 2008 (SR 2008/208)***

[www.legislation.govt.nz/regulation/public/2008/0208/latest/DLM1382001.html](http://www.legislation.govt.nz/regulation/public/2008/0208/latest/DLM1382001.html)

#### ***Health and Safety in Employment Act 1992 No 96***

[www.legislation.govt.nz/act/public/1992/0096/latest/DLM278829.html?search=ts\\_act\\_health+and+safety\\_resel&p=1&sr=1](http://www.legislation.govt.nz/act/public/1992/0096/latest/DLM278829.html?search=ts_act_health+and+safety_resel&p=1&sr=1)

#### ***Resource Management Act 1991 No 69***

[www.legislation.govt.nz/act/public/1991/0069/latest/DLM230265.html?search=ts\\_act\\_resource+management\\_resel&p=1&sr=1](http://www.legislation.govt.nz/act/public/1991/0069/latest/DLM230265.html?search=ts_act_resource+management_resel&p=1&sr=1)

### MANAGING FDE

#### **Environment Canterbury**

##### ***A Guide to Managing Farm Dairy Effluent***

This is a guide booklet produced by Dexcel and Environment Canterbury to provide advice to farmers. It covers all aspects of FDE management including storage ponds, and RMA issues for ponds.

[www.ecan.govt.nz/publications/plans/canterburyeffluentbooklet.pdf](http://www.ecan.govt.nz/publications/plans/canterburyeffluentbooklet.pdf)

#### **AgResearch**

##### ***Best Practice Management of Farm Dairy Effluent in the Manawatu-Wanganui Region***

This is a guide for FDE management to meet Horizons Regional Council's rules. There is no reference to dams or the BA.

[www.envirolink.govt.nz/pagefiles/376/421-hzlc43.pdf](http://www.envirolink.govt.nz/pagefiles/376/421-hzlc43.pdf)

## **Dairy Australia**

### ***Effluent and Manure Database for the Australian Dairy Industry***

This is a detailed and comprehensive code of all aspects of FDE management for Australian conditions. Aspects of sections 2.4 (pond site investigations, p56–60) and 2.35 (pond design and construction, p61–66) are relevant in New Zealand.

[www.dairyingfortomorrow.com/index.php?id=48](http://www.dairyingfortomorrow.com/index.php?id=48)

## **DairyNZ**

### ***Environment: Designing Or Upgrading Effluent Systems***

Dairy NZ offers a suite of effluent related guidance documents.

<http://resources.dairynz.co.nz/Resource/ListForDairyNZSite?pageid=2145869375>

### ***Farm Dairy Effluent (FDE) Design Code of Practice***

The purpose of this document is to guide designers through the process of developing an FDE system, from the initial site investigation through to commissioning of the final system. It provides a general design approach, including lists of things that must be taken into consideration.

### ***Farm Dairy Effluent (FDE) Design Standards***

The purpose of this document is to provide a set of standards against which to assess the design of individual FDE systems in New Zealand, and is intended to be used in conjunction with the FDE Design Practice Note.

### ***Farm Dairy Effluent (FDE) Pond Design and Construction***

A farmers guide to building a new effluent storage pond. This guide aims to help farmers through the process and various factors to consider when building a new effluent pond.

### ***Farm Dairy Effluent Systems: Planning the right system for your farm***

This booklet helps the principal ask the right questions to get the right advice and service and so will result in the most appropriate FDE system being installed.

### ***Farmfacts: Farm Infrastructure***

Guidance on other related farm infrastructure:

Tracks and races (8-1)

Feed pads - design and construction (8-2)

Feed pads - management and maintenance (8-3)

Stand-off pads - design and construction (8-4)

Stand-off pads - management and maintenance (8-5)

Covered pads and barns (8-6)

Road underpasses (8-7)

Building culverts and bridges (8-8)

## **POND DESIGN AND CONSTRUCTION**

### **Dairy NZ**

A tool to assist in calculation the working volumes and true dimensions of FDE ponds and tanks.

[www.dairynz.co.nz/page/pageid/2145866686?resourceId=748](http://www.dairynz.co.nz/page/pageid/2145866686?resourceId=748)

### **Environment Bay of Plenty**

The following document reviews the use of seepage collars in small dams and proposes adopting filter collars and discontinuing with seepage collars.

[www.boprc.govt.nz/media/33310/report-060900-reviewuseseseepagecollarsinsmalldams.pdf](http://www.boprc.govt.nz/media/33310/report-060900-reviewuseseseepagecollarsinsmalldams.pdf)

## **Environment Southland**

Environment Southland has a number of very useful documents available on their website.

[www.es.govt.nz/environment/farming/](http://www.es.govt.nz/environment/farming/)

### ***Code of Practice for Design and Construction of Agricultural Effluent Ponds***

A manual for pond owners and construction personnel specifically focused on pond construction.

[www.es.govt.nz/download.aspx?f=/media/8617/code-of-practice-for-design-and-construction-of-agricultural-effluent-ponds.pdf](http://www.es.govt.nz/download.aspx?f=/media/8617/code-of-practice-for-design-and-construction-of-agricultural-effluent-ponds.pdf)

### ***Design and Construction of Storage Ponds***

This two-page document is intended for contractors and farmer to explain the basics of storage pond design and construction.

[www.es.govt.nz/media/5899/design-and-construction-of-storage-ponds.pdf](http://www.es.govt.nz/media/5899/design-and-construction-of-storage-ponds.pdf)

## **Institution of Professional Engineers New Zealand**

### ***IPENZ Practice Note 08: Engineers and Ethical Obligations***

This Practice Note describes the ethical obligations engineers have to clients, other engineers, and the public.

[www.ipenz.org.nz/ipenz/forms/pdfs/pn08\\_ethical\\_obligations.pdf](http://www.ipenz.org.nz/ipenz/forms/pdfs/pn08_ethical_obligations.pdf)

### ***IPENZ/ACENZ Short Form Agreement for Consultant Engagement***

This is a recommended standard contract form between a consultant and a client, including model conditions of engagement. There is space to include scope and nature of services, programme for the services, fees and timing of payments, information or services to be provided by the client, and variations to the conditions of engagement.

[www.ipenz.org.nz/ipenz/practicesupport/endorsedinfo/](http://www.ipenz.org.nz/ipenz/practicesupport/endorsedinfo/)

### ***IPENZ/ACENZ Producer Statements***

[www.ipenz.org.nz/ipenz/practicesupport/endorsedinfo/](http://www.ipenz.org.nz/ipenz/practicesupport/endorsedinfo/)

### ***Construction Monitoring Services***

Five levels of construction monitoring service are defined with the decision as to which level is appropriate being project-dependent. Nominating a level at project commencement assists in providing an agreed understanding as to the expected level of monitoring for the principal and the engineer.

[www.ipenz.org.nz/ipenz/practicesupport/endorsedinfo/codes/](http://www.ipenz.org.nz/ipenz/practicesupport/endorsedinfo/codes/)

## **Ministry of Business, Innovation and Employment**

### ***Large Dams***

This describes the dam safety scheme and provides guidance for RAs and owners of large dams.

[www.dbh.govt.nz/dam-safety-scheme-navigating](http://www.dbh.govt.nz/dam-safety-scheme-navigating)

[www.dbh.govt.nz/userfiles/file/publications/building/building-act/dam-safety-scheme-guidance-for-regional-authorities-and-owners-of-large-dams.pdf](http://www.dbh.govt.nz/userfiles/file/publications/building/building-act/dam-safety-scheme-guidance-for-regional-authorities-and-owners-of-large-dams.pdf)

This web page provides details for the proposed amendments to the Dam Safety Scheme.

[www.dbh.govt.nz/ris-dam-safety-scheme](http://www.dbh.govt.nz/ris-dam-safety-scheme)

### ***Small Dams and the Building Code: Guidance for Regional Authorities, Contractors and Owners of Small Dams***

This assists owners of small dams in understanding how the construction of small dams relates to the *Building Code*. This document is an explanatory note on how you should consider the *Building Code* when building a (small) dam.

[www.dbh.govt.nz/small-dams-guidance](http://www.dbh.govt.nz/small-dams-guidance)

### ***Industrial Liquid Waste***

This is the compliance document for clause G14 of the *Building Code* relating to industrial liquid waste. It quotes the relevant clauses from the *Building Code* contained in the first schedule of the Building Regulations 2005. The document describes the requirements to be satisfied by specific design for systems used for the collection, storage, treatment, and disposal of industrial liquid waste.

[www.dbh.govt.nz/UserFiles/File/Publications/Building/Compliance-documents/G14-industrial-liquid-waste-2nd-edition-amendment-4.pdf](http://www.dbh.govt.nz/UserFiles/File/Publications/Building/Compliance-documents/G14-industrial-liquid-waste-2nd-edition-amendment-4.pdf)

### ***Safety from Falling***

The compliance document for the New Zealand Building Code for establishing compliance where Safety from Falling using barriers is contained in Clause F4 Safety from Falling – Third Edition (September 2007)

[www.dbh.govt.nz/UserFiles/File/Publications/Building/Compliance-documents/F4-safety-from-falling.pdf](http://www.dbh.govt.nz/UserFiles/File/Publications/Building/Compliance-documents/F4-safety-from-falling.pdf)

## **Nelson, KD**

### ***Design and Construction of Small Earth Dams***

Published by Inkata Press, Melbourne, ISBN 0 909605 34 3

## **New Zealand Geotechnical Society**

### ***Description of Soils and Rocks***

This is a guideline for the field classification and description of soil and rock for engineering purposes.

[www.nzgs.org/Publications/Guidelines/soil\\_and\\_rock.pdf](http://www.nzgs.org/Publications/Guidelines/soil_and_rock.pdf)

## **Otago Regional Council/New Zealand Contractors Federation**

### ***Design and Construction of Agricultural Effluent Ponds***

This document provides guidelines for contractors and design consultants, including details similar to the Environment Southland document. Close similarities include permeability limits and a definition of SQPs.

[www.orc.govt.nz/publications-and-reports/farming-and-land-management/dairy-farming/design-and-construction-of-agricultural-effluent-ponds/](http://www.orc.govt.nz/publications-and-reports/farming-and-land-management/dairy-farming/design-and-construction-of-agricultural-effluent-ponds/)

## **Standards New Zealand**

### ***NZS 3910:2003 (Conditions of Contract for Building and Civil Engineering Construction)***

This is the tried and proven form of contract for the design and construction of earthworks in New Zealand.

[www.standards.co.nz/webshop/?action=viewsearchproduct&mod=catalog&pid=3910%3a2003%28nzs%29&searchid=977833&searchorderingindex=1&searchsessionid=ee6f156425172e5418357e389418c376](http://www.standards.co.nz/webshop/?action=viewsearchproduct&mod=catalog&pid=3910%3a2003%28nzs%29&searchid=977833&searchorderingindex=1&searchsessionid=ee6f156425172e5418357e389418c376)

## **The New Zealand Society on Large Dams (NZSOLD)**

### ***Guidelines on Inspecting Small Dams***

These guidelines are intended to give a general overview of what to look for, and why, when inspecting a small dam.

[www.ipenz.org.nz/nzsold/guide001.pdf](http://www.ipenz.org.nz/nzsold/guide001.pdf)

## **United States Environmental Protection Agency (US EPA)**

### ***Designing and Installing Liners (Part IV Protecting Ground Water Chapter 7: Section B)***

These guidelines on designing and installing liners provide technical considerations for ponds and protecting groundwater from contamination and explores liners and leak detection systems.

[www.epa.gov/osw/nonhaz/industrial/guide/pdf/chap7b.pdf](http://www.epa.gov/osw/nonhaz/industrial/guide/pdf/chap7b.pdf)

## PART 2: CLAY LINERS FOR PONDS

### **Landfill Guidelines,**

Centre of Advanced Engineering. (2000).

Christchurch, New Zealand: University of Canterbury Centre for Advanced Engineering.

### **“Full-scale hydraulic performance of soil-bentonite and compacted lay liners” Hardy Lecture, Chapuis R, 2002, the 2000 R.M, Canadian Geotechnical Journal, Vol 39, pp 417 to 439.**

Waste Containment Facilities, Guidance for Construction, Quality Assurance and Quality Control of Liner and Cover Systems.

Daniel D.E. and Koerner R.M. (1995). New York, United States of America: American Society of Civil Engineers.

### **Guideline for Hand Held Shear Vane Test**

New Zealand Geotechnical Society (2001)

[www.nzgs.org/Publications/Guidelines/shear\\_vane\\_guidelines.pdf](http://www.nzgs.org/Publications/Guidelines/shear_vane_guidelines.pdf)

### **Soil Mechanics in Engineering Practice, 3rd Edition.**

Terzaghi K, Peck R.B. and Mesri G. (1996). New York, United States of America: John Wiley & Sons.

### **Geotechnical Engineering in Residual Soils.**

Wesley. (2010). Hoboken New Jersey, United States of America: John Wiley & Sons.

## PART 3: GEOMEMBRANE (SYNTHETIC LINER) SELECTION

### **United States Department of Agriculture (USDA),**

#### **Pond Sealing or Lining Compacted Clay Treatment, Code 521D, September 2010, Natural Resources Conservation Service, Conservation Practice Standard**

[http://www.nrcs.usda.gov/Internet/FSE\\_DOCUMENTS/stelprdb1046899.pdf](http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/stelprdb1046899.pdf)

### **United States Environmental Protection Agency (US EPA)**

#### **United States Environmental Protection Agency (US EPA) Part IV Protecting Ground Water, Chapter 7: Section B,**

Designing and Installing Liners, Technical Considerations for New Surface Impoundments, Landfills, and Waste Piles.

<http://www.epa.gov/osw/nonhaz/industrial/guide/pdf/chap7b.pdf>

### **Geosynthetic Institute**

#### **GRI Specifications**

<http://www.geosynthetic-institute.org/specifications.htm>

#### **A Guide to Polymeric Geomembranes, a Practical Approach, Wiley Series in Polymer Science, Scheirs, John**

<http://www.wiley-vch.de/publish/en/AreaOfInterestCE00/availableTitles/0-470-51920-7/>



# APPENDICES



## Appendix A – IPENZ SHORT FORM AGREEMENT

### Short Form Agreement for Consultant Engagement

**Between:**

.....  
(Client)

**and:**

.....  
(Consultant)

Collectively referred to herein as the "Parties" and individually as a "Party"

**Project:**

**Location:**

**Scope & nature of the Services:**

**Programme for the Services:**

**Fees & timing of payments:**

**Information or services to be provided by the Client:**

The Client engages the Consultant to provide the Services described above and the Consultant agrees to perform the Services for the remuneration provided above. Both Parties agree to be bound by the provision of the Short Form Model Conditions of Engagement (overleaf), including clauses 2, 3, 9 and 10 and any variations noted below. Once signed, this agreement, together with the conditions overleaf and any attachments, will replace all or any oral agreement previously reached between the Parties.

**Variations to the Short Form Model Conditions of Engagement (overleaf):**

**Client authorised signatory (ies):**

**Consultant authorised signatory (ies):**

**Print name:**

**Print name:**

**Date:**

**Date:**

## SHORT FORM MODEL CONDITIONS OF ENGAGEMENT

1. The Consultant shall perform the Services as described in the attached documents.
2. Nothing in this Agreement shall restrict, negate, modify or limit any of the Client's rights under the Consumer Guarantees Act 1993 where the Services acquired are of a kind ordinarily acquired for personal, domestic or household use or consumption and the Client is not acquiring the Services for the purpose of a business.
3. The Client and the Consultant agree that where all, or any of, the Services are acquired for the purposes of a business the provisions of the Consumer Guarantees Act 1993 are excluded in relation to those Services.
4. In providing the Services the Consultant shall exercise the degree of skill, care and diligence normally expected of a competent professional.
5. The Client shall provide to the Consultant, free of cost, as soon as practicable following any request for information, all information in his or her power to obtain which may relate to the Services. The Consultant shall not, without the Client's prior consent, use information provided by the Client for purposes unrelated to the Services. In providing the information to the Consultant, the Client shall ensure compliance with the Copyright Act 1994 and shall identify any proprietary rights that any other person may have in any information provided.
6. The Client may order variations to the Services in writing or may request the Consultant to submit proposals for variation to the Services. Where the Consultant considers a direction from the Client or any other circumstance is a Variation the Consultant shall notify the Client as soon as practicable.
7. The Client shall pay the Consultant for the Services the fees and expenses at the times and in the manner set out in the attached documents. Where this Agreement has been entered by an agent (or a person purporting to act as agent) on behalf of the Client, the agent and Client shall be jointly and severally liable for payment of all fees and expenses due to the Consultant under this Agreement.
8. All amounts payable by the Client shall be paid within twenty (20) working days of the relevant invoice being mailed to the Client. Late payment shall constitute a default, and the Client shall pay default interest on overdue amounts from the date payment falls due to the date of payment at the rate of the Consultant's overdraft rate plus 2% and in addition the costs of any actions taken by the Consultant to recover the debt.
9. Where Services are carried out on a time charge basis, the Consultant may purchase such incidental goods and/or Services as are reasonably required for the Consultant to perform the Services. The cost of obtaining such incidental goods and/or Services shall be payable by the Client. The Consultant shall maintain records which clearly identify time and expenses incurred.
10. Where the Consultant breaches this Agreement, the Consultant is liable to the Client for reasonably foreseeable claims, damages, liabilities), losses or expenses caused directly by the breach. The Consultant shall not be liable to the Client under this Agreement for the Client's indirect, consequential or special loss, or loss of profit, however arising, whether under contract, in tort or otherwise.
11. The maximum aggregate amount payable, whether in contract, tort or otherwise, in relation to claims, damages, liabilities, losses or expenses, shall be five times the fee (exclusive of GST and disbursements) with a maximum limit of \$NZ500,000.
12. Without limiting any defences a Party may have under the Limitation Act 2010, neither Party shall be considered liable for any loss or damage resulting from any occurrence unless a claim is formally made on a Party within 6 years from completion of the Services.
13. The Consultant shall take out and maintain for the duration of the Services a policy of Professional Indemnity insurance for the amount of liability under clause 11. The Consultant undertakes to use all reasonable endeavours to maintain a similar policy of insurance for six years after the completion of the Services.
14. If either Party is found liable to the other (whether in contract, tort or otherwise), and the claiming Party and/or a Third Party has contributed to the loss or damage, the liable Party shall only be liable to the proportional extent of its own contribution.
15. Intellectual property prepared or created by the Consultant in carrying out the Services ("New Intellectual Property") shall be jointly owned by the Client and the Consultant. The Client and Consultant hereby grant to the other an unrestricted royalty-free license in perpetuity to copy or use New intellectual Property. Intellectual property owned by a Party prior to the commencement of this Agreement and intellectual property created by a Party independently of this Agreement remains the property of that Party. The ownership of data and factual information collected by the Consultant and paid for by the Client shall, after payment by the Client, lie with the Client. The Consultant does not warrant the suitability of New Intellectual Property for any purpose other than the Services or any other use stated in the Agreement.
16. The Consultant has not and will not assume any obligation as the Client's Agent or otherwise which may be imposed upon the Client from time to time pursuant to the Health and Safety in Employment Act 1992 ("the Act") arising out of this engagement. The Consultant and Client agree that in terms of the Act, the Consultant will not be the person who controls the place of work.
17. The Client may suspend all or part of the Services by notice to the Consultant who shall immediately make arrangements to stop the Services and minimise further expenditure. The Client and the Consultant may (in the event the other Party is in material default) terminate the Agreement by notice to the other Party. Suspension or termination shall not prejudice or affect the accrued rights or claims and liabilities of the Parties.
18. The Parties shall attempt in good faith to settle any dispute by mediation.
19. This Agreement is governed by the New Zealand law, the New Zealand courts have jurisdiction in respect of this Agreement, and all amounts are payable in New Zealand dollars.

# Appendix B1 – FORM OF PRODUCER STATEMENT FOR: DESIGN OF FARM DAIRY EFFLUENT PONDS

ISSUED BY \_\_\_\_\_ (Design Firm)

TO \_\_\_\_\_ (Owner/Developer)

TO BE SUPPLIED TO \_\_\_\_\_ (Consent Authority)

IN RESPECT OF \_\_\_\_\_ (Description of Works)

\_\_\_\_\_  
\_\_\_\_\_

AT \_\_\_\_\_ (Address)

\_\_\_\_\_  
\_\_\_\_\_

\_\_\_\_\_ (Design Firm) has been engaged by

\_\_\_\_\_ (Principal)

to provide the following design services: \_\_\_\_\_

\_\_\_\_\_

I (Suitably Qualified Person), a duly authorised representative of \_\_\_\_\_

\_\_\_\_\_ (Design Firm)

\_\_\_\_\_ (Qualifications)

CPEng

ETPract

IPENZ Member No

believe on reasonable grounds that the pond(s) when constructed in accordance with the drawings, specifications, and other documents provided or listed, will comply with the relevant codes and rules stated below.

IPENZ Practice Note 21: Code of Practice for the Design and Construction of Farm Dairy Effluent Ponds

\_\_\_\_\_ (Relevant Codes and Rules)

\_\_\_\_\_ (Signature of Authorised Representative)

\_\_\_\_\_ (Date)

# Appendix B2 – FORM OF PRODUCER STATEMENT FOR: CONSTRUCTION REVIEW OF FARM DAIRY EFFLUENT PONDS

**ISSUED BY** \_\_\_\_\_ (Construction Review Firm)

**TO** \_\_\_\_\_ (Owner/Developer)

**TO BE SUPPLIED TO** \_\_\_\_\_ (Consent Authority)

**IN RESPECT OF** \_\_\_\_\_ (Description of Contract Works)

**AT** \_\_\_\_\_ (Address)

\_\_\_\_\_ (Design Firm)

has been engaged by \_\_\_\_\_ (Principal)

to carry out construction monitoring in accordance with Conditions(s) \_\_\_\_\_

of Council decision on Resource Consent Application \_\_\_\_\_

I (Suitably Qualified Person), \_\_\_\_\_ a duly authorised representative of

\_\_\_\_\_ (Design Firm)

\_\_\_\_\_ (Qualifications)

CPEng

ETPract

IPENZ Member No.

believe on reasonable grounds that the pond structure(s) when constructed in accordance with the drawings, specifications, and other documents provided or listed, will comply with the relevant codes and rules stated below.

All  part only, of the building works has been completed in accordance with the relevant consents.

IPENZ Practice Note 21: Code of Practice for the Design and Construction of Farm Dairy Effluent Ponds

\_\_\_\_\_ (Signature of Authorised Representative)

\_\_\_\_\_ (Date)

\_\_\_\_\_ (Address)

\_\_\_\_\_

## Appendix B3 – FORM OF PRODUCER STATEMENT FOR: CONSTRUCTION OF FARM DAIRY EFFLUENT PONDS

**ISSUED BY** \_\_\_\_\_ (Contractor)

**TO** \_\_\_\_\_ (Owner/Developer)

**IN RESPECT OF** \_\_\_\_\_ (Description of Contract Works)

**AT** \_\_\_\_\_ (Address)

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

has contracted to \_\_\_\_\_ (Contractor)

\_\_\_\_\_ (Owner/Developer)

To carry out and complete works in accordance with a contract, titled \_\_\_\_\_

\_\_\_\_\_ (Project)

\_\_\_\_\_ (“the contract”)

I \_\_\_\_\_ a duly authorised representative of

\_\_\_\_\_ (Duly Authorised Agent)

\_\_\_\_\_ (Contractor)

believe on reasonable grounds that \_\_\_\_\_ has carried out and completed

\_\_\_\_\_ (Contractor)

All  Part only, as specified in the attached particulars of the works in accordance with the contract.

\_\_\_\_\_ (Signature of Authorised Agent on behalf of)

\_\_\_\_\_ (Date)

\_\_\_\_\_ (Contractor)

\_\_\_\_\_ (Address)

## Appendix C – REGULATORY CHECKLIST

### Regional Council – RMA

#### *Preliminary*

- Which region?
- What regional plans? There may be more than one that is applicable.
- Identify driver for pond requirement. Is it as a condition of Resource Consent? Is it to meet a standard for a Permitted Activity? Is it for some other reason? List standards, conditions, requirements.

#### *Specifics*

- Is the volume requirement specified in a plan or consent?
- Are separations specified? Check distances to water bodies, bores, wetlands.
- Is the permeability limit specified in the plan or consent?
- Can the pond be installed without diversion of any watercourse?
- Can pond be installed without breaching an RC earthworks consenting requirement?
- Can the above criteria be met, or is there a need to go back to the RC for further consenting?  
If so, ensure any conditions are met.
- Identify certification requirements; this will frequently include permeability.
- Undertake certification as required. Note: contractors fitting synthetic pond liners can be required to certify the permeability of the installed liner.

### District Council – RMA

#### *Preliminary*

- Which district?
- What district plans? There may be more than one that is applicable.

#### *Specifics*

- Is construction and ongoing operation of an FDE pond a Permitted Activity?
- Does the plan provide performance standards for effluent ponds as Permitted Activities?
- Are separations specified? Check distances to roads, boundaries, houses, residential zones, marae.
- Are there limitations on the earthworks' depth, volume, or timing?
- Can Permitted Activity criteria/performance standards be met, or is there a need to go back to the DC for consenting? If so, ensure any conditions are met.
- Identify certification requirements; these will frequently involve stability of earthworks.
- Undertake certification as required.

## Regional Council Requirements for Effluent Ponds

REGION	EFFLUENT DISCHARGE TO WATER	EFFLUENT DISCHARGE TO LAND	EFFLUENT POND SIZE	SEEPAGE/ PERMEABILITY
<b>Northland</b>	Yes*	Permitted	Recommend design criteria from Dairy and Environment Committee (DEC) manual (NRC can calculate this for you)	No more than minor contamination of groundwater by seepage
<b>Auckland</b>	Yes*	Permitted	Not specified but recommend use of DESC**	Ponds must be well constructed and sealed to prevent contamination of groundwater
<b>Waikato</b>	Yes*	Permitted	Not specified but strongly recommend use of an accredited designer to calculate the pond size using DESC**	10 <sup>-9</sup> m/s
<b>Bay of Plenty</b>	Yes*	Controlled	Recommend use of DESC**	Both renewal and new consents within the Rotorua Lakes catchment require ponds to be sealed to Pond Construction Practice Note standard. It is strongly advised that all new ponds are built to this standard.
<b>Taranaki</b>	Yes*	Controlled	Not specified for storage ponds	Not specified, but ponds must be sealed
<b>Horizons</b>	No	Controlled	According to DESC**	Recommend that all effluent construction follows IPENZ PN21. Future discharge consents in the region will require this via a consent condition.
<b>Hawke's Bay</b>	No	Controlled; discretionary in sensitive catchments	Recommend use of DESC**	10 <sup>-9</sup> m/s
<b>Wellington</b>	No	Controlled	Not specified but recommend use of DESC**	Seepage to be imperceptible

REGION	EFFLUENT DISCHARGE TO WATER	EFFLUENT DISCHARGE TO LAND	EFFLUENT POND SIZE	SEEPAGE/ PERMEABILITY
<b>Tasman District</b>	Yes*	Permitted	Recommend use of DESC**	Any new/modified ponds have to be shown to meet the sealing standards of PN21
<b>Marlborough District</b>	No	Permitted excluding the Wairau/ Awatere catchment (Controlled)	Not specified	Not specified
<b>West Coast</b>	Yes*	Permitted	Effluent treatment– specified on a per number of cows basis.  For storage purposes – a minimum of 30 days is required	Can apply for a resource consent for seepage to groundwater providing special conditions are met
<b>Canterbury</b>	No	Controlled	Must demonstrate adequacy, recommend use of the DESC**	Seepage rate: $10^{-8}$ m/s (1 mm/d)
<b>Otago</b>	No	Permitted	Not specified	Storage system sealed to prevent seepage
<b>Southland</b>	No	Controlled	Recommend use of DESC**	Plans and specifications containing the information describing the proposed design and construction process to avoid adverse effects on water quality

\* with consent

\*\* DESC Dairy Effluent Storage Calculator

Note: this table is indicative rather than definitive and subject to change. In all instances, the rules of the relevant regional/district council should be consulted directly.

## **Building Act**

### ***Does the pond involve a dam?***

- If the fluid level in the pond will rise above the level of the surrounding land, then a dam is involved, and the RC is the administering authority.
- If the dam is greater than three metres high, and impounds more than 20,000 m<sup>3</sup> of fluid (that is, it is a large dam), then a Building Consent will be required; an application should be prepared and lodged with the RC. The design and construction will need to comply with the approved plans and Building Consent conditions, verified by certification.
- If the dam is lower than three metres or it impounds less than 20,000 m<sup>3</sup> of fluid, then a Building Consent from the RC is not required, but the dam must be designed and constructed in compliance with *Building Code* requirements, and verified by certification.

### ***What if the pond does not involve a dam?***

- If the fluid level in the pond will not rise above the level of the surrounding land, then a dam is not involved and the DC is the administering authority.
- Check with the building inspector whether the walls of the pond will be considered to be a retaining wall, and whether a Building Consent will be required. The three-metre height exemption for a retaining wall in a rural zone and designed by a CPEng should excuse most ponds from a Building Consent requirement.
- If consent is required, an application should be prepared and lodged with the DC. The design and construction will need to comply with the Building Consent conditions, and verified by certification.
- If consent is not required, the walls of the pond should still be designed and constructed in compliance with the *Building Code* standards, and verified by certification.

## **Historic Places Act**

- Has the district plan been checked as to whether the proposed works may affect known heritage or archaeological sites?
- Are there archaeological discovery protocols in place?

## Appendix D – POND CERTIFICATION CHECKLIST

The following items detail the recommended test and inspection items for an SQP to be able to certify a FDE pond.

### 1.1 TESTING AT CONSTRUCTION COMPLETION

For earthen embankment ponds:

- Bunds compacted sufficiently, as confirmed by testing
- All unsuitable *in situ* material removed during construction
- Correct finished levels at top of bunds and base of pond.

Engineer to certify for clay-lined ponds:

- Suitable clay was used and provide all test results
- Compaction was adequate to satisfy seepage rate requirements of plan or consent
- Thickness of clay liner used
- Depth of pond base to groundwater
- The pond will meet the seepage requirements of the plan or consent.

### 1.2 GEOMEMBRANES (SYNTHETIC LINERS)

When geomembranes are used, certification should include:

- Visual check of integrity of liner
- The type of liner used and whether it meets plan or consent requirements
- Area has been rolled and surface properly prepared
- Anchor trench correctly constructed and compacted
- Welding/joining test records by suitably trained person (including destructive testing) provided.

Where a liner installer has been used to place the liner, they should be requested to certify and provide a guarantee against leakage and that a minimum permeability standard has been met.



## DISCLAIMER

DairyNZ Limited (“DairyNZ”, “we”, “our”) and the Institution of Professional Engineers New Zealand (IPENZ) endeavour to ensure the information in this Practice Note is accurate and current. However we do not accept liability for any error or omission, nor can we be held responsible for its accuracy, currency, or fitness for purpose as best practice is subject to change without notice.

The information in this Practice Note is intended to provide the best possible advice DairyNZ and IPENZ have access to. It is important to note the information is provided as general guidance only and is not intended as a substitute for specific advice. Practices, systems, and advice may vary depending on the individual circumstances. The information may also be subject to change at any time without notice. DairyNZ and IPENZ take no responsibility whatsoever for the currency and/or accuracy of this information, its completeness, or fitness for purpose.

## COPYRIGHT

Copyright in this publication (including text, graphics, logos, and icons) is owned or licensed to DairyNZ.

Other than for the purposes of, and subject to the conditions prescribed under, the Copyright Act 1994 and similar legislation which applies in your location, and except as expressly authorised by these terms and conditions, you may not in any form or by any means adapt, reproduce, store, distribute, print, display, perform, publish, or create derivative works from any part of this publication or commercialise any information, products, or services obtained from any part of this publication without our written permission.



To facilitate the delivery of this Practice Note, DairyNZ as sponsor have engaged Opus International Consultants Ltd as the lead consultant.

<b>Editor/Lead Author:</b>	<b>Other Contributing Authors (Parts 2 and 4):</b>	
Rex Corlett	David Dennison	Ken Read
Principal Infrastructure Engineer	Principal Geotechnical Engineer	Senior Engineering Geologist
Invercargill, NZ	Hamilton, NZ	Hamilton, NZ

© DairyNZ 2013



The Institution of Professional Engineers New Zealand Inc.  
*Pūtahi Kaiwetepanga Ngaio o Aotearoa*

PO Box 12 241, Wellington 6144, New Zealand  
**E** [ipenz@ipenz.org.nz](mailto:ipenz@ipenz.org.nz)      **W** [www.ipenz.org.nz](http://www.ipenz.org.nz)